

All-Phase Environmental Consultants, Inc.

**SHORT TERM RADON INSPECTION
REPORT
FOR**



**Pueblo City Schools
(aka. Pueblo School District No. 60)
315 W 11th St, Pueblo, CO 81003
(719) 549-7100**

PROJECT NO. 19-3518

Report By:
All-Phase Environmental Consultants Inc.
701 W. 9th Street
Pueblo, Colorado 81003
Ph. (719) 545-0375
Cell (719) 406-3688
E-mail: Joey@allphaseenvironmental.com
Visit us at www.all-phaseenvironmental.com

I. Introduction

Starting on April 6, 2019 and concluding on June 10, 2019 Joseph Cardenas & Richard L. Ralston, of All-Phase Environmental Consultants Inc. (APEC) performed Short-Term Radon Testing for campuses owned and operated by Pueblo City Schools Also Known As Pueblo School District 60 . The testing of these properties was conducted to determine if elevated levels of radon were detected in areas where students & staff spend the majority of their time. The data received from the samples will be used to determine if Pueblo City Schools will need to conduct further investigations, such as follow-up long-term testing and/or perform mitigation activities on these campuses. APEC set test kits in 1st floor areas including classrooms, gymnasiums, cafeterias, etc. The sample areas, time set, date and serial number of each kit was logged on a spreadsheet, later used as the Chain of Custody (COC). The test kits remained in each testing location for a period minimum of 48 hours but not to exceed 96 hours. Once retrieved the test kit serial number was verified and time and date were logged for the pickup. Test kits and the COC were then shipped priority overnight to the laboratory Air Chek in North Carolina for analysis.

II. Radon in Schools – EPA Information

The Consumer Protection Division (CPD) of the Colorado Department of Public Health and Environment (CDPHE) regulates radon in schools under 6 CCR 1010-6, (10-102). The regulation, adopted in 1991, requires schools to test for radon by March 1, 1991 and keep test results on file at each school for public inspection. New and remodeled schools must test within 19 months of occupancy. Schools must notify CDPHE of remodeling so the department can assess the need for additional radon testing. Schools are not required to share test results with the department. There is no authority to require mitigation, nor is there enforcement authority for schools that do not test. Schools are not required to report the results to teachers or parents. The U.S. Environmental Protection Agency (EPA) does not require radon testing in schools. Most states do not require radon testing in schools. EPA's investigations of radon in schools were initiated in 1988 with a study of schools in Fairfax County, Virginia. Findings from that study were used to develop the Radon Measurement in Schools - An Interim Report (EPA 520/1-89- 010). Schools have been using this document as an interim guide for measuring radon in schools. In 1989 and 1990, EPA conducted the School Protocol Development Study, a nationwide effort to further examine how best to conduct radon measurements in schools. Results from this study have been used to improve the procedures for testing radon in schools and are incorporated into this document. The results of this study also suggested that elevated radon levels (levels ≥ 4 pCi/L) may exist in at least some schools in every state. Although most elevated measurements in this study were slightly greater than 4 pCi/L, several schools were found with levels well over 20 pCi/L while some have been found with concentrations over 100 pCi/L.

About Radon

Radon is a naturally occurring radioactive gas. It comes from the natural breakdown (decay) of uranium which is found in soil and rock all over the United States. Radon travels through soil and enters buildings through cracks and other holes in the foundation. Eventually, it decays into radioactive particles (decay products) that can become trapped in your lungs when you breathe. As these particles in turn decay, they release small bursts of radiation. This radiation can damage lung tissue and lead to lung cancer over the course of your lifetime. EPA studies have found that radon concentrations in outdoor air average about 0.4 pCi/L. However, radon and its decay products can accumulate too much higher concentrations inside a building.

Radon is colorless, odorless, and tasteless. The only way to know whether or not an elevated level of radon is present in any room of a school is to test. Each frequently occupied room that is in contact with the ground should be measured because adjacent rooms can have significantly different levels of radon.

III. Short Term Radon Testing Procedures**A. Schools and Buildings Tested – Pueblo City Schools District #60**

1. Administration building
2. Baca Elementary school
3. Belmont Elementary School
4. Bessemer Academy
5. Beulah Heights Elementary School
6. Bradford Elementary School
7. Bus Barn
8. Carlile Elementary School
9. Caesar Chavez Elementary
10. Centennial High School
11. Central High School
12. Columbian Elementary
13. Corwin International Magnet School
14. Data Center
15. East High School
16. Fountain International
17. Franklin Elementary School
18. Fulton Heights Campus (PSAS)
19. Goodnight Elementary School
20. Haaff Elementary School
21. Heaton Middle School
22. Heritage Elementary School
23. Highland Park Elementary
24. Irving Elementary School

25. Minnequa Elementary School
26. Morton Elementary School
27. Paragon School
28. Parkview Elementary School
29. Pitts Middle School
30. Pueblo School for Arts and Science
31. Riskey Middle School
32. Roncalli Middle School
33. Service Center
34. South High School
35. South Park Elementary School
36. Sunset park Elementary School

B. Placement of Radon Canisters

There are two general ways to test for radon:

1. **Short Term Tests:** A short-term test is the quickest way to test for radon. In this test, the testing device remains in an area (e.g., schoolroom) for a period of 2 to 90 days depending on the device. Because radon levels tend to vary from day to day and from season to season, a short-term test is less likely than a long-term test to give an average radon level for a school year.

Short-term measurements are most often made with activated charcoal devices, alpha track detectors, electret-ion chambers, continuous monitors, and charcoal liquid scintillation detectors. Alpha track detectors and electret-ion chambers are used for long-term tests. Some general information about radon detectors is given in Appendix D. More detailed information can be found in the document entitled Indoor Radon and Radon Decay Product Measurement Device Protocols (EPA-402-R-92-004). In order to assure adequate test results, only devices that are used for a measurement period of at least 48 continuous hours should be used when testing for radon in school buildings.

Of the short-term tests, a 90-day test may provide a more representative picture of the average school year radon level in a schoolroom than 2 to 5-day tests. Long term tests are able to integrate fluctuations of radon concentrations with time. For example, while a 2-day radon measurement might be made during a period of higher than usual radon levels, a 90-day measurement will allow such highs, if they are occurring, to be balanced by periods of moderate or low radon concentrations. Alternatively, 2 to 5-day tests indicate the radon level for a shorter period of testing during which radon levels may have been somewhat higher or lower than the school year average. However, EPA research suggests that, on average, these

measurements are more likely to reflect the average radon level for a 3-month or longer period when testing is conducted in the coldest months of the year when closed conditions are more likely to be present.

2. **Long-Term Tests** - A long-term test remains in place for more than 90 days. A long-term test (e.g., a test conducted over the school year) will give a result that is more likely to represent the school year average radon level in a schoolroom than a short-term test.

Specific Requirements for Placement of Radon Detectors:

- Do not place detectors near drafts resulting from heating, ventilating vents, air conditioning vents, fans, doors, and windows.
- Place detectors where they are least likely to be disturbed or covered up.
- Do not place detectors in direct sunlight or in areas of high humidity.
- Place detectors at least approximately 50 centimeters (20 inches), from the floor and 10 centimeters (4 inches) from other objects and away from the exterior walls of the building.
- Place detectors about every 2,000 square feet for large spaces.
- Do not disturb the test device at any time during the test.

C. Laboratory Information and Chain of Custody Procedures

Every field sheet is entered into a Chain of Custody, an excel Spreadsheet provided by the lab. The serial number of each kit, the start and finish times and dates, room temperature, the room location and the school or building name are all entered on the spreadsheet. After the Chain of Custody was completed and verified it was emailed to the lab at info@radon.com to start the analysis of the kits. The short term samples were delivered for analysis to:

Air Check
Radon Lab
1936 Butler Bridge Rd
Mills River, NC 28759-3892

Generally speaking, about 0.4 pCi/L of radon is found naturally occurring in the outside air and the average indoor radon level is normally about 1.3 pCi/L. The EPA recommends that mitigation techniques be implemented to reduce indoor radon if levels are above 4 pCi/L. Radon levels can usually be lowered to a safe level using a process called radon mitigation, which typically consists of a sub-slab vapor extraction system. Some radon mitigation methods prevent radon from entering the structure while others reduce radon levels after the gas is present.

Laboratory Results – Above 4 pCi/L**Table 1: Field Data & Lab Results for samples above 4 pCi/L:**

Sample ID	School	Room	Start Time	Start Date	End Time	End Date	Results pCi/L
9220301	Highland park	2-18	3:00pm	5-8-2019	4:00pm	5-10-2019	5.6
9220302	Highland park	2-16	3:00pm	5-8-2019	4:00pm	5-10-2019	4.6
9220303	Highland Park	2-14	3:00pm	5-8-2019	4:00pm	5-10-2019	4.8
9220304	Highland Park	2-14	3:00pm	5-8-2019	4:00pm	5-10-2019	6.0
9220305	Highland Park	1-17	3:00pm	5-8-2019	4:00pm	5-10-2019	4.7
9220306	Highland Park	1-13	3:00pm	5-8-2019	4:00pm	5-10-2019	4.6
9220307	Highland Park	1-15	3:00pm	5-8-2019	4:00pm	5-10-2019	5.3
9220308	Highland Park	1-11	3:00pm	5-8-2019	4:00pm	5-10-2019	5.2
9220309	Highland Park	1-10	3:00pm	5-8-2019	4:00pm	5-10-2019	5.3
9220310	Highland Park	1-01	3:00pm	5-8-2019	4:00pm	5-10-2019	5.9
9220311	Highland Park	1-01	3:00pm	5-8-2019	4:00pm	5-10-2019	5.8
9220313	Highland Park	1-09	3:00pm	5-8-2019	4:00pm	5-10-2019	4.7
9220573	Highland Park	Cafeteria	3:00pm	5-8-2019	4:00pm	5-10-2019	6.6
9220577	Highland Park	Cafeteria	3:00pm	5-8-2019	4:00pm	5-10-2019	7.7
9220578	Highland Park	Gym	3:00pm	5-8-2019	4:00pm	5-10-2019	4.9
9220580	Highland Park	4-26	3:00pm	5-8-2019	4:00pm	5-10-2019	4.6
9220581	Highland Park	5-29	3:00pm	5-8-2019	4:00pm	5-10-2019	4.0
9220582	Highland Park	Gym	3:00pm	5-8-2019	4:00pm	5-10-2019	5.0
9220583	Highland Park	4-23	3:00pm	5-8-2019	4:00pm	5-10-2019	5.1
9220584	Highland Park	4-25	3:00pm	5-8-2019	4:00pm	5-10-2019	5.1
9220587	Highland Park	Spec Ed	3:00pm	5-8-2019	4:00pm	5-10-2019	4.4
9220591	Highland Park	5-28	3:00pm	5-8-2019	4:00pm	5-10-2019	4.8
9220592	Highland Park	5-30	3:00pm	5-8-2019	4:00pm	5-10-2019	6.8
9220598	Highland Park	20	3:00pm	5-8-2019	4:00pm	5-10-2019	4.2
9220599	Highland Park	5-27	3:00pm	5-8-2019	4:00pm	5-10-2019	4.3
9220600	Highland Park	22	3:00pm	5-8-2019	4:00pm	5-10-2019	4.4

Sample ID	School	Room	Start Time	Start Date	End Time	End Date	Results pCi/L
9220328	South Park	20	2:00pm	5-10-2019	4:00pm	5-13-2019	4.7
9220335	South Park	19	2:00pm	5-10-2019	4:00pm	5-13-2019	4.4
9220340	South Park	21	2:00pm	5-10-2019	4:00pm	5-13-2019	5.7
9220341	South Park	16	2:00pm	5-10-2019	4:00pm	5-13-2019	4.1
9220342	South Park	17	2:00pm	5-10-2019	4:00pm	5-13-2019	4.3
9220343	South Park	15	2:00pm	5-10-2019	4:00pm	5-13-2019	4.7
9220345	South Park	11	2:00pm	5-10-2019	4:00pm	5-13-2019	5.1
9220346	South Park	9	2:00pm	5-10-2019	4:00pm	5-13-2019	4.3
9220347	South Park	12	2:00pm	5-10-2019	4:00pm	5-13-2019	4.1
9220348	South Park	13	2:00pm	5-10-2019	4:00pm	5-13-2019	4.2
Sample ID	School	Room	Start Time	Start Date	End Time	End Date	Results pCi/L
9209993	Administration	20C	2:00	4-29-2019	3:00	5-1-2019	8.6
9209996	Administration	12	2:00	4-29-2019	3:00	5-1-2019	4.2
9209997	Administration	21	2:00	4-29-2019	3:00	5-1-2019	4.1
9209998	Administration	20C	2:00	4-29-2019	3:00	5-1-2019	8.2
9210000	Administration	1	2:00	4-29-2019	3:00	5-1-2019	4.1

IV. Conclusions and Recommendations for Further Action(s)

The results received via email from the laboratory, by APEC indicate that the aforementioned classrooms in the specific schools, exceed the EPA's recommended action level of 4 pCi/L. It is recommended that follow-up long term testing be conducted in the fall/winter months of the 2019/2020 school year. Long term testing is over a 3 month period using test kits in the same classrooms and locations where the previous short term kits were placed. The long term kits will be set using the same set up and removal procedures as the short term kits and utilize the same type of field sheet to ensure the accuracy of the test being conducted. The only difference being that the test kits will remain in place for a period of at least 90 days and preferably when the HVAC system and "normal" conditions are experienced.

In addition to initial and follow-up measurements, EPA recommends that schools retest sometime in the future especially after significant changes to the building structure or the HVAC system. Suggested times for retesting are as follows:

- If no mitigation is required after initial testing (e.g., all rooms were found to have levels below 4 pCi/L), retest all frequently occupied rooms in contact with the ground sometime in the future. As a building ages and settles, radon entry may increase due to cracks in the foundation or other structural changes.

- If radon mitigation measures have been implemented in a school, retest these systems as a periodic check on any implemented radon reduction measures.
- If major renovations to the structure of a school building or major alterations to a school's HVAC system are planned, retest the school before initiating the renovation. If elevated radon is present, radon-resistant techniques can be included as part of the renovation.
- Retest after major renovations to the structure of a school building or after major alterations to a school's HVAC system. These renovations and alterations may increase radon levels within a school building.
- Long term testing during the winter months is recommended for any areas above 4 pCi/L.

Appendix A: Chain of Custody Forms and Lab Results – by School

Appendix A:
CHAIN OF CUSTODY
FORMS & LAB RESULTS -
by School

Administration Building

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00
* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
8210000	04/29/2019	14:00	05/01/2019	15:00
9209999	04/29/2019	14:00	05/01/2019	15:00
9209992	04/29/2019	14:00	05/01/2019	15:00
9209996	04/29/2019	14:00	05/01/2019	15:00
9209997	04/29/2019	14:00	05/01/2019	15:00
9209993	04/29/2019	14:00	05/01/2019	15:00
9209998	04/29/2019	14:00	05/01/2019	15:00

TAB]

(+ / - 5 degrees) (your designations for facility, building and room)
r example

(optional)

(enter proper code)
0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Admin Building	Main Structure	R1		1
68	Admin Building	Main Structure	R5B		1
68	Admin Building	Main Structure	R7		1
68	Admin Building	Main Structure	R12		1
68	Admin Building	Main Structure	R21		1
68	Admin Building	Main Structure	R20c		1
68	Admin Building	Main Structure	R20c		1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9209992	2019-04-29	2:00 pm	2019-05-01	3:00 pm	68	ADMIN BUILDING	MAIN STRUCTURE	R7		1	3.7
9209993	2019-04-29	2:00 pm	2019-05-01	3:00 pm	68	ADMIN BUILDING	MAIN STRUCTURE	R20C		1	8.6
9209996	2019-04-29	2:00 pm	2019-05-01	3:00 pm	68	ADMIN BUILDING	MAIN STRUCTURE	R12		1	4.2
9209997	2019-04-29	2:00 pm	2019-05-01	3:00 pm	68	ADMIN BUILDING	MAIN STRUCTURE	R21		1	4.1
9209998	2019-04-29	2:00 pm	2019-05-01	3:00 pm	68	ADMIN BUILDING	MAIN STRUCTURE	R20C		1	8.2
9209999	2019-04-29	2:00 pm	2019-05-01	3:00 pm	68	ADMIN BUILDING	MAIN STRUCTURE	R5B		1	2.3
9210000	2019-04-29	2:00 pm	2019-05-01	3:00 pm	68	ADMIN BUILDING	MAIN STRUCTURE	R1		1	4.1

Baca Elementary

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00
* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9220374	05/15/2019	16:00	05/17/2019	16:00
9220374	05/15/2019	16:00	05/17/2019	16:00
9220376	05/15/2019	16:00	05/17/2019	16:00
9220378	05/15/2019	16:00	05/17/2019	16:00
9220377	05/15/2019	16:00	05/17/2019	16:00
9220379	05/15/2019	16:00	05/17/2019	16:00
9220383	05/15/2019	16:00	05/17/2019	16:00
9220380	05/15/2019	16:00	05/17/2019	16:00
9220381	05/15/2019	16:00	05/17/2019	16:00
9220382	05/15/2019	16:00	05/17/2019	16:00
9220385	05/15/2019	16:00	05/17/2019	16:00
9220387	05/15/2019	16:00	05/17/2019	16:00
9220388	05/15/2019	16:00	05/17/2019	16:00
9220391	05/15/2019	16:00	05/17/2019	16:00
9220384	05/15/2019	16:00	05/17/2019	16:00
9220394	05/15/2019	16:00	05/17/2019	16:00
9220393	05/15/2019	16:00	05/17/2019	16:00
9220395	05/15/2019	16:00	05/17/2019	16:00
9220392	05/15/2019	16:00	05/17/2019	16:00
9220396	05/15/2019	16:00	05/17/2019	16:00
9220397	05/15/2019	16:00	05/17/2019	16:00
9220400	05/15/2019	16:00	05/17/2019	16:00
9220398	05/15/3000	16:00	05/17/2019	16:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=oth

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	BACA Elementary	Main School	R167		1
68	BACA Elementary	Main School	Cafeteria		1
68	BACA Elementary	Main School	Cafeteria		1
68	BACA Elementary	Main School	Gym		1
68	BACA Elementary	Main School	Gym		1
68	BACA Elementary	Main School	Kindergarten		1
68	BACA Elementary	Main School	R163		1
68	BACA Elementary	Main School	R164		1
68	BACA Elementary	Main School	R125		1
68	BACA Elementary	Main School	R131		1
68	BACA Elementary	Main School	Media		1
68	BACA Elementary	Main School	R132		1
68	BACA Elementary	Main School	R133		1
68	BACA Elementary	Main School	Computer Lab		1
68	BACA Elementary	Main School	R135		1
68	BACA Elementary	Main School	R136		1
68	BACA Elementary	Main School	R137		1
68	BACA Elementary	Main School	R138		1
68	BACA Elementary	Main School	R146		1
68	BACA Elementary	Main School	R153		1
68	BACA Elementary	Main School	R152		1
68	BACA Elementary	Main School	R147		1
68	BACA Elementary	Main School	R148		1

Radon test result report for:
**BACA ELEMENTARY
 MAIN SCHOOL**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9220376	CAFETERIA	2019-05-15 @ 4:00 pm	2019-05-17 @ 4:00 pm	< 0.3	2019-05-20
9220391	COMPUTER LAB	2019-05-15 @ 4:00 pm	2019-05-17 @ 4:00 pm	0.7 ± 0.4	2019-05-20
9220377	GYM	2019-05-15 @ 4:00 pm	2019-05-17 @ 4:00 pm	0.7 ± 0.4	2019-05-20
9220378	GYM	2019-05-15 @ 4:00 pm	2019-05-17 @ 4:00 pm	0.7 ± 0.4	2019-05-20
9220379	KINDERGARTEN	2019-05-15 @ 4:00 pm	2019-05-17 @ 4:00 pm	0.9 ± 0.4	2019-05-20
9220385	MEDIA	2019-05-15 @ 4:00 pm	2019-05-17 @ 4:00 pm	< 0.3	2019-05-20
9220381	R125	2019-05-15 @ 4:00 pm	2019-05-17 @ 4:00 pm	< 0.3	2019-05-20
9220382	R131	2019-05-15 @ 4:00 pm	2019-05-17 @ 4:00 pm	0.6 ± 0.4	2019-05-20
9220387	R132	2019-05-15 @ 4:00 pm	2019-05-17 @ 4:00 pm	< 0.3	2019-05-20
9220388	R133	2019-05-15 @ 4:00 pm	2019-05-17 @ 4:00 pm	0.5 ± 0.3	2019-05-20
9220384	R135	2019-05-15 @ 4:00 pm	2019-05-17 @ 4:00 pm	< 0.3	2019-05-20
9220394	R136	2019-05-15 @ 4:00 pm	2019-05-17 @ 4:00 pm	< 0.3	2019-05-20
9220393	R137	2019-05-15 @ 4:00 pm	2019-05-17 @ 4:00 pm	0.6 ± 0.3	2019-05-20
9220395	R138	2019-05-15 @ 4:00 pm	2019-05-17 @ 4:00 pm	< 0.3	2019-05-20
9220392	R146	2019-05-15 @ 4:00 pm	2019-05-17 @ 4:00 pm	0.6 ± 0.3	2019-05-20
9220400	R147	2019-05-15 @ 4:00 pm	2019-05-17 @ 4:00 pm	< 0.3	2019-05-20
9220398	R148	3000-05-15 @ 4:00 pm	2019-05-17 @ 4:00 pm	???? IB	2019-05-20
9220397	R152	2019-05-15 @ 4:00 pm	2019-05-17 @ 4:00 pm	< 0.3	2019-05-20
9220396	R153	2019-05-15 @ 4:00 pm	2019-05-17 @ 4:00 pm	< 0.3	2019-05-20
9220374	R167	2019-05-15 @ 4:00 pm	2019-05-17 @ 4:00 pm	< 0.3	2019-05-20

Belmont Elementary

*(from test kit)**Times should be in 24 hour format, 1pm = 13:00*** round times so that 9:31 and 10:28 both display 10:00, fo*

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9226055	05/17/2019	11:00	05/20/2019	17:00
9226053	05/17/2019	11:00	05/20/2019	17:00
9226048	05/17/2019	11:00	05/20/2019	17:00
9226051	05/17/2019	11:00	05/20/2019	17:00
9226056	05/17/2019	11:00	05/20/2019	17:00
9226054	05/17/2019	11:00	05/20/2019	17:00
9226052	05/17/2019	11:00	05/20/2019	17:00
9226057	05/17/2019	11:00	05/20/2019	17:00
9226058	05/17/2019	11:00	05/20/2019	17:00
9226059	05/17/2019	11:00	05/20/2019	17:00
9226061	05/17/2019	11:00	05/20/2019	17:00
9226062	05/17/2019	11:00	05/20/2019	17:00
9226060	05/17/2019	11:00	05/20/2019	17:00
9226063	05/17/2019	11:00	05/20/2019	17:00
9226064	05/17/2019	11:00	05/20/2019	17:00
9226069	05/17/2019	11:00	05/20/2019	17:00
9226065	05/17/2019	11:00	05/20/2019	17:00
9226071	05/17/2019	11:00	05/20/2019	17:00
9226066	05/17/2019	11:00	05/20/2019	17:00
9226067	05/17/2019	11:00	05/20/2019	17:00
9226068	05/17/2019	11:00	05/20/2019	17:00
9226070	05/17/2019	11:00	05/20/2019	17:00
9226042	05/17/2019	11:00	05/20/2019	17:00
9226073	05/17/2019	11:00	05/20/2019	17:00
9226074	05/17/2019	11:00	05/20/2019	17:00
9226077	05/17/2019	11:00	05/20/2019	17:00
9226078	05/17/2019	11:00	05/20/2019	17:00
9226075	05/17/2019	11:00	05/20/2019	17:00
9226076	05/17/2019	11:00	05/20/2019	17:00
9226079	05/17/2019	11:00	05/20/2019	17:00
9226081	05/17/2019	11:00	05/20/2019	17:00
9226087	05/17/2019	11:00	05/20/2019	17:00
9226082	05/17/2019	11:00	05/20/2019	17:00
9226080	05/17/2019	11:00	05/20/2019	17:00
9226083	05/17/2019	11:00	05/20/2019	17:00
9226084	05/17/2019	11:00	05/20/2019	17:00
9226088	05/17/2019	11:00	05/20/2019	17:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Belmont Elementary	Main School	Cafeteria		1
68	Belmont Elementary	Main School	Cafeteria		1
68	Belmont Elementary	Main School	Gym		1
68	Belmont Elementary	Main School	Gym		1
68	Belmont Elementary	Main School	R16		1
68	Belmont Elementary	Main School	Mrs Leonard		1
68	Belmont Elementary	Main School	R17		1
68	Belmont Elementary	Main School	Media Center		1
68	Belmont Elementary	Main School	Media Center		1
68	Belmont Elementary	Main School	R132		1
68	Belmont Elementary	Main School	R13		1
68	Belmont Elementary	Main School	R6		1
68	Belmont Elementary	Main School	R12		1
68	Belmont Elementary	Main School	R7		1
68	Belmont Elementary	Main School	R11		1
68	Belmont Elementary	Main School	R8		1
68	Belmont Elementary	Main School	R10		1
68	Belmont Elementary	Main School	R9		1
68	Belmont Elementary	Main School	ESL Rm		1
68	Belmont Elementary	Main School	Music Rm		1
68	Belmont Elementary	Main School	1151A		1
68	Belmont Elementary	Main School	R5		1
68	Belmont Elementary	Main School	R18		1
68	Belmont Elementary	Main School	R4		1
68	Belmont Elementary	Main School	R19		1
68	Belmont Elementary	Main School	R3		1
68	Belmont Elementary	Main School	R20		1
68	Belmont Elementary	Main School	R21		1
68	Belmont Elementary	Main School	R21		1
68	Belmont Elementary	Main School	R2		1
68	Belmont Elementary	Main School	Kindergarten		1
68	Belmont Elementary	Main School	Kindergarten		1
68	Belmont Elementary	Main School	Kindergarten		1
68	Belmont Elementary	Main School	Pre School		1
68	Belmont Elementary	Main School	Pre School		1
68	Belmont Elementary	Main School	R5		1
68	Belmont Elementary	Main School	R19		1

Radon test result report for:
**BELMONT ELEMENTARY
 MAIN SCHOOL**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9226068	1151A	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	1.3 ± 0.3	2019-05-22
9226055	CAFETERIA	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	1.5 ± 0.3	2019-05-22
9226053	CAFETERIA	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	1.5 ± 0.3	2019-05-22
9226066	ESL RM	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	0.7 ± 0.3	2019-05-22
9226051	GYM	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	0.5 ± 0.3	2019-05-22
9226048	GYM	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	< 0.3	2019-05-22
9226081	KINDERGARTEN	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	1.2 ± 0.3	2019-05-22
9226087	KINDERGARTEN	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	1.2 ± 0.3	2019-05-22
9226082	KINDERGARTEN	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	1.0 ± 0.3	2019-05-22
9226058	MEDIA CENTER	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	0.6 ± 0.3	2019-05-22
9226057	MEDIA CENTER	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	< 0.3	2019-05-22
9226054	MRS LEONARD	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	< 0.3	2019-05-22
9226067	MUSIC RM	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	0.6 ± 0.3	2019-05-22
9226083	PRE SCHOOL	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	1.3 ± 0.3	2019-05-22
9226080	PRE SCHOOL	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	1.5 ± 0.3	2019-05-22
9226065	R10	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	1.4 ± 0.3	2019-05-22
9226064	R11	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	0.5 ± 0.3	2019-05-22
9226060	R12	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	0.5 ± 0.3	2019-05-22
9226061	R13	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	0.8 ± 0.3	2019-05-22
9226059	R132	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	< 0.3	2019-05-22
9226056	R16	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	0.9 ± 0.3	2019-05-22
9226052	R17	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	< 0.3	2019-05-22
9226042	R18	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	< 0.3	2019-05-22
9226088	R19	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	< 0.3	2019-05-22
9226074	R19	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	< 0.3	2019-05-22
9226079	R2	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	< 0.3	2019-05-22
9226078	R20	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	0.9 ± 0.3	2019-05-22
9226075	R21	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	0.7 ± 0.3	2019-05-22
9226076	R21	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	< 0.3	2019-05-22
9226077	R3	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	0.6 ± 0.3	2019-05-22
9226073	R4	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	0.9 ± 0.3	2019-05-22
9226084	R5	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	0.6 ± 0.3	2019-05-22
9226070	R5	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	0.7 ± 0.3	2019-05-22
9226062	R6	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	0.7 ± 0.3	2019-05-22
9226063	R7	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	1.1 ± 0.3	2019-05-22
9226069	R8	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	0.8 ± 0.3	2019-05-22
9226071	R9	2019-05-17 @ 11:00 am	2019-05-20 @ 5:00 pm	0.7 ± 0.3	2019-05-22

Bessemer Academy

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00

* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9209727	04/23/2019	16:00	04/25/2019	16:00
9209734	04/23/2019	16:00	04/25/2019	16:00
9209741	04/23/2019	16:00	04/25/2019	16:00
9209735	04/23/2019	16:00	04/25/2019	16:00
9209736	04/23/2019	16:00	04/25/2019	16:00
9209737	04/23/2019	16:00	04/25/2019	16:00
9209738	04/23/2019	16:00	04/25/2019	16:00
9209732	04/23/2019	16:00	04/25/2019	16:00
9209739	04/23/2019	16:00	04/25/2019	16:00
9209740	04/23/2019	16:00	04/25/2019	16:00
9209742	04/23/2019	16:00	04/25/2019	16:00
9209746	04/23/2019	16:00	04/25/2019	16:00
9209744	04/23/2019	16:00	04/25/2019	16:00
9209743	04/23/2019	16:00	04/25/2019	16:00
9209752	04/23/2019	16:00	04/25/2019	16:00
9209754	04/23/2019	16:00	04/25/2019	16:00
9209747	04/23/2019	16:00	04/25/2019	16:00
9209759	04/23/2019	16:00	04/25/2019	16:00
9209745	04/23/2019	16:00	04/25/2019	16:00
9209748	04/23/2019	16:00	04/25/2019	16:00
9209749	04/23/2019	16:00	04/25/2019	16:00
9209762	04/23/2019	16:00	04/25/2019	16:00
9209753	04/23/2019	16:00	04/25/2019	16:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Bessmer Elementary	Main School	R106		1
68	Bessmer Elementary	Main School	R107		1
68	Bessmer Elementary	Main School	R108		1
68	Bessmer Elementary	Main School	R105		1
68	Bessmer Elementary	Main School	R103		1
68	Bessmer Elementary	Main School	R102		1
68	Bessmer Elementary	Main School	R109		1
68	Bessmer Elementary	Main School	R101		1
68	Bessmer Elementary	Main School	R110		1
68	Bessmer Elementary	Main School	R110		1
68	Bessmer Elementary	Main School	Gym		1
68	Bessmer Elementary	Main School	Gym		1
68	Bessmer Elementary	Main School	R112		1
68	Bessmer Elementary	Main School	R112		1
68	Bessmer Elementary	Main School	R119		1
68	Bessmer Elementary	Main School	R113		1
68	Bessmer Elementary	Main School	R114		1
68	Bessmer Elementary	Main School	R118		1
68	Bessmer Elementary	Main School	R115		1
68	Bessmer Elementary	Main School	R116		1
68	Bessmer Elementary	Main School	Zapukvip		1
68	Bessmer Elementary	Main School	Office B		1
68	Bessmer Elementary	Main School	nsulers Office		1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9209727	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	106		1	1.0
9209732	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	101		1	0.9
9209734	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	107		1	0.8
9209735	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	105		1	1.0
9209736	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	103		1	1.7
9209737	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	102		1	0.8
9209738	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	109		1	0.8
9209739	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	110		1	0.6
9209740	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	110		1	< 0.3
9209741	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	108		1	0.7
9209742	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	GYM		1	0.8
9209743	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	112		1	0.7
9209744	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	112		1	0.7
9209745	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	115		1	0.9
9209746	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	GYM		1	0.7
9209747	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	114		1	0.7
9209748	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	116		1	0.8
9209749	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	ZAPUKVIP		1	0.7
9209752	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	119		1	0.7
9209753	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	CONSULERS OFFICE		1	0.6
9209754	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	113		1	0.9
9209759	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	118		1	0.7
9209762	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	BESSMER ELEMENTARY	MAIN SCHOOL	OFFICE B		1	0.5

Beulah Heights

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00
* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9210199	04/16/2019	15:00	04/18/2019	15:00
9210193	04/16/2019	15:00	04/18/2019	15:00
9210183	04/16/2019	15:00	04/18/2019	15:00
9210192	04/16/2019	15:00	04/18/2019	15:00
9210194	04/16/2019	15:00	04/18/2019	15:00
9210195	04/16/2019	15:00	04/18/2019	15:00
9210196	04/16/2019	15:00	04/18/2019	15:00
9210197	04/16/2019	15:00	04/18/2019	15:00
9209840	04/16/2019	15:00	04/18/2019	15:00
9209850	04/16/2019	15:00	04/18/2019	15:00
9209849	04/16/2019	15:00	04/18/2019	15:00
9209851	04/16/2019	15:00	04/18/2019	15:00
9209853	04/16/2019	15:00	04/18/2019	15:00
9209843	04/16/2019	15:00	04/18/2019	15:00
9209842	04/16/2019	15:00	04/18/2019	15:00
9209837	04/16/2019	15:00	04/18/2019	15:00
9209844	04/16/2019	15:00	04/18/2019	15:00
9209846	04/16/2019	15:00	04/18/2019	15:00
9209847	04/16/2019	15:00	04/18/2019	15:00
9209848	04/16/2019	15:00	04/18/2019	15:00
9209856	04/16/2019	15:00	04/18/2019	15:00
9209852	04/16/2019	15:00	04/18/2019	15:00
9209863	04/16/2019	15:00	04/18/2019	15:00
9210200	04/16/2019	15:00	04/18/2019	15:00
9209864	04/16/2019	15:00	04/18/2019	15:00
9209865	04/16/2019	15:00	04/18/2019	15:00
9209858	04/16/2019	15:00	04/18/2019	15:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Beulah Heights	Main	21		1
68	Beulah Heights	Main	20		1
68	Beulah Heights	Main	22		1
68	Beulah Heights	Main	23		1
68	Beulah Heights	Main	24		1
68	Beulah Heights	Main	25		1
68	Beulah Heights	Main	26		1
68	Beulah Heights	Main	27		1
68	Beulah Heights	Main	Computer		1
68	Beulah Heights	Main	28		1
68	Beulah Heights	Main	29		1
68	Beulah Heights	Main	29		1
68	Beulah Heights	Main	Media		1
68	Beulah Heights	Main	34		1
68	Beulah Heights	Main	35		1
68	Beulah Heights	Main	36		1
68	Beulah Heights	Main	41		1
68	Beulah Heights	Main	40		1
68	Beulah Heights	Main	39		1
68	Beulah Heights	Main	37		1
68	Beulah Heights	Main	39		1
68	Beulah Heights	Main	38		1
68	Beulah Heights	Main	42		1
68	Beulah Heights	Main	32		1
68	Beulah Heights	Main	30		1
68	Beulah Heights	Main	31		1
68	Beulah Heights	Main	31		1

Radon test result report for:
BEULAH HEIGHTS
MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9210193	20	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	< 0.3	2019-04-23
9210199	21	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	0.5 ± 0.5	2019-04-23
9210183	22	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	< 0.3	2019-04-23
9210192	23	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	1.0 ± 0.5	2019-04-23
9210194	24	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	1.0 ± 0.5	2019-04-23
9210195	25	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	1.2 ± 0.5	2019-04-23
9210196	26	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	0.8 ± 0.5	2019-04-23
9210197	27	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	1.3 ± 0.5	2019-04-23
9209850	28	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	1.1 ± 0.5	2019-04-23
9209849	29	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	1.6 ± 0.5	2019-04-23
9209851	29	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	< 0.3	2019-04-23
9209864	30	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	< 0.3	2019-04-23
9209865	31	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	0.7 ± 0.5	2019-04-23
9209858	31	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	< 0.3	2019-04-23
9210200	32	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	0.8 ± 0.5	2019-04-23
9209843	34	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	0.9 ± 0.5	2019-04-23
9209842	35	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	0.6 ± 0.5	2019-04-23
9209837	36	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	1.3 ± 0.5	2019-04-23
9209848	37	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	1.0 ± 0.5	2019-04-23
9209852	38	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	1.1 ± 0.5	2019-04-23
9209847	39	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	1.2 ± 0.5	2019-04-23
9209856	39	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	0.7 ± 0.5	2019-04-23
9209846	40	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	0.7 ± 0.4	2019-04-23
9209844	41	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	1.3 ± 0.5	2019-04-23
9209863	42	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	< 0.3	2019-04-23
9209840	COMPUTER	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	1.7 ± 0.5	2019-04-23
9209853	MEDIA	2019-04-16 @ 3:00 pm	2019-04-18 @ 3:00 pm	0.8 ± 0.5	2019-04-23

Bradford Elementary

(from test kit)

Times should be in 24 hour format, 1pm = 13:00

* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9220472	05/03/2019	11:00	05/06/2019	17:00
9220473	05/03/2019	11:00	05/06/2019	17:00
9220474	05/03/2019	11:00	05/06/2019	17:00
9220475	05/03/2019	11:00	05/06/2019	17:00
9220476	05/03/2019	11:00	05/06/2019	17:00
9220477	05/03/2019	11:00	05/06/2019	17:00
9220478	05/03/2019	11:00	05/06/2019	17:00
9220479	05/03/2019	11:00	05/06/2019	17:00
9220480	05/03/2019	11:00	05/06/2019	17:00
9220481	05/03/2019	11:00	05/06/2019	17:00
9220482	05/03/2019	11:00	05/06/2019	17:00
9220483	05/03/2019	11:00	05/06/2019	17:00
9220484	05/03/2019	11:00	05/06/2019	17:00
9220485	05/03/2019	11:00	05/06/2019	17:00
9220486	05/03/2019	11:00	05/06/2019	17:00
9220487	05/03/2019	11:00	05/06/2019	17:00
9220488	05/03/2019	11:00	05/06/2019	17:00
9220489	05/03/2019	11:00	05/06/2019	17:00
9220490	05/03/2019	11:00	05/06/2019	17:00
9220491	05/03/2019	11:00	05/06/2019	17:00
9220492	05/03/2019	11:00	05/06/2019	17:00
9220496	05/03/2019	11:00	05/06/2019	17:00
9220493	05/03/2019	11:00	05/06/2019	17:00
9220494	05/03/2019	11:00	05/06/2019	17:00
9220495	05/03/2019	11:00	05/06/2019	17:00
9220497	05/03/2019	11:00	05/06/2019	17:00
9220498	05/03/2019	11:00	05/06/2019	17:00
9220499	05/03/2019	11:00	05/06/2019	17:00
9220500	05/03/2019	11:00	05/06/2019	17:00
9220503	05/03/2019	11:00	05/06/2019	17:00
9220502	05/03/2019	11:00	05/06/2019	17:00
9220504	05/03/2019	11:00	05/06/2019	17:00
9220514	05/03/2019	11:00	05/06/2019	17:00
9220521	05/03/2019	11:00	05/06/2019	17:00
9220522	05/03/2019	11:00	05/06/2019	17:00
9220513	05/03/2019	11:00	05/06/2019	17:00
9220507	05/03/2019	11:00	05/06/2019	17:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Bradford	Main School	Baca		1
68	Bradford	Main School	Tina		1
68	Bradford	Main School	Gloria		1
68	Bradford	Main School	R10		1
68	Bradford	Main School	R9		1
68	Bradford	Main School	R8		1
68	Bradford	Main School	R7		1
68	Bradford	Main School	R6		1
68	Bradford	Main School	R5		1
68	Bradford	Main School	Media Center		1
68	Bradford	Main School	Media Center		1
68	Bradford	Main School	Media Center		1
68	Bradford	Main School	R4		1
68	Bradford	Main School	Gym		1
68	Bradford	Main School	Gym		1
68	Bradford	Main School	R12		1
68	Bradford	Main School	R14		1
68	Bradford	Main School	R11		1
68	Bradford	Main School	R13		1
68	Bradford	Main School	R16		1
68	Bradford	Main School	R16		1
68	Bradford	Main School	R15		1
68	Bradford	Main School	R20		1
68	Bradford	Main School	R19		1
68	Bradford	Main School	R22		1
68	Bradford	Main School	R21		1
68	Bradford	Main School	R24		1
68	Bradford	Main School	R23		1
68	Bradford	Main School	Cafeteria		1
68	Bradford	Main School	Cafeteria		1
68	Bradford	Main School	Cafeteria		1
68	Bradford	Main School	R1		1
68	Bradford	Main School	R2		1
68	Bradford	Main School	R2		1
68	Bradford	Main School	Mobile 6		1
68	Bradford	Main School	Mobile 6		1
68	Bradford	Main School	Mobile 5		1
			Gym		

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9220472	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	BACA		1	< 0.3
9220473	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	TINA		1	< 0.3
9220474	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	GLORIA		1	< 0.3
9220475	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	10		1	1.0
9220476	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	9		1	1.9
9220477	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	8		1	1.8
9220478	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	7		1	0.6
9220479	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	6		1	0.7
9220480	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	5		1	0.9
9220481	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	MEDIA CENTER		1	< 0.3
9220482	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	MEDIA CENTER		1	< 0.3
9220483	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	MEDIA CENTER		1	< 0.3
9220484	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	4		1	0.5
9220485	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	GYM		1	0.9
9220486	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	GYM		1	0.5
9220487	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	12		1	0.6
9220488	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	14		1	1.4
9220489	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	11		1	1.4
9220490	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	13		1	1.6
9220491	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	16		1	< 0.3
9220492	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	16		1	< 0.3
9220493	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	20		1	1.6
9220494	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	19		1	1.0
9220495	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	22		1	1.3
9220496	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	15		1	0.7
9220497	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	21		1	1.4
9220498	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	24		1	1.8
9220499	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	23		1	3.0
9220500	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	CAFETERIA		1	1.7
9220502	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	CAFETERIA		1	1.7
9220503	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	CAFETERIA		1	1.6
9220504	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	1		1	3.3
9220507	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	MOBILE 5		1	< 0.3
9220513	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	MOBILE 6		1	< 0.3
9220514	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	2		1	2.5

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9220521	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	2		1	3.0
9220522	2019-05-03	11:00 am	2019-05-06	5:00 pm	68	BRADFORD	MAIN SCHOOL	MOBILE 6		1	< 0.3

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Bus Barn

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00
* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9220568	05/08/2019	14:00	05/10/2019	14:00
9220567	05/08/2019	14:00	05/10/2019	14:00
9220564	05/08/2019	14:00	05/10/2019	14:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Bus Barn	Main Building	Office #1		1
68	Bus Barn	Main Building	Office #2		1
68	Bus Barn	Main Building	ference Room		1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9220564	2019-05-08	2:00 pm	2019-05-10	2:00 pm	68	BUS BARN	MAIN BUILDING	CONFERENCE ROOM		1	0.6
9220567	2019-05-08	2:00 pm	2019-05-10	2:00 pm	68	BUS BARN	MAIN BUILDING	OFFICE #2		1	< 0.3
9220568	2019-05-08	2:00 pm	2019-05-10	2:00 pm	68	BUS BARN	MAIN BUILDING	OFFICE #1		1	0.6

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Caesar Chavez

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00
* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9220354	05/14/2019	16:00	05/16/2019	16:00
9220355	05/14/2019	16:00	05/16/2019	16:00
9220350	05/14/2019	16:00	05/16/2019	16:00
9220351	05/14/2019	16:00	05/16/2019	16:00
9220356	05/14/2019	16:00	05/16/2019	16:00
9220352	05/14/2019	16:00	05/16/2019	16:00
9220358	05/14/2019	16:00	05/16/2019	16:00
9220357	05/14/2019	16:00	05/16/2019	16:00
9220359	05/14/2019	16:00	05/16/2019	16:00
9220360	05/14/2019	16:00	05/16/2019	16:00
9220365	05/14/2019	16:00	05/16/2019	16:00
9220366	05/14/2019	16:00	05/16/2019	16:00
9220363	05/14/2019	16:00	05/16/2019	16:00
9220361	05/14/2019	16:00	05/16/2019	16:00
9220362	05/14/2019	16:00	05/16/2019	16:00
9220364	05/14/2019	16:00	05/16/2019	16:00
9220367	05/14/2019	16:00	05/16/2019	16:00
9220368	05/14/2019	16:00	05/16/2019	16:00
9220369	05/14/2019	16:00	05/16/2019	16:00
9220370	05/14/2019	16:00	05/16/2019	16:00
9220371	05/14/2019	16:00	05/16/2019	16:00
9220372	05/14/2019	16:00	05/16/2019	16:00
9220373	05/14/2019	16:00	05/16/2019	16:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Ceasaer Chavez	Main School	Gym		1
68	Ceasaer Chavez	Main School	Gym		1
68	Ceasaer Chavez	Main School	Cafeteria		1
68	Ceasaer Chavez	Main School	Cafeteria		1
68	Ceasaer Chavez	Main School	Rm 93		1
68	Ceasaer Chavez	Main School	Rm 106A		1
68	Ceasaer Chavez	Main School	Rm 106		1
68	Ceasaer Chavez	Main School	Rm 107		1
68	Ceasaer Chavez	Main School	Rm 108		1
68	Ceasaer Chavez	Main School	Rm 109		1
68	Ceasaer Chavez	Main School	Rm 110		1
68	Ceasaer Chavez	Main School	Library		1
68	Ceasaer Chavez	Main School	Library		1
68	Ceasaer Chavez	Main School	Library		1
68	Ceasaer Chavez	Main School	Rm 102		1
68	Ceasaer Chavez	Main School	Rm 101		1
68	Ceasaer Chavez	Main School	Rm 100		1
68	Ceasaer Chavez	Main School	Rm 99		1
68	Ceasaer Chavez	Main School	Rm 97		1
68	Ceasaer Chavez	Main School	Rm 103		1
68	Ceasaer Chavez	Main School	Rm 104		1
68	Ceasaer Chavez	Main School	Rm 105		1
68	Ceasaer Chavez	Main School	Rm 105		1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9220350	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	CAFETERIA		1	1.2
9220351	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	CAFETERIA		1	1.3
9220352	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	RM 106A		1	1.6
9220354	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	GYM		1	1.9
9220355	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	GYM		1	2.2
9220356	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	RM 93		1	1.8
9220357	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	RM 107		1	2.1
9220358	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	RM 106		1	3.5
9220359	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	RM 108		1	2.3
9220360	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	RM 109		1	2.7
9220361	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	LIBRARY		1	1.1
9220362	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	RM 102		1	1.2
9220363	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	LIBRARY		1	1.3
9220364	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	RM 101		1	1.3
9220365	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	RM 110		1	2.1
9220366	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	LIBRARY		1	1.6
9220367	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	RM 100		1	1.4
9220368	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	RM 99		1	1.8
9220369	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	RM 97		1	2.1
9220370	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	RM 103		1	1.1
9220371	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	RM 104		1	2.5
9220372	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	RM 105		1	1.8
9220373	2019-05-14	4:00 pm	2019-05-16	4:00 pm	68	CEASAER CHAVEZ	MAIN SCHOOL	RM 105		1	2.0

Carlile Elementary

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00
* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9209900	04/19/2019	11:00	04/22/2019	17:00
9209896	04/19/2019	11:00	04/22/2019	17:00
9209884	04/19/2019	11:00	04/22/2019	17:00
9209703	04/19/2019	11:00	04/22/2019	17:00
9209704	04/19/2019	11:00	04/22/2019	17:00
9209713	04/19/2019	11:00	04/22/2019	17:00
9209890	04/19/2019	11:00	04/22/2019	17:00
9209885	04/19/2019	11:00	04/22/2019	17:00
9209888	04/19/2019	11:00	04/22/2019	18:00
9209714	04/19/2019	11:00	04/22/2019	18:00
9209877	04/19/2019	11:00	04/22/2019	18:00
9209702	04/19/2019	11:00	04/22/2019	18:00
9209705	04/19/2019	11:00	04/22/2019	18:00
9209701	04/19/2019	11:00	04/22/2019	18:00
9209711	04/19/2019	11:00	04/22/2019	18:00
9209707	04/19/2019	11:00	04/22/2019	18:00
9209709	04/19/2019	11:00	04/22/2019	18:00
9209710	04/19/2019	11:00	04/22/2019	18:00
9209708	04/19/2019	11:00	04/22/2019	18:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Carlile Elementary	Main School	R27		1
68	Carlile Elementary	Main School	R28		1
68	Carlile Elementary	Main School	R29		1
68	Carlile Elementary	Main School	Media Center		1
68	Carlile Elementary	Main School	Media Center		1
68	Carlile Elementary	Main School	R21		1
68	Carlile Elementary	Main School	R25		1
68	Carlile Elementary	Main School	R22		1
68	Carlile Elementary	Main School	R24		1
68	Carlile Elementary	Main School	R23		1
68	Carlile Elementary	Main School	Cafeteria		1
68	Carlile Elementary	Main School	cafeteria		1
68	Carlile Elementary	Main School	Cafeteria		1
68	Carlile Elementary	Main School	Gym		1
68	Carlile Elementary	Main School	Gym		1
68	Carlile Elementary	Main School	Preschool		1
68	Carlile Elementary	Main School	Ess A2		1
68	Carlile Elementary	Main School	A4		1
68	Carlile Elementary	Main School	A3		1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9209701	2019-04-19	11:00 am	2019-04-22	6:00 pm	68	CARLILE ELEMENTARY	MAIN SCHOOL	GYM		1	1.6
9209702	2019-04-19	11:00 am	2019-04-22	6:00 pm	68	CARLILE ELEMENTARY	MAIN SCHOOL	CAFETERIA		1	1.8
9209703	2019-04-19	11:00 am	2019-04-22	5:00 pm	68	CARLILE ELEMENTARY	MAIN SCHOOL	MEDIA CENTER		1	1.2
9209704	2019-04-19	11:00 am	2019-04-22	5:00 pm	68	CARLILE ELEMENTARY	MAIN SCHOOL	MEDIA CENTER		1	1.5
9209705	2019-04-19	11:00 am	2019-04-22	6:00 pm	68	CARLILE ELEMENTARY	MAIN SCHOOL	CAFETERIA		1	1.7
9209707	2019-04-19	11:00 am	2019-04-22	6:00 pm	68	CARLILE ELEMENTARY	MAIN SCHOOL	PRESCHOOL		1	< 0.3
9209708	2019-04-19	11:00 am	2019-04-22	6:00 pm	68	CARLILE ELEMENTARY	MAIN SCHOOL	A3		1	< 0.3
9209709	2019-04-19	11:00 am	2019-04-22	6:00 pm	68	CARLILE ELEMENTARY	MAIN SCHOOL	ESS A2		1	< 0.3
9209710	2019-04-19	11:00 am	2019-04-22	6:00 pm	68	CARLILE ELEMENTARY	MAIN SCHOOL	A4		1	< 0.3
9209711	2019-04-19	11:00 am	2019-04-22	6:00 pm	68	CARLILE ELEMENTARY	MAIN SCHOOL	GYM		1	1.6
9209713	2019-04-19	11:00 am	2019-04-22	5:00 pm	68	CARLILE ELEMENTARY	MAIN SCHOOL	21		1	0.8
9209714	2019-04-19	11:00 am	2019-04-22	6:00 pm	68	CARLILE ELEMENTARY	MAIN SCHOOL	23		1	1.0
9209877	2019-04-19	11:00 am	2019-04-22	6:00 pm	68	CARLILE ELEMENTARY	MAIN SCHOOL	CAFETERIA		1	2.2
9209884	2019-04-19	11:00 am	2019-04-22	5:00 pm	68	CARLILE ELEMENTARY	MAIN SCHOOL	29		1	1.0
9209885	2019-04-19	11:00 am	2019-04-22	5:00 pm	68	CARLILE ELEMENTARY	MAIN SCHOOL	22		1	0.7
9209888	2019-04-19	11:00 am	2019-04-22	6:00 pm	68	CARLILE ELEMENTARY	MAIN SCHOOL	24		1	0.6
9209890	2019-04-19	11:00 am	2019-04-22	5:00 pm	68	CARLILE ELEMENTARY	MAIN SCHOOL	25		1	1.0
9209896	2019-04-19	11:00 am	2019-04-22	5:00 pm	68	CARLILE ELEMENTARY	MAIN SCHOOL	28		1	1.0
9209900	2019-04-19	11:00 am	2019-04-22	5:00 pm	68	CARLILE ELEMENTARY	MAIN SCHOOL	27		1	0.5

Centennial High School

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00

* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9227201	05/28/2019	16:00	05/30/2019	16:00
9227202	05/28/2019	16:00	05/30/2019	16:00
9227400	05/28/2019	16:00	05/30/2019	16:00
9227203	05/28/2019	16:00	05/30/2019	16:00
9227204	05/28/2019	16:00	05/30/2019	16:00
9227205	05/28/2019	16:00	05/30/2019	16:00
9227207	05/28/2019	16:00	05/30/2019	16:00
9227208	05/28/2019	16:00	05/30/2019	16:00
9227209	05/28/2019	16:00	05/30/2019	16:00
9227210	05/28/2019	16:00	05/30/2019	16:00
9227211	05/28/2019	16:00	05/30/2019	16:00
9227212	05/28/2019	16:00	05/30/2019	16:00
9227213	05/28/2019	16:00	05/30/2019	16:00
9227214	05/28/2019	16:00	05/30/2019	16:00
9227217	05/28/2019	16:00	05/30/2019	16:00
9227218	05/28/2019	16:00	05/30/2019	16:00
9227219	05/28/2019	16:00	05/30/2019	16:00
9227215	05/28/2019	16:00	05/30/2019	16:00
9227220	05/28/2019	16:00	05/30/2019	16:00
9227216	05/28/2019	16:00	05/30/2019	16:00
9227222	05/28/2019	16:00	05/30/2019	16:00
9227223	05/28/2019	16:00	05/30/2019	16:00
9227224	05/28/2019	16:00	05/30/2019	16:00
9227225	05/28/2019	16:00	05/30/2019	16:00
9227226	05/28/2019	16:00	05/30/2019	16:00
9227227	05/28/2019	16:00	05/30/2019	16:00
9227228	05/28/2019	16:00	05/30/2019	16:00
9227229	05/28/2019	16:00	05/30/2019	16:00
9227230	05/28/2019	16:00	05/30/2019	16:00
9227231	05/28/2019	16:00	05/30/2019	16:00
9227232	05/28/2019	16:00	05/30/2019	16:00
9227233	05/28/2019	16:00	05/30/2019	16:00
9227234	05/28/2019	16:00	05/30/2019	16:00
9227235	05/28/2019	16:00	05/30/2019	16:00
9227236	05/28/2019	16:00	05/30/2019	16:00
9227237	05/28/2019	16:00	05/30/2019	16:00
9227238	05/28/2019	16:00	05/30/2019	16:00
9227240	05/28/2019	16:00	05/30/2019	16:00
9227241	05/28/2019	16:00	05/30/2019	16:00
9227242	05/28/2019	16:00	05/30/2019	16:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Centennial	Main School	R301		1
68	Centennial	Main School	R310		1
68	Centennial	Main School	R408		1
68	Centennial	Main School	R403 B		1
68	Centennial	Main School	R403 A		1
68	Centennial	Main School	R403 C		1
68	Centennial	Main School	Gym		1
68	Centennial	Main School	R105		1
68	Centennial	Main School	R105		1
68	Centennial	Main School	R105		1
68	Centennial	Main School	R110		1
68	Centennial	Main School	R110		1
68	Centennial	Main School	R113		1
68	Centennial	Main School	R113		1
68	Centennial	Main School	R207		1
68	Centennial	Main School	R207		1
68	Centennial	Main School	R203		1
68	Centennial	Main School	R203		1
68	Centennial	Main School	R303		1
68	Centennial	Main School	R302		1
68	Centennial	Main School	R313		1
68	Centennial	Main School	R312		1
68	Centennial	Main School	R311		1
68	Centennial	Main School	R309		1
68	Centennial	Main School	R300		1
68	Centennial	Main School	R410		1
68	Centennial	Main School	R411		1
68	Centennial	Main School	R413		1
68	Centennial	Main School	R414		1
68	Centennial	Main School	R416		1
68	Centennial	Main School	R417		1
68	Centennial	Main School	R417		1
68	Centennial	Main School	R418		1
68	Centennial	Main School	R419		1
68	Centennial	Main School	R407		1
68	Centennial	Main School	R405		1
68	Centennial	Main School	R404		1
68	Centennial	Main School	R406		1
68	Centennial	Main School	Cafeteria		1
68	Centennial	Main School	Cafeteria		1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9227201	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	301		1	< 0.3
9227202	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	310		1	< 0.3
9227203	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	R403 B		1	< 0.3
9227204	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	R403 A		1	0.8
9227205	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	R403 C		1	0.7
9227207	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	GYM		1	0.5
9227208	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	105		1	< 0.3
9227209	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	105		1	0.9
9227210	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	105		1	0.7
9227211	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	110		1	0.8
9227212	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	110		1	1.0
9227213	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	113		1	0.6
9227214	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	113		1	< 0.3
9227215	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	203		1	0.6
9227216	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	302		1	< 0.3
9227217	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	207		1	< 0.3
9227218	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	207		1	< 0.3
9227219	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	203		1	< 0.3
9227220	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	303		1	0.5
9227222	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	313		1	< 0.3
9227223	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	312		1	< 0.3
9227224	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	311		1	0.5
9227225	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	309		1	0.5
9227226	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	300		1	0.6
9227227	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	410		1	< 0.3
9227228	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	411		1	0.6
9227229	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	413		1	0.6
9227230	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	414		1	< 0.3
9227231	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	416		1	< 0.3
9227232	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	417		1	< 0.3
9227233	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	417		1	< 0.3
9227234	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	418		1	< 0.3
9227235	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	419		1	< 0.3
9227236	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	407		1	2.8
9227237	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	405		1	< 0.3

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9227238	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	404		1	0.5
9227240	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	406		1	< 0.3
9227241	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	CAFETERIA		1	< 0.3
9227242	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	CAFETERIA		1	< 0.3
9227400	2019-05-28	4:00 pm	2019-05-30	4:00 pm	68	CENTENNIAL	MAIN SCHOOL	408		1	0.6

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Central High School

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00
* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9209881	04/19/2019	9:00	04/22/2019	17:00
9209883	04/19/2019	9:00	04/22/2019	17:00
9209887	04/19/2019	9:00	04/22/2019	17:00
9209891	04/19/2019	9:00	04/22/2019	17:00
9209889	04/19/2019	9:00	04/22/2019	17:00
9209867	04/19/2019	9:00	04/22/2019	17:00
9209878	04/19/2019	9:00	04/22/2019	17:00
9209861	04/19/2019	9:00	04/22/2019	17:00
9209880	04/19/2019	9:00	04/22/2019	17:00
9209879	04/19/2019	9:00	04/22/2019	17:00
9209870	04/19/2019	9:00	04/22/2019	17:00
9209868	04/19/2019	9:00	04/22/2019	17:00
9209882	04/19/2019	9:00	04/22/2019	17:00
9209886	04/19/2019	9:00	04/22/2019	17:00
9209893	04/19/2019	9:00	04/22/2019	17:00
9209894	04/19/2019	9:00	04/22/2019	17:00
9209898	04/19/2019	9:00	04/22/2019	17:00
9209897	04/19/2019	9:00	04/22/2019	17:00
9209899	04/19/2019	9:00	04/22/2019	17:00
9209895	04/19/2019	9:00	04/22/2019	17:00
9209892	04/19/2019	9:00	04/22/2019	17:00
9209869	04/19/2019	9:00	04/22/2019	17:00
9209872	04/19/2019	9:00	04/22/2019	17:00
9209876	04/19/2019	9:00	04/22/2019	17:00
9209873	04/19/2019	9:00	04/22/2019	17:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Central High School	Main School	R209		1
68	Central High School	Main School	R210		1
68	Central High School	Main School	R208		1
68	Central High School	Main School	R208		1
68	Central High School	Main School	R207		1
68	Central High School	Main School	R211		1
68	Central High School	Main School	R211		1
68	Central High School	Main School	R212		1
68	Central High School	Main School	R212		1
68	Central High School	Main School	205-206		1
68	Central High School	Main School	205-206		1
68	Central High School	Main School	R204		1
68	Central High School	Main School	R200		1
68	Central High School	Main School	R202		1
68	Central High School	Main School	R201		1
68	Central High School	Main School	Cafeteria		1
68	Central High School	Main School	Cafeteria		1
68	Central High School	Main School	R106		1
68	Central High School	Main School	R111		1
68	Central High School	Main School	R107		1
68	Central High School	Main School	R107		1
68	Central High School	Main School	Gym		1
68	Central High School	Main School	Gym		1
68	Central High School	Main School	Veight Room		1
68	Central High School	Main School	Veight Room		1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9209861	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	212		1	0.7
9209867	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	211		1	0.6
9209868	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	204		1	1.6
9209869	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	GYM		1	< 0.3
9209870	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	205-206		1	0.8
9209872	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	GYM		1	< 0.3
9209873	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	WEIGHT ROOM		1	
9209876	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	WEIGHT ROOM		1	1.1
9209878	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	211		1	0.6
9209879	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	205-206		1	0.6
9209880	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	212		1	0.8
9209881	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	209		1	0.8
9209882	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	200		1	1.5
9209883	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	210		1	0.9
9209886	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	202		1	1.0
9209887	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	208		1	0.6
9209889	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	207		1	1.2
9209891	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	208		1	0.8
9209892	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	107		1	1.2
9209893	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	201		1	1.4
9209894	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	CAFETERIA		1	1.0
9209895	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	107		1	1.8
9209897	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	106		1	0.9
9209898	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	CAFETERIA		1	0.8
9209899	2019-04-19	9:00 am	2019-04-22	5:00 pm	68	CENTRAL HIGH SCHOOL	MAIN SCHOOL	111		1	0.5

Columbian Elementary

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00
* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9209994	05/03/2019	10:00	05/06/2019	15:00
9209995	05/03/2019	10:00	05/06/2019	15:00
9220402	05/03/2019	10:00	05/06/2019	15:00
9220403	05/03/2019	10:00	05/06/2019	15:00
9220404	05/03/2019	10:00	05/06/2019	15:00
9220401	05/03/2019	10:00	05/06/2019	15:00
9220405	05/03/2019	10:00	05/06/2019	15:00
9220406	05/03/2019	10:00	05/06/2019	15:00
9220408	05/03/2019	10:00	05/06/2019	15:00
9220407	05/03/2019	10:00	05/06/2019	15:00
9220409	05/03/2019	10:00	05/06/2019	15:00
9220410	05/03/2019	10:00	05/06/2019	15:00
9220412	05/03/2019	10:00	05/06/2019	15:00
9220415	05/03/2019	10:00	05/06/2019	15:00
9220413	05/03/2019	10:00	05/06/2019	15:00
9220414	05/03/2019	10:00	05/06/2019	15:00
9220416	05/03/2019	10:00	05/06/2019	15:00
9220417	05/03/2019	10:00	05/06/2019	15:00
9220418	05/03/2019	10:00	05/06/2019	15:00
9220419	05/03/2019	10:00	05/06/2019	15:00
9220420	05/03/2019	10:00	05/06/2019	15:00
9220421	05/03/2019	10:00	05/06/2019	15:00
9220422	05/03/2019	10:00	05/06/2019	15:00
9220423	05/03/2019	10:00	05/06/2019	15:00
9220424	05/03/2019	10:00	05/06/2019	15:00
9220425	05/03/2019	10:00	05/06/2019	15:00
9220426	05/03/2019	10:00	05/06/2019	15:00
9220427	05/03/2019	10:00	05/06/2019	15:00
9220428	05/03/2019	10:00	05/06/2019	15:00
9220429	05/03/2019	10:00	05/06/2019	15:00
9220430	05/03/2019	10:00	05/06/2019	15:00
9220431	05/03/2019	10:00	05/06/2019	15:00
9220432	05/03/2019	10:00	05/06/2019	15:00
9220433	05/03/2019	10:00	05/06/2019	15:00
9220434	05/03/2019	10:00	05/06/2019	15:00
9220435	05/03/2019	10:00	05/06/2019	15:00
9220436	05/03/2019	10:00	05/06/2019	15:00
9220437	05/03/2019	10:00	05/06/2019	15:00
9220438	05/03/2019	10:00	05/06/2019	15:00
9220439	05/03/2019	10:00	05/06/2019	15:00

(+ / - 5 degrees) (your designations for facility, building and room)
 for example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=other

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Columbian	Main School	R44		1
68	Columbian	Main School	R42		1
68	Columbian	Main School	R40		1
68	Columbian	Main School	R38		1
68	Columbian	Main School	R39		1
68	Columbian	Main School	R37		1
68	Columbian	Main School	R35 C		1
68	Columbian	Main School	R35 B		1
68	Columbian	Main School	R35 A		1
68	Columbian	Main School	Media Center		1
68	Columbian	Main School	Media Center		1
68	Columbian	Main School	computer Lab		1
68	Columbian	Main School	R34		1
68	Columbian	Main School	R32		1
68	Columbian	Main School	R31		1
68	Columbian	Main School	R30		1
68	Columbian	Main School	R29		1
68	Columbian	Main School	R28		1
68	Columbian	Main School	R27		1
68	Columbian	Main School	R26		1
68	Columbian	Main School	R23		1
68	Columbian	Main School	R24		1
68	Columbian	Main School	R25		1
68	Columbian	Main School	R43		1
68	Columbian	Main School	R45		1
68	Columbian	Main School	R47		1
68	Columbian	Main School	R49		1
68	Columbian	Main School	R50		1
68	Columbian	Main School	R59		1
68	Columbian	Main School	R48		1
68	Columbian	Main School	Cafeteria		1
68	Columbian	Main School	Cafeteria		1
68	Columbian	Main School	R55		1
68	Columbian	Main School	R46		1
68	Columbian	Main School	R41		1
68	Columbian	Main School	Gym		1
68	Columbian	Main School	Gym		1
68	Columbian	Main School	Media Center		1
68	Columbian	Main School	R27		1
68	Columbian	Main School	R59		1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9209994	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	44		1	0.8
9209995	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	42		1	0.8
9220401	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	37		1	0.6
9220402	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	40		1	0.7
9220403	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	38		1	< 0.3
9220404	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	39		1	0.7
9220405	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	R35 C		1	0.5
9220406	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	R35 B		1	1.0
9220407	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	MEDIA CENTER		1	0.7
9220408	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	R35 A		1	1.1
9220409	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	MEDIA CENTER		1	1.0
9220410	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	COMPUTER LAB		1	0.8
9220412	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	34		1	0.6
9220413	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	31		1	1.4
9220414	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	30		1	1.2
9220415	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	32		1	2.5
9220416	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	29		1	< 0.3
9220417	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	28		1	0.8
9220418	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	27		1	0.6
9220419	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	26		1	< 0.3
9220420	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	23		1	< 0.3
9220421	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	24		1	0.6
9220422	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	25		1	0.6
9220423	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	43		1	< 0.3
9220424	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	45		1	0.5
9220425	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	47		1	0.6
9220426	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	49		1	0.6
9220427	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	50		1	0.7
9220428	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	59		1	0.5
9220429	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	48		1	0.6
9220430	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	CAFETERIA		1	0.7
9220431	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	CAFETERIA		1	0.7
9220432	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	55		1	1.0
9220433	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	46		1	0.8
9220434	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	41		1	0.6

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9220435	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	GYM		1	1.1
9220436	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	GYM		1	0.9
9220437	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	MEDIA CENTER		1	0.8
9220438	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	27		1	0.5
9220439	2019-05-03	10:00 am	2019-05-06	3:00 pm	68	COLUMBIAN	MAIN SCHOOL	59		1	0.5

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Corwin International

(from test kit)

Times should be in 24 hour format, 1pm = 13:00

(+ / - 5 degrees); (your designations for facility, building and room)

(optional)

(enter proper code)

*P.O. = Post Office

* round times so that 9:31 and 10:28 both display 10:00, for example

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>	<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
9210280	04/05/2019	14:00	04/08/2019	17:00	68	Corwin Int'l Magnet	Main School	R101		1st
9210267	04/05/2019	14:00	04/08/2019	17:00	68	Corwin Int'l Magnet	Main School	R103		1st
9210269	04/05/2019	14:00	04/08/2019	17:00	68	Corwin Int'l Magnet	Main School	R104		1st
9210228	04/05/2019	14:00	04/08/2019	17:00	68	Corwin Int'l Magnet	Main School	R105		1st
9210277	04/05/2019	14:00	04/08/2019	17:00	68	Corwin Int'l Magnet	Main School	R106		1st
9210268	04/05/2019	14:00	04/08/2019	17:00	68	Corwin Int'l Magnet	Main School	R107		1st
9210271	04/05/2019	15:00	04/08/2019	17:00	68	Corwin Int'l Magnet	Main School	R113		1st
9210247	04/05/2019	15:00	04/08/2019	17:00	68	Corwin Int'l Magnet	Main School	R113		1st
9210294	04/05/2019	15:00	04/08/2019	17:00	68	Corwin Int'l Magnet	Main School	R115		1st
9210279	04/05/2019	15:00	04/08/2019	17:00	68	Corwin Int'l Magnet	Main School	R117		1st
9210278	04/05/2019	15:00	04/08/2019	17:00	68	Corwin Int'l Magnet	Main School	R118		1st
9210270	04/05/2019	15:00	04/08/2019	17:00	68	Corwin Int'l Magnet	Main School	R116		1st
9210274	04/05/2019	15:00	04/08/2019	18:00	68	Corwin Int'l Magnet	Main School	Science Lab		1st
9210276	04/05/2019	15:00	04/08/2019	17:00	68	Corwin Int'l Magnet	Main School	Stage		1st
9210281	04/05/2019	15:00	04/08/2019	18:00	68	Corwin Int'l Magnet	Main School	R125		1st
9210284	04/05/2019	15:00	04/08/2019	18:00	68	Corwin Int'l Magnet	Main School	IT Lab		1st
9210275	04/05/2019	15:00	04/08/2019	18:00	68	Corwin Int'l Magnet	Main School	R128		1st
9210282	04/05/2019	15:00	04/08/2019	18:00	68	Corwin Int'l Magnet	Main School	Meeting Room		1st
9210266	04/05/2019	15:00	04/08/2019	18:00	68	Corwin Int'l Magnet	Main School	Meeting Room		1st
9210272	04/05/2019	15:00	04/08/2019	18:00	68	Corwin Int'l Magnet	Main School	R127		1st
9210286	04/05/2019	15:00	04/08/2019	18:00	68	Corwin Int'l Magnet	Main School	Ident Services		1st
9210295	04/05/2019	15:00	04/08/2019	18:00	68	Corwin Int'l Magnet	Main School	R132		1st
9210300	04/05/2019	16:00	04/08/2019	18:00	68	Corwin Int'l Magnet	Main School	R130		1st
9210287	04/05/2019	16:00	04/08/2019	18:00	68	Corwin Int'l Magnet	Main School	R130		1st
9210297	04/05/2019	16:00	04/08/2019	18:00	68	Corwin Int'l Magnet	Main School	Gym		1st
9210299	04/05/2019	16:00	04/08/2019	18:00	68	Corwin Int'l Magnet	Main School	Cafeteria		1st
9210290	04/05/2019	16:00	04/08/2019	18:00	68	Corwin Int'l Magnet	Main School	SW Gym		1st
9210291	04/05/2019	16:00	04/08/2019	18:00	68	Corwin Int'l Magnet	Main School	Office P.O.		1st
9210285	04/05/2019	16:00	04/08/2019	18:00	68	Corwin Int'l Magnet	Main School	Main Office		1st

Radon test result report for:
**CORWIN INT'L MAGNET
 MAIN SCHOOL**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9210299	CAFETERIA	2019-04-05 @ 4:00 pm	2019-04-08 @ 6:00 pm	1.1 ± 0.3	2019-04-10
9210297	GYM	2019-04-05 @ 4:00 pm	2019-04-08 @ 6:00 pm	2.6 ± 0.3	2019-04-10
9210284	IT LAB	2019-04-05 @ 3:00 pm	2019-04-08 @ 6:00 pm	< 0.3	2019-04-10
9210285	MAIN OFFICE	2019-04-05 @ 4:00 pm	2019-04-08 @ 6:00 pm	< 0.3	2019-04-10
9210266	MEETING ROOM	2019-04-05 @ 3:00 pm	2019-04-08 @ 6:00 pm	0.5 ± 0.3	2019-04-10
9210282	MEETING ROOM	2019-04-05 @ 3:00 pm	2019-04-08 @ 6:00 pm	0.5 ± 0.3	2019-04-10
9210291	OFFICE P.O.	2019-04-05 @ 4:00 pm	2019-04-08 @ 6:00 pm	< 0.3	2019-04-10
9210280	R101	2019-04-05 @ 2:00 pm	2019-04-08 @ 5:00 pm	< 0.3	2019-04-10
9210267	R103	2019-04-05 @ 2:00 pm	2019-04-08 @ 5:00 pm	< 0.3	2019-04-10
9210269	R104	2019-04-05 @ 2:00 pm	2019-04-08 @ 5:00 pm	< 0.3	2019-04-10
9210228	R105	2019-04-05 @ 2:00 pm	2019-04-08 @ 5:00 pm	< 0.3	2019-04-10
9210277	R106	2019-04-05 @ 2:00 pm	2019-04-08 @ 5:00 pm	0.6 ± 0.3	2019-04-10
9210268	R107	2019-04-05 @ 2:00 pm	2019-04-08 @ 5:00 pm	< 0.3	2019-04-10
9210271	R113	2019-04-05 @ 3:00 pm	2019-04-08 @ 5:00 pm	0.8 ± 0.3	2019-04-10
9210247	R113	2019-04-05 @ 3:00 pm	2019-04-08 @ 5:00 pm	< 0.3	2019-04-10
9210294	R115	2019-04-05 @ 3:00 pm	2019-04-08 @ 5:00 pm	< 0.3	2019-04-10
9210270	R116	2019-04-05 @ 3:00 pm	2019-04-08 @ 5:00 pm	0.9 ± 0.3	2019-04-10
9210279	R117	2019-04-05 @ 3:00 pm	2019-04-08 @ 5:00 pm	< 0.3	2019-04-10
9210278	R118	2019-04-05 @ 3:00 pm	2019-04-08 @ 5:00 pm	< 0.3	2019-04-10
9210272	R127	2019-04-05 @ 3:00 pm	2019-04-08 @ 6:00 pm	< 0.3	2019-04-10
9210275	R128	2019-04-05 @ 3:00 pm	2019-04-08 @ 6:00 pm	0.6 ± 0.3	2019-04-10
9210287	R130	2019-04-05 @ 4:00 pm	2019-04-08 @ 6:00 pm	0.5 ± 0.3	2019-04-10
9210300	R130	2019-04-05 @ 4:00 pm	2019-04-08 @ 6:00 pm	0.7 ± 0.3	2019-04-10
9210295	R132	2019-04-05 @ 3:00 pm	2019-04-08 @ 6:00 pm	< 0.3	2019-04-10
9210274	SCIENCE LAB	2019-04-05 @ 3:00 pm	2019-04-08 @ 6:00 pm	0.7 ± 0.3	2019-04-10
9210276	STAGE	2019-04-05 @ 3:00 pm	2019-04-08 @ 5:00 pm	1.0 ± 0.3	2019-04-10
9210286	STUDENT SERVICES	2019-04-05 @ 3:00 pm	2019-04-08 @ 6:00 pm	< 0.3	2019-04-10
9210290	SW GYM	2019-04-05 @ 4:00 pm	2019-04-08 @ 6:00 pm	< 0.3	2019-04-10

Data Center

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00
* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9220563	05/08/2019	14:00	05/10/2019	14:00
9220565	05/08/2019	14:00	05/10/2019	14:00
9220569	05/08/2019	14:00	05/10/2019	14:00
9220566	05/08/2019	14:00	05/10/2019	14:00
9220570	05/08/2019	15:00	05/10/2019	14:00
9220574	05/08/2019	15:00	05/10/2019	14:00
9220575	05/08/2019	15:00	05/10/2019	14:00
9220576	05/08/2019	15:00	05/10/2019	14:00
9220571	05/08/2019	15:00	05/10/2019	14:00
9220572	05/08/2019	15:00	05/10/2019	14:00

(+ / - 5 degrees) (your designations for facility, building and room) (optional) (enter proper code)
 r example 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Data Center	Main Building	Support Area		1
68	Data Center	Main Building	anda's Office		1
68	Data Center	Main Building	anda's Office		1
68	Data Center	Main Building	k Tobey's Office		1
68	Data Center	Main Building	Office 07A		1
68	Data Center	Main Building	Rm 107B		1
68	Data Center	Main Building	onference Rm		1
68	Data Center	Main Building	ronica's Office		1
68	Data Center	Main Building	Janitors Rm		1
68	Data Center	Main Building	IT Rm		1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9220563	2019-05-08	2:00 pm	2019-05-10	2:00 pm	68	DATA CENTER	MAIN BUILDING	SUPPORT AREA		1	0.7
9220565	2019-05-08	2:00 pm	2019-05-10	2:00 pm	68	DATA CENTER	MAIN BUILDING	VANDA'S OFFICE		1	1.0
9220566	2019-05-08	2:00 pm	2019-05-10	2:00 pm	68	DATA CENTER	MAIN BUILDING	MARK TOBEY'S OFFICE		1	0.8
9220569	2019-05-08	2:00 pm	2019-05-10	2:00 pm	68	DATA CENTER	MAIN BUILDING	VANDA'S OFFICE		1	0.6
9220570	2019-05-08	3:00 pm	2019-05-10	2:00 pm	68	DATA CENTER	MAIN BUILDING	OFFICE 07A		1	0.6
9220571	2019-05-08	3:00 pm	2019-05-10	2:00 pm	68	DATA CENTER	MAIN BUILDING	JANITORS RM		1	0.9
9220572	2019-05-08	3:00 pm	2019-05-10	2:00 pm	68	DATA CENTER	MAIN BUILDING	IT RM		1	1.5
9220574	2019-05-08	3:00 pm	2019-05-10	2:00 pm	68	DATA CENTER	MAIN BUILDING	RM 107B		1	1.0
9220575	2019-05-08	3:00 pm	2019-05-10	2:00 pm	68	DATA CENTER	MAIN BUILDING	CONFERENCE RM		1	0.8
9220576	2019-05-08	3:00 pm	2019-05-10	2:00 pm	68	DATA CENTER	MAIN BUILDING	VERONICA'S OFFICE		1	0.8

East High School

(from test kit)

Times should be in 24 hour format, 1pm = 13:00

* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9226092	05/21/2019	16:00	05/23/2019	16:00
9226093	05/21/2019	16:00	05/23/2019	16:00
9226094	05/21/2019	16:00	05/23/2019	16:00
9226085	05/21/2019	16:00	05/23/2019	16:00
9226089	05/21/2019	16:00	05/23/2019	16:00
9226086	05/21/2019	16:00	05/23/2019	16:00
9226090	05/21/2019	16:00	05/23/2019	16:00
9226097	05/21/2019	16:00	05/23/2019	16:00
9226091	05/21/2019	16:00	05/23/2019	16:00
9226095	05/21/2019	16:00	05/23/2019	16:00
9226098	05/21/2019	16:00	05/23/2019	16:00
9227303	05/21/2019	16:00	05/23/2019	16:00
9226096	05/21/2019	16:00	05/23/2019	16:00
9227304	05/21/2019	16:00	05/23/2019	16:00
9227305	05/21/2019	16:00	05/23/2019	16:00
9226099	05/21/2019	16:00	05/23/2019	16:00
9227306	05/21/2019	16:00	05/23/2019	16:00
9227301	05/21/2019	16:00	05/23/2019	16:00
9227313	05/21/2019	16:00	05/23/2019	16:00
9227302	05/21/2019	16:00	05/23/2019	16:00
9227307	05/21/2019	16:00	05/23/2019	16:00
9227308	05/21/2019	16:00	05/23/2019	16:00
9227309	05/21/2019	16:00	05/23/2019	16:00
9227314	05/21/2019	16:00	05/23/2019	16:00
9227311	05/21/2019	16:00	05/23/2019	16:00
9227312	05/21/2019	16:00	05/23/2019	16:00
9227310	05/21/2019	16:00	05/23/2019	16:00
9227317	05/21/2019	16:00	05/23/2019	16:00
9227318	05/21/2019	16:00	05/23/2019	16:00
9227319	05/21/2019	16:00	05/23/2019	16:00
9227315	05/21/2019	16:00	05/23/2019	16:00
9227321	05/21/2019	16:00	05/23/2019	16:00
9227325	05/21/2019	16:00	05/23/2019	16:00
9227316	05/21/2019	16:00	05/23/2019	16:00
9227322	05/21/2019	16:00	05/23/2019	16:00
9227323	05/21/2019	16:00	05/23/2019	16:00
9227324	05/21/2019	16:00	05/23/2019	16:00
9227326	05/21/2019	16:00	05/23/2019	16:00
9227327	05/21/2019	16:00	05/23/2019	16:00
9227329	05/21/2019	16:00	05/23/2019	16:00
9227328	05/21/2019	16:00	05/23/2019	16:00
9227330	05/21/2019	16:00	05/23/2019	16:00
9227331	05/21/2019	16:00	05/23/2019	16:00
9227332	05/21/2019	16:00	05/23/2019	16:00
9226100	05/21/2019	16:00	05/23/2019	16:00

TAB]

9227333	05/21/2019	16:00	05/23/2019	16:00
9227334	05/21/2019	16:00	05/23/2019	16:00
9227335	05/21/2019	16:00	05/23/2019	16:00
9227337	05/21/2019	16:00	05/23/2019	16:00
9227338	05/21/2019	16:00	05/23/2019	16:00
9227339	05/21/2019	16:00	05/23/2019	16:00
9227341	05/21/2019	16:00	05/23/2019	16:00
9227340	05/21/2019	16:00	05/23/2019	16:00
9227342	05/21/2019	16:00	05/23/2019	16:00
9227343	05/21/2019	16:00	05/23/2019	16:00
9227344	05/21/2019	16:00	05/23/2019	16:00
9227345	05/21/2019	16:00	05/23/2019	16:00
9227346	05/21/2019	16:00	05/23/2019	16:00
9227347	05/21/2019	16:00	05/23/2019	16:00
9227348	05/21/2019	16:00	05/23/2019	16:00
9227349	05/21/2019	16:00	05/23/2019	16:00
9227350	05/21/2019	16:00	05/23/2019	16:00
9227351	05/21/2019	16:00	05/23/2019	16:00
9227352	05/21/2019	16:00	05/23/2019	16:00
9227353	05/21/2019	16:00	05/23/2019	16:00
9227354	05/21/2019	16:00	05/23/2019	16:00
9227355	05/21/2019	16:00	05/23/2019	16:00
9227356	05/21/2019	16:00	05/23/2019	16:00
9227357	05/21/2019	16:00	05/23/2019	16:00
9227358	05/21/2019	16:00	05/23/2019	16:00
9227359	05/21/2019	16:00	05/23/2019	16:00
9227360	05/21/2019	16:00	05/23/2019	16:00
9227362	05/21/2019	16:00	05/23/2019	16:00
9227363	05/21/2019	16:00	05/23/2019	16:00
9227361	05/21/2019	16:00	05/23/2019	16:00
9227364	05/21/2019	16:00	05/23/2019	16:00
9227365	05/21/2019	16:00	05/23/2019	16:00
9227366	05/21/2019	16:00	05/23/2019	16:00
9227371	05/21/2019	16:00	05/23/2019	16:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	East Highschool	Main School	Cafeteria		1
68	East Highschool	Main School	Cafeteria		1
68	East Highschool	Main School	R42		1
68	East Highschool	Main School	R42		1
68	East Highschool	Main School	R44		1
68	East Highschool	Main School	R81		1
68	East Highschool	Main School	R39		1
68	East Highschool	Main School	R32		1
68	East Highschool	Main School	R2		1
68	East Highschool	Main School	R4		1
68	East Highschool	Main School	R5		1
68	East Highschool	Main School	R50		1
68	East Highschool	Main School	R51B		1
68	East Highschool	Main School	R57		1
68	East Highschool	Main School	R53		1
68	East Highschool	Main School	R53		1
68	East Highschool	Main School	R54		1
68	East Highschool	Main School	R6		1
68	East Highschool	Main School	R8		1
68	East Highschool	Main School	R51A		1
68	East Highschool	Main School	Media		1
68	East Highschool	Main School	Media		1
68	East Highschool	Main School	R55		1
68	East Highschool	Main School	R77		1
68	East Highschool	Main School	R73		1
68	East Highschool	Main School	R71		1
68	East Highschool	Main School	R64		1
68	East Highschool	Main School	R66		1
68	East Highschool	Main School	R61		1
68	East Highschool	Main School	R17		1
68	East Highschool	Main School	R16		1
68	East Highschool	Main School	R14		1
68	East Highschool	Main School	R13		1
68	East Highschool	Main School	R12		1
68	East Highschool	Main School	R11		1
68	East Highschool	Main School	R11		1
68	East Highschool	Main School	R11		1
68	East Highschool	Main School	R22		1
68	East Highschool	Main School	R18		1
68	East Highschool	Main School	R19		1
68	East Highschool	Main School	R20		1
68	East Highschool	Main School	R21		1
68	East Highschool	Main School	R9		1
68	East Highschool	Main School	R7		1
68	East Highschool	Main School	R10		1

TAB]

68	East Highschool	Main School	R3	1
68	East Highschool	Main School	R52	1
68	East Highschool	Main School	R58	1
68	East Highschool	Main School	R67	1
68	East Highschool	Main School	R65	1
68	East Highschool	Main School	R63	1
68	East Highschool	Main School	R62	1
68	East Highschool	Main School	R60	1
68	East Highschool	Main School	R24	1
68	East Highschool	Main School	R23	1
68	East Highschool	Main School	R26	1
68	East Highschool	Main School	R25	1
68	East Highschool	Main School	R25	1
68	East Highschool	Main School	R28	1
68	East Highschool	Main School	R27	1
68	East Highschool	Main School	R30	1
68	East Highschool	Main School	R29	1
68	East Highschool	Main School	R35	1
68	East Highschool	Main School	R31	1
68	East Highschool	Main School	R34	1
68	East Highschool	Main School	R37	1
68	East Highschool	Main School	R36	1
68	East Highschool	Main School	R38	1
68	East Highschool	Main School	R38	1
68	East Highschool	Main School	R40	1
68	East Highschool	Main School	R40	1
68	East Highschool	Main School	R41	1
68	East Highschool	Main School	R45	1
68	East Highschool	Main School	Veight Room	1
68	East Highschool	Main School	Veight Room	1
68	East Highschool	Main School	Gym 1	1
68	East Highschool	Main School	Gym 1	1
68	East Highschool	Main School	Gym 2	1
68	East Highschool	Main School	Gym 2	1

Radon test result report for:
**EAST HIGHSCHOOL
 MAIN SCHOOL**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9226100	10	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	2.3 ± 0.3	2019-05-24
9227324	11	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.5 ± 0.3	2019-05-24
9227322	11	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.6 ± 0.3	2019-05-24
9227323	11	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.8 ± 0.3	2019-05-24
9227316	12	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.1 ± 0.3	2019-05-24
9227325	13	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.4 ± 0.3	2019-05-24
9227321	14	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.6 ± 0.3	2019-05-24
9227315	16	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.9 ± 0.3	2019-05-24
9227319	17	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.7 ± 0.3	2019-05-24
9227327	18	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.3 ± 0.3	2019-05-24
9227329	19	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.8 ± 0.3	2019-05-24
9227328	20	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.7 ± 0.3	2019-05-24
9227330	21	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.2 ± 0.3	2019-05-24
9227326	22	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	2.1 ± 0.3	2019-05-24
9227343	23	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.7 ± 0.3	2019-05-24
9227342	24	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	2.0 ± 0.3	2019-05-24
9227345	25	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.8 ± 0.3	2019-05-24
9227346	25	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.8 ± 0.3	2019-05-24
9227344	26	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.7 ± 0.3	2019-05-24
9227348	27	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	2.1 ± 0.3	2019-05-24
9227347	28	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	2.0 ± 0.3	2019-05-24
9227350	29	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.6 ± 0.3	2019-05-24
9227333	3	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.9 ± 0.3	2019-05-24
9227349	30	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.5 ± 0.3	2019-05-24
9227352	31	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.2 ± 0.3	2019-05-24
9226097	32	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.2 ± 0.3	2019-05-24
9227353	34	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.0 ± 0.3	2019-05-24
9227351	35	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.8 ± 0.3	2019-05-24
9227355	36	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.6 ± 0.3	2019-05-24
9227354	37	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.2 ± 0.3	2019-05-24
9227357	38	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	2.4 ± 0.3	2019-05-24
9227356	38	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.9 ± 0.3	2019-05-24
9226090	39	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.3 ± 0.3	2019-05-24
9226095	4	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	2.0 ± 0.3	2019-05-24
9227358	40	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	2.0 ± 0.3	2019-05-24
9227359	40	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	2.3 ± 0.3	2019-05-24
9227360	41	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	0.9 ± 0.3	2019-05-24

Radon test result report for:
**EAST HIGHSCHOOL
 MAIN SCHOOL**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9226085	42	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.5 ± 0.3	2019-05-24
9226094	42	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.6 ± 0.3	2019-05-24
9226089	44	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	2.0 ± 0.3	2019-05-24
9227362	45	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.8 ± 0.3	2019-05-24
9226098	5	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	2.2 ± 0.3	2019-05-24
9227303	50	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.1 ± 0.3	2019-05-24
9227334	52	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.2 ± 0.3	2019-05-24
9227305	53	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	2.5 ± 0.3	2019-05-24
9226099	53	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	2.3 ± 0.3	2019-05-24
9227306	54	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	3.3 ± 0.4	2019-05-24
9227309	55	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	3.2 ± 0.4	2019-05-24
9227304	57	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	5.5 ± 0.4	2019-05-24
9227335	58	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	5.4 ± 0.4	2019-05-24
9227301	6	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.9 ± 0.3	2019-05-24
9227340	60	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.1 ± 0.3	2019-05-24
9227318	61	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.3 ± 0.3	2019-05-24
9227341	62	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	0.9 ± 0.3	2019-05-24
9227339	63	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	2.0 ± 0.3	2019-05-24
9227310	64	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.1 ± 0.3	2019-05-24
9227338	65	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.4 ± 0.3	2019-05-24
9227317	66	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.1 ± 0.3	2019-05-24
9227337	67	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.2 ± 0.3	2019-05-24
9227332	7	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.8 ± 0.3	2019-05-24
9227312	71	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	0.8 ± 0.3	2019-05-24
9227311	73	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	0.8 ± 0.3	2019-05-24
9227314	77	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.3 ± 0.3	2019-05-24
9227313	8	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.9 ± 0.3	2019-05-24
9226086	81	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	2.1 ± 0.3	2019-05-24
9227331	9	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	2.1 ± 0.3	2019-05-24
9226092	CAFETERIA	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	2.6 ± 0.3	2019-05-24
9226093	CAFETERIA	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	2.7 ± 0.3	2019-05-24
9227364	GYM 1	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.4 ± 0.3	2019-05-24
9227365	GYM 1	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.4 ± 0.3	2019-05-24
9227371	GYM 2	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.8 ± 0.3	2019-05-24
9227366	GYM 2	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.8 ± 0.3	2019-05-24
9227307	MEDIA	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	< 0.3	2019-05-24
9227308	MEDIA	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	0.5 ± 0.3	2019-05-24

May 28, 2019

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:
**EAST HIGH SCHOOL
MAIN SCHOOL**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9227302	R51A	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.9 ± 0.3	2019-05-24
9226096	R51B	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.8 ± 0.3	2019-05-24
9227361	WEIGHT ROOM	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.9 ± 0.3	2019-05-24
9227363	WEIGHT ROOM	2019-05-21 @ 4:00 pm	2019-05-23 @ 4:00 pm	1.6 ± 0.3	2019-05-24

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Fountain International

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00
* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9220440	05/03/2019	11:00	05/06/2019	15:00
9220441	05/03/2019	11:00	05/06/2019	15:00
9220442	05/03/2019	11:00	05/06/2019	15:00
9220443	05/03/2019	11:00	05/06/2019	15:00
9220444	05/03/2019	11:00	05/06/2019	15:00
9220445	05/03/2019	11:00	05/06/2019	15:00
9220446	05/03/2019	11:00	05/06/2019	15:00
9220449	05/03/2019	11:00	05/06/2019	15:00
9220447	05/03/2019	11:00	05/06/2019	15:00
9220448	05/03/2019	11:00	05/06/2019	15:00
9220450	05/03/2019	11:00	05/06/2019	15:00
9220451	05/03/2019	11:00	05/06/2019	15:00
9220452	05/03/2019	11:00	05/06/2019	15:00
9220453	05/03/2019	11:00	05/06/2019	15:00
9220454	05/03/2019	11:00	05/06/2019	15:00
9220455	05/03/2019	11:00	05/06/2019	15:00
9220456	05/03/2019	11:00	05/06/2019	15:00
9220459	05/03/2019	11:00	05/06/2019	15:00
9220457	05/03/2019	11:00	05/06/2019	15:00
9220458	05/03/2019	11:00	05/06/2019	15:00
9220460	05/03/2019	11:00	05/06/2019	15:00
9220461	05/03/2019	11:00	05/06/2019	15:00
9220462	05/03/2019	11:00	05/06/2019	15:00
9220463	05/03/2019	11:00	05/06/2019	15:00
9220464	05/03/2019	11:00	05/06/2019	15:00
9220465	05/03/2019	11:00	05/06/2019	15:00
9220466	05/03/2019	11:00	05/06/2019	15:00
9220467	05/03/2019	11:00	05/06/2019	15:00
9220468	05/03/2019	11:00	05/06/2019	15:00
9220470	05/03/2019	11:00	05/06/2019	15:00
9220469	05/03/2019	11:00	05/06/2019	15:00
9220471	05/03/2019	11:00	05/06/2019	15:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Fountain	Main School	R1		1
68	Fountain	Main School	R2		1
68	Fountain	Main School	R3		1
68	Fountain	Main School	R42		1
68	Fountain	Main School	Media Center		1
68	Fountain	Main School	Media Center		1
68	Fountain	Main School	R14		1
68	Fountain	Main School	R10		1
68	Fountain	Main School	R13		1
68	Fountain	Main School	R11		1
68	Fountain	Main School	R25		1
68	Fountain	Main School	R44		1
68	Fountain	Main School	R44		1
68	Fountain	Main School	R20		1
68	Fountain	Main School	R21		1
68	Fountain	Main School	R22		1
68	Fountain	Main School	R23		1
68	Fountain	Main School	R45		1
68	Fountain	Main School	R36		1
68	Fountain	Main School	R30		1
68	Fountain	Main School	R30		1
68	Fountain	Main School	R37		1
68	Fountain	Main School	R35		1
68	Fountain	Main School	R32		1
68	Fountain	Main School	R34		1
68	Fountain	Main School	R54		1
68	Fountain	Main School	Cafeteria		1
68	Fountain	Main School	Cafeteria		1
68	Fountain	Main School	R52		1
68	Fountain	Main School	Gym		1
68	Fountain	Main School	Gym		1
68	Fountain	Main School	Gym		1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9220440	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	1		1	1.6
9220441	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	2		1	1.3
9220442	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	3		1	1.4
9220443	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	42		1	0.9
9220444	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	MEDIA CENTER		1	1.5
9220445	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	MDEIA CENTER		1	1.3
9220446	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	14		1	0.7
9220447	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	13		1	1.1
9220448	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	11		1	0.9
9220449	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	10		1	1.0
9220450	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	25		1	< 0.3
9220451	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	44		1	1.3
9220452	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	44		1	1.0
9220453	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	20		1	0.5
9220454	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	21		1	< 0.3
9220455	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	22		1	< 0.3
9220456	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	23		1	0.6
9220457	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	36		1	1.1
9220458	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	30		1	0.8
9220459	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	45		1	1.2
9220460	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	30		1	0.9
9220461	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	37		1	0.9
9220462	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	35		1	0.9
9220463	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	32		1	1.1
9220464	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	34		1	1.4
9220465	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	54		1	1.0
9220466	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	CAFETERIA		1	1.3
9220467	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	CAFETERIA		1	1.2
9220468	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	52		1	1.3
9220469	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	GYM		1	1.2
9220470	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	GYM		1	1.1
9220471	2019-05-03	11:00 am	2019-05-06	3:00 pm	68	FOUNTAIN	MAIN SCHOOL	GYM		1	1.0

Franklin Elementary

*(from test kit)**Times should be in 24 hour format, 1pm = 13:00*** round times so that 9:31 and 10:28 both display 10:00, fo*

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
7258327	06/07/2019	14:00	06/10/2019	15:00
7258328	06/07/2019	14:00	06/10/2019	15:00
7258329	06/07/2019	14:00	06/10/2019	15:00
7258333	06/07/2019	14:00	06/10/2019	15:00
7258330	06/07/2019	14:00	06/10/2019	15:00
7258331	06/07/2019	14:00	06/10/2019	15:00
7258332	06/07/2019	14:00	06/10/2019	15:00
7258334	06/07/2019	14:00	06/10/2019	15:00
7258335	06/07/2019	14:00	06/10/2019	15:00
7258336	06/07/2019	14:00	06/10/2019	15:00
7258337	06/07/2019	14:00	06/10/2019	15:00
7258338	06/07/2019	14:00	06/10/2019	15:00
7258339	06/07/2019	14:00	06/10/2019	15:00
7258340	06/07/2019	14:00	06/10/2019	15:00
7258341	06/07/2019	14:00	06/10/2019	15:00
7258342	06/07/2019	14:00	06/10/2019	15:00
7258343	06/07/2019	14:00	06/10/2019	15:00
7258344	06/07/2019	14:00	06/10/2019	15:00
7258345	06/07/2019	14:00	06/10/2019	15:00
7258346	06/07/2019	14:00	06/10/2019	15:00
7258347	06/07/2019	14:00	06/10/2019	15:00
7258348	06/07/2019	14:00	06/10/2019	15:00
7258349	06/07/2019	14:00	06/10/2019	15:00
7258350	06/07/2019	14:00	06/10/2019	15:00
7258351	06/07/2019	14:00	06/10/2019	15:00
7258352	06/07/2019	14:00	06/10/2019	15:00
7258353	06/07/2019	14:00	06/10/2019	15:00
7258354	06/07/2019	14:00	06/10/2019	15:00
7258355	06/07/2019	14:00	06/10/2019	15:00
7258356	06/07/2019	14:00	06/10/2019	15:00
7258357	06/07/2019	14:00	06/10/2019	15:00
7258358	06/07/2019	14:00	06/10/2019	15:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Frankland	Main School	R6		1
68	Frankland	Main School	R5		1
68	Frankland	Main School	R3		1
68	Frankland	Main School	R4		1
68	Frankland	Main School	R1		1
68	Frankland	Main School	R2		1
68	Frankland	Main School	RA		1
68	Frankland	Main School	RB		1
68	Frankland	Main School	Gym		1
68	Frankland	Main School	Gym		1
68	Frankland	Main School	Media		1
68	Frankland	Main School	Media		1
68	Frankland	Main School	Small Group		1
68	Frankland	Main School	R21		1
68	Frankland	Main School	R16		1
68	Frankland	Main School	R15		1
68	Frankland	Main School	R15		1
68	Frankland	Main School	R18		1
68	Frankland	Main School	R17		1
68	Frankland	Main School	R20		1
68	Frankland	Main School	Cafeteria		1
68	Frankland	Main School	Multi Purpose		1
68	Frankland	Main School	Cafeteria		1
68	Frankland	Main School	Cafeteria		1
68	Frankland	Main School	R8		1
68	Frankland	Main School	R9		1
68	Frankland	Main School	R10		1
68	Frankland	Main School	R12		1
68	Frankland	Main School	R12		1
68	Frankland	Main School	R11		1
68	Frankland	Main School	R14		1
68	Frankland	Main School	R13		1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
7258327	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	6		1	0.6
7258328	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	5		1	< 0.3
7258329	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	3		1	0.5
7258330	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	1		1	< 0.3
7258331	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	2		1	< 0.3
7258332	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	RA		1	< 0.3
7258333	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	4		1	< 0.3
7258334	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	RB		1	0.5
7258335	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	GYM		1	< 0.3
7258336	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	GYM		1	< 0.3
7258337	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	MEDIA		1	< 0.3
7258338	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	MEDIA		1	< 0.3
7258339	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	SMALL GROUP		1	< 0.3
7258340	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	21		1	< 0.3
7258341	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	16		1	< 0.3
7258342	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	15		1	< 0.3
7258343	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	15		1	< 0.3
7258344	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	18		1	< 0.3
7258345	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	17		1	< 0.3
7258346	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	20		1	< 0.3
7258347	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	CAFETERIA		1	0.5
7258348	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	MULTI PURPOSE		1	0.8
7258349	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	CAFETERIA		1	0.9
7258350	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	CAFETERIA		1	0.8
7258351	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	8		1	0.5
7258352	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	9		1	0.7
7258353	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	10		1	0.6
7258354	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	12		1	0.5
7258355	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	12		1	0.7
7258356	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	11		1	0.7
7258357	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	14		1	< 0.3
7258358	2019-06-07	2:00 pm	2019-06-10	3:00 pm	68	FRANKLAND	MAIN SCHOOL	13		1	0.8

Fulton Heights

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00
* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
7258359	06/07/2019	15:00	06/10/2019	15:00
7258360	06/07/2019	15:00	06/10/2019	15:00
7258363	06/07/2019	15:00	06/10/2019	15:00
7258361	06/07/2019	15:00	06/10/2019	15:00
7258362	06/07/2019	15:00	06/10/2019	15:00
7258364	06/07/2019	15:00	06/10/2019	15:00
7258365	06/07/2019	15:00	06/10/2019	15:00
7258366	06/07/2019	15:00	06/10/2019	15:00
7258367	06/07/2019	15:00	06/10/2019	15:00
7258368	06/07/2019	15:00	06/10/2019	15:00
7258369	06/07/2019	15:00	06/10/2019	15:00
7258370	06/07/2019	15:00	06/10/2019	15:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=oth

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Fulton Heights	Main School	R20		1
68	Fulton Heights	Main School	R26		1
68	Fulton Heights	Main School	R24		1
68	Fulton Heights	Main School	R25		1
68	Fulton Heights	Main School	R22		1
68	Fulton Heights	Main School	R24		1
68	Fulton Heights	Main School	R23		1
68	Fulton Heights	Main School	Cafeteria		1
68	Fulton Heights	Main School	Cafeteria		1
68	Fulton Heights	Main School	Cafeteria		1
68	Fulton Heights	Main School	R10		1
68	Fulton Heights	Main School	R11		1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
7258359	2019-06-07	3:00 pm	2019-06-10	3:00 pm	68	FULTON HEIGHTS	MAIN SCHOOL	20		1	1.6
7258360	2019-06-07	3:00 pm	2019-06-10	3:00 pm	68	FULTON HEIGHTS	MAIN SCHOOL	26		1	0.8
7258361	2019-06-07	3:00 pm	2019-06-10	3:00 pm	68	FULTON HEIGHTS	MAIN SCHOOL	25		1	0.7
7258362	2019-06-07	3:00 pm	2019-06-10	3:00 pm	68	FULTON HEIGHTS	MAIN SCHOOL	22		1	0.5
7258363	2019-06-07	3:00 pm	2019-06-10	3:00 pm	68	FULTON HEIGHTS	MAIN SCHOOL	24		1	< 0.3
7258364	2019-06-07	3:00 pm	2019-06-10	3:00 pm	68	FULTON HEIGHTS	MAIN SCHOOL	24		1	0.8
7258365	2019-06-07	3:00 pm	2019-06-10	3:00 pm	68	FULTON HEIGHTS	MAIN SCHOOL	23		1	0.5
7258366	2019-06-07	3:00 pm	2019-06-10	3:00 pm	68	FULTON HEIGHTS	MAIN SCHOOL	CAFETERIA		1	1.0
7258367	2019-06-07	3:00 pm	2019-06-10	3:00 pm	68	FULTON HEIGHTS	MAIN SCHOOL	CAFETERIA		1	0.9
7258368	2019-06-07	3:00 pm	2019-06-10	3:00 pm	68	FULTON HEIGHTS	MAIN SCHOOL	CAFETERIA		1	1.0
7258369	2019-06-07	3:00 pm	2019-06-10	3:00 pm	68	FULTON HEIGHTS	MAIN SCHOOL	10		1	1.3
7258370	2019-06-07	3:00 pm	2019-06-10	3:00 pm	68	FULTON HEIGHTS	MAIN SCHOOL	11		1	1.2

Goodnight Elementary

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00

* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9209760	04/23/2019	17:00	04/25/2019	17:00
9209750	04/23/2019	17:00	04/25/2019	17:00
9209751	04/23/2019	17:00	04/25/2019	17:00
9209755	04/23/2019	17:00	04/25/2019	17:00
9209756	04/23/2019	17:00	04/25/2019	17:00
9209761	04/23/2019	17:00	04/25/2019	17:00
9209763	04/23/2019	17:00	04/25/2019	17:00
9209757	04/23/2019	17:00	04/25/2019	17:00
9209758	04/23/2019	17:00	04/25/2019	17:00
9209768	04/23/2019	17:00	04/25/2019	17:00
9209767	04/23/2019	17:00	04/25/2019	17:00
9209769	04/23/2019	17:00	04/25/2019	17:00
9209774	04/23/2019	17:00	04/25/2019	17:00
9209766	04/23/2019	17:00	04/25/2019	17:00
9209770	04/23/2019	17:00	04/25/2019	17:00
9209771	04/23/2019	17:00	04/25/2019	17:00
9209776	04/23/2019	17:00	04/25/2019	17:00
9209777	04/23/2019	17:00	04/25/2019	17:00
9209764	04/23/2019	17:00	04/25/2019	17:00
9209772	04/23/2019	17:00	04/25/2019	17:00
9209773	04/23/2019	17:00	04/25/2019	17:00
9209775	04/23/2019	17:00	04/25/2019	17:00
9209780	04/23/2019	17:00	04/25/2019	17:00
9209779	04/23/2019	17:00	04/25/2019	17:00
9209778	04/23/2019	17:00	04/25/2019	17:00
9209781	04/23/2019	17:00	04/25/2019	17:00
9209782	04/23/2019	17:00	04/25/2019	17:00
9209783	04/23/2019	17:00	04/25/2019	17:00
9209784	04/23/2019	17:00	04/25/2019	17:00
9209785	04/23/2019	17:00	04/25/2019	17:00
9209788	04/23/2019	17:00	04/25/2019	17:00
9209789	04/23/2019	17:00	04/25/2019	17:00
9209790	04/23/2019	17:00	04/25/2019	17:00
9209786	04/23/2019	17:00	04/25/2019	17:00
9209787	04/23/2019	17:00	04/25/2019	17:00
9209791	04/23/2019	17:00	04/25/2019	17:00
9209796	04/23/2019	17:00	04/25/2019	17:00
9209794	04/23/2019	17:00	04/25/2019	17:00
9209797	04/23/2019	17:00	04/25/2019	17:00
9209798	04/23/2019	17:00	04/25/2019	17:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Goodnight	Main School	R2		1
68	Goodnight	Main School	DR LGAL		1
68	Goodnight	Main School	R00		1
68	Goodnight	Main School	R3		1
68	Goodnight	Main School	R2		1
68	Goodnight	Main School	Cafeteria		1
68	Goodnight	Main School	Cafeteria		1
68	Goodnight	Main School	Library		1
68	Goodnight	Main School	Library		1
68	Goodnight	Main School	R15		1
68	Goodnight	Main School	R17		1
68	Goodnight	Main School	R16		1
68	Goodnight	Main School	R14		1
68	Goodnight	Main School	R22		1
68	Goodnight	Main School	R21		1
68	Goodnight	Main School	R23		1
68	Goodnight	Main School	Nurse		1
68	Goodnight	Main School	Well		1
68	Goodnight	Main School	Musso		1
68	Goodnight	Main School	R53		1
68	Goodnight	Main School	HOS		1
68	Goodnight	Main School	Music		1
68	Goodnight	Main School	Spanish		1
68	Goodnight	Main School	R43		1
68	Goodnight	Main School	Sandstorm		1
68	Goodnight	Main School	Thielbar		1
68	Goodnight	Main School	R33		1
68	Goodnight	Main School	R32		1
68	Goodnight	Main School	R41		1
68	Goodnight	Main School	Science		1
68	Goodnight	Main School	HilleBearnd		1
68	Goodnight	Main School	omputer Room		1
68	Goodnight	Main School	Moduler 25		1
68	Goodnight	Main School	Moduler 24		1
68	Goodnight	Main School	Moduler 23		1
68	Goodnight	Main School	Moduler 22		1
68	Goodnight	Main School	Moduler 21		1
68	Goodnight	Main School	Moduler 20		1
68	Goodnight	Main School	oduler Shurse		1
68	Goodnight	Main School	oduler Attento		1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9209750	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	DR LGAL		1	0.7
9209751	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	R00		1	0.8
9209755	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	3		1	0.8
9209756	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	2		1	0.8
9209757	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	LIBRARY		1	< 0.3
9209758	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	LIBRARY		1	0.6
9209760	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	2		1	0.8
9209761	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	CAFETERIA		1	0.9
9209763	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	CAFETERIA		1	1.2
9209764	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	MUSSO		1	0.7
9209766	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	22		1	0.6
9209767	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	17		1	0.5
9209768	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	15		1	< 0.3
9209769	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	16		1	0.7
9209770	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	21		1	< 0.3
9209771	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	23		1	0.5
9209772	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	53		1	< 0.3
9209773	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	HOS		1	0.7
9209774	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	14		1	< 0.3
9209775	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	MUSIC		1	< 0.3
9209776	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	NURSE		1	0.7
9209777	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	WELL		1	< 0.3
9209778	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	SANDSTORM		1	< 0.3
9209779	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	43		1	0.6
9209780	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	SPANISH		1	0.5
9209781	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	THIELBAR		1	< 0.3
9209782	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	33		1	< 0.3
9209783	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	32		1	< 0.3
9209784	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	41		1	< 0.3
9209785	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	SCIENCE		1	< 0.3
9209786	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	MODULER 24		1	< 0.3
9209787	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	MODULER 23		1	< 0.3
9209788	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	HILLEBEARND		1	< 0.3
9209789	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	COMPUTER ROOM		1	0.7
9209790	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	MODULER 25		1	0.5

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9209791	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	MODULER 22		1	< 0.3
9209794	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	MODULER 20		1	< 0.3
9209796	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	MODULER 21		1	< 0.3
9209797	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	MODULER SHURSE		1	0.5
9209798	2019-04-23	5:00 pm	2019-04-25	5:00 pm	68	GOODNIGHT	MAIN SCHOOL	MODULER ATTENTO		1	0.6

Haaff Elementary

*(from test kit)**Times should be in 24 hour format, 1pm = 13:00*** round times so that 9:31 and 10:28 both display 10:00, fo*

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9227367	05/22/2019	16:00	05/24/2019	16:00
9227373	05/22/2019	16:00	05/24/2019	16:00
9227369	05/22/2019	16:00	05/24/2019	16:00
9227374	05/22/2019	16:00	05/24/2019	16:00
9227370	05/22/2019	16:00	05/24/2019	16:00
9227372	05/22/2019	16:00	05/24/2019	16:00
9227375	05/22/2019	16:00	05/24/2019	16:00
9227376	05/22/2019	16:00	05/24/2019	16:00
9227377	05/22/2019	16:00	05/24/2019	16:00
9227378	05/22/2019	16:00	05/24/2019	16:00
9227379	05/22/2019	16:00	05/24/2019	16:00
9227381	05/22/2019	16:00	05/24/2019	16:00
9227382	05/22/2019	16:00	05/24/2019	16:00
9227386	05/22/2019	16:00	05/24/2019	16:00
9227383	05/22/2019	16:00	05/24/2019	16:00
9227384	05/22/2019	16:00	05/24/2019	16:00
9227385	05/22/2019	16:00	05/24/2019	16:00
9227380	05/22/2019	16:00	05/24/2019	16:00
9227387	05/22/2019	16:00	05/24/2019	16:00
9227391	05/22/2019	16:00	05/24/2019	16:00
9227392	05/22/2019	16:00	05/24/2019	16:00
9227388	05/22/2019	16:00	05/24/2019	16:00
9227393	05/22/2019	16:00	05/24/2019	16:00
9227389	05/22/2019	16:00	05/24/2019	16:00
9227390	05/22/2019	16:00	05/24/2019	16:00
9227368	05/22/2019	16:00	05/24/2019	16:00
9227394	05/22/2019	16:00	05/24/2019	16:00
9227395	05/22/2019	16:00	05/24/2019	16:00
9227396	05/22/2019	16:00	05/24/2019	16:00
9227397	05/22/2019	16:00	05/24/2019	16:00
9227398	05/22/2019	16:00	05/24/2019	16:00
9227399	05/22/2019	16:00	05/24/2019	16:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Haaff Elementary	Main School	Cafeteria		1st
68	Haaff Elementary	Main School	Cafeteria		1st
68	Haaff Elementary	Main School	Gym		1st
68	Haaff Elementary	Main School	Gym		1st
68	Haaff Elementary	Main School	Room29		1st
68	Haaff Elementary	Main School	Room30		1st
68	Haaff Elementary	Main School	Room31		1st
68	Haaff Elementary	Main School	Room 32		1st
68	Haaff Elementary	Main School	Room 34		1st
68	Haaff Elementary	Main School	Room 33		1st
68	Haaff Elementary	Main School	Room 35		1st
68	Haaff Elementary	Main School	Media Center		1st
68	Haaff Elementary	Main School	Media Center		1st
68	Haaff Elementary	Main School	Room 25A		1st
68	Haaff Elementary	Main School	Room 25A		1st
68	Haaff Elementary	Main School	Room 18A		1st
68	Haaff Elementary	Main School	Room 16A		1st
68	Haaff Elementary	Main School	Room 18B		1st
68	Haaff Elementary	Main School	Room 16B		1st
68	Haaff Elementary	Main School	Room 17		1st
68	Haaff Elementary	Main School	Room 15		1st
68	Haaff Elementary	Main School	Room 14		1st
68	Haaff Elementary	Main School	Room 14		1st
68	Haaff Elementary	Main School	Room 12		1st
68	Haaff Elementary	Main School	Room 13		1st
68	Haaff Elementary	Main School	Room 11		1st
68	Haaff Elementary	Main School	Room 10		1st
68	Haaff Elementary	Main School	Room 19		1st
68	Haaff Elementary	Main School	Room 21		1st
68	Haaff Elementary	Main School	Room 20		1st
68	Haaff Elementary	Main School	Room 22		1st
68	Haaff Elementary	Main School	Room B39		1st

Radon test result report for:
**HAAFF ELEMENTARY
 MAIN SCHOOL**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9227367	CAFETERIA	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	0.8 ± 0.4	2019-05-28
9227373	CAFETERIA	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	0.7 ± 0.4	2019-05-28
9227374	GYM	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	1.1 ± 0.4	2019-05-28
9227369	GYM	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	1.2 ± 0.4	2019-05-28
9227381	MEDIA CENTER	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	0.6 ± 0.4	2019-05-28
9227382	MEDIA CENTER	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	< 0.3	2019-05-28
9227394	ROOM 10	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	0.9 ± 0.4	2019-05-28
9227368	ROOM 11	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	1.2 ± 0.4	2019-05-28
9227389	ROOM 12	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	< 0.3	2019-05-28
9227390	ROOM 13	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	0.7 ± 0.4	2019-05-28
9227388	ROOM 14	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	1.1 ± 0.4	2019-05-28
9227393	ROOM 14	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	0.9 ± 0.4	2019-05-28
9227392	ROOM 15	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	1.2 ± 0.4	2019-05-28
9227385	ROOM 16A	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	< 0.3	2019-05-28
9227387	ROOM 16B	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	0.9 ± 0.4	2019-05-28
9227391	ROOM 17	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	1.5 ± 0.4	2019-05-28
9227384	ROOM 18A	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	0.6 ± 0.4	2019-05-28
9227380	ROOM 18B	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	0.6 ± 0.4	2019-05-28
9227395	ROOM 19	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	0.8 ± 0.4	2019-05-28
9227397	ROOM 20	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	< 0.3	2019-05-28
9227396	ROOM 21	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	1.0 ± 0.4	2019-05-28
9227398	ROOM 22	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	1.0 ± 0.4	2019-05-28
9227386	ROOM 25A	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	< 0.3	2019-05-28
9227383	ROOM 25A	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	< 0.3	2019-05-28
9227376	ROOM 32	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	0.7 ± 0.4	2019-05-28
9227378	ROOM 33	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	1.5 ± 0.4	2019-05-28
9227377	ROOM 34	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	0.7 ± 0.4	2019-05-28
9227379	ROOM 35	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	1.1 ± 0.4	2019-05-28
9227399	ROOM B39	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	< 0.3	2019-05-28
9227370	ROOM29	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	0.9 ± 0.4	2019-05-28
9227372	ROOM30	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	0.7 ± 0.4	2019-05-28
9227375	ROOM31	2019-05-22 @ 4:00 pm	2019-05-24 @ 4:00 pm	1.1 ± 0.4	2019-05-28

Heaton Middle School

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00

* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9227244	05/31/2019	14:00	06/03/2019	14:00
9227243	05/31/2019	14:00	06/03/2019	14:00
9227246	05/31/2019	14:00	06/03/2019	14:00
9227247	05/31/2019	14:00	06/03/2019	14:00
9227248	05/31/2019	14:00	06/03/2019	14:00
9227249	05/31/2019	14:00	06/03/2019	14:00
9227250	05/31/2019	14:00	06/03/2019	14:00
9227251	05/31/2019	14:00	06/03/2019	14:00
9227253	05/31/2019	14:00	06/03/2019	14:00
9227252	05/31/2019	14:00	06/03/2019	14:00
9227254	05/31/2019	14:00	06/03/2019	14:00
9227255	05/31/2019	14:00	06/03/2019	14:00
9227256	05/31/2019	14:00	06/03/2019	14:00
9227257	05/31/2019	14:00	06/03/2019	14:00
9227258	05/31/2019	14:00	06/03/2019	14:00
9227259	05/31/2019	14:00	06/03/2019	14:00
9227260	05/31/2019	14:00	06/03/2019	14:00
9227263	05/31/2019	14:00	06/03/2019	14:00
9227264	05/31/2019	14:00	06/03/2019	14:00
9227265	05/31/2019	14:00	06/03/2019	14:00
9227266	05/31/2019	14:00	06/03/2019	14:00
9227262	05/31/2019	14:00	06/03/2019	14:00
9227267	05/31/2019	14:00	06/03/2019	14:00
9227268	05/31/2019	14:00	06/03/2019	14:00
9227269	05/31/2019	14:00	06/03/2019	14:00
9227270	05/31/2019	14:00	06/03/2019	14:00
9227276	05/31/2019	14:00	06/03/2019	14:00
9227271	05/31/2019	14:00	06/03/2019	14:00
9227272	05/31/2019	14:00	06/03/2019	14:00
9227273	05/31/2019	14:00	06/03/2019	14:00
9227274	05/31/2019	14:00	06/03/2019	14:00
9227277	05/31/2019	14:00	06/03/2019	14:00
9227278	05/31/2019	14:00	06/03/2019	14:00
9227279	05/31/2019	14:00	06/03/2019	14:00
9227280	05/31/2019	14:00	06/03/2019	14:00
9227281	05/31/2019	14:00	06/03/2019	14:00
9227285	05/31/2019	14:00	06/03/2019	14:00
9227282	05/31/2019	14:00	06/03/2019	14:00
9227286	05/31/2019	14:00	06/03/2019	14:00
9227283	05/31/2019	14:00	06/03/2019	14:00
9227287	05/31/2019	14:00	06/03/2019	14:00
9227288	05/31/2019	14:00	06/03/2019	14:00
9227289	05/31/2019	14:00	06/03/2019	14:00
9227284	05/31/2019	14:00	06/03/2019	14:00
9227293	05/31/2019	14:00	06/03/2019	14:00

TAB]

9227290	05/31/2019	14:00	06/03/2019	14:00
9227291	05/31/2019	14:00	06/03/2019	14:00
9227295	05/31/2019	14:00	06/03/2019	14:00
9227294	05/31/2019	14:00	06/03/2019	14:00
9227296	05/31/2019	14:00	06/03/2019	14:00
9227275	05/31/2019	14:00	06/03/2019	14:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Heaton Middle School	Main School	R27		1
68	Heaton Middle School	Main School	R26		1
68	Heaton Middle School	Main School	R25		1
68	Heaton Middle School	Main School	R24		1
68	Heaton Middle School	Main School	R21		1
68	Heaton Middle School	Main School	R23		1
68	Heaton Middle School	Main School	R22		1
68	Heaton Middle School	Main School	Cafeteria		1
68	Heaton Middle School	Main School	Cafeteria		1
68	Heaton Middle School	Main School	R14		1
68	Heaton Middle School	Main School	R13		1
68	Heaton Middle School	Main School	R10		1
68	Heaton Middle School	Main School	R12		1
68	Heaton Middle School	Main School	R51		1
68	Heaton Middle School	Main School	Vrestling Rm		1
68	Heaton Middle School	Main School	Vrestling Rm		1
68	Heaton Middle School	Main School	R52 A		1
68	Heaton Middle School	Main School	R52 A		1
68	Heaton Middle School	Main School	Music Rm		1
68	Heaton Middle School	Main School	R53		1
68	Heaton Middle School	Main School	R53		1
68	Heaton Middle School	Main School	R54		1
68	Heaton Middle School	Main School	Auditorium		1
68	Heaton Middle School	Main School	Gym 1		1
68	Heaton Middle School	Main School	Gym 1		1
68	Heaton Middle School	Main School	Gym 2		1
68	Heaton Middle School	Main School	Gym 2		1
68	Heaton Middle School	Main School	R40		1
68	Heaton Middle School	Main School	R40		1
68	Heaton Middle School	Main School	R49		1
68	Heaton Middle School	Main School	R41		1
68	Heaton Middle School	Main School	R42		1
68	Heaton Middle School	Main School	R47		1
68	Heaton Middle School	Main School	R46		1
68	Heaton Middle School	Main School	R43		1
68	Heaton Middle School	Main School	R45		1
68	Heaton Middle School	Main School	R44		1
68	Heaton Middle School	Main School	Library		1
68	Heaton Middle School	Main School	Library		1
68	Heaton Middle School	Main School	Library		1
68	Heaton Middle School	Main School	R38		1
68	Heaton Middle School	Main School	R30		1
68	Heaton Middle School	Main School	R27		1
68	Heaton Middle School	Main School	R31		1
68	Heaton Middle School	Main School	R32		1

TAB]

68	Heaton Middle School	Main School	R36	1
68	Heaton Middle School	Main School	R33	1
68	Heaton Middle School	Main School	R35	1
68	Heaton Middle School	Main School	R34	1
68	Heaton Middle School	Main School	R34	1
68	Heaton Middle School	Main School	R48	1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9227243	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	26		1	1.5
9227244	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	27		1	1.6
9227246	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	25		1	1.9
9227247	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	24		1	2.0
9227248	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	21		1	1.8
9227249	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	23		1	1.6
9227250	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	22		1	1.2
9227251	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	CAFETERIA		1	1.0
9227252	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	14		1	1.7
9227253	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	CAFETERIA		1	1.7
9227254	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	13		1	< 0.3
9227255	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	10		1	1.8
9227256	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	12		1	1.2
9227257	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	51		1	5.1
9227258	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	WRESTLING RM		1	5.0
9227259	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	WRESTLING RM		1	1.2
9227260	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	R52 A		1	1.3
9227262	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	54		1	0.8
9227263	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	R52 A		1	1.2
9227264	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	MUSIC RM		1	1.0
9227265	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	53		1	1.0
9227266	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	53		1	1.5
9227267	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	AUDITORIUM		1	0.8
9227268	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	GYM 1		1	0.6
9227269	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	GYM 1		1	< 0.3
9227270	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	GYM 2		1	0.5
9227271	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	40		1	1.8
9227272	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	40		1	1.4
9227273	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	49		1	1.6
9227274	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	41		1	2.2
9227275	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	48		1	1.3
9227276	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	GYM 2		1	0.6
9227277	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	42		1	1.8
9227278	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	47		1	1.5
9227279	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	46		1	1.4

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9227280	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	43		1	1.7
9227281	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	45		1	1.4
9227282	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	LIBRARY		1	0.9
9227283	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	LIBRARY		1	0.6
9227284	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	31		1	2.1
9227285	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	44		1	1.9
9227286	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	LIBRARY		1	1.0
9227287	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	38		1	2.2
9227288	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	30		1	2.2
9227289	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	27		1	2.0
9227290	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	36		1	1.9
9227291	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	33		1	2.3
9227293	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	32		1	2.1
9227294	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	34		1	2.6
9227295	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	35		1	1.7
9227296	2019-05-31	2:00 pm	2019-06-03	2:00 pm	68	HEATON MIDDLE SCHOOL	MAIN SCHOOL	34		1	2.5

Heritage Elementary

*(from test kit)**Times should be in 24 hour format, 1pm = 13:00*** round times so that 9:31 and 10:28 both display 10:00, fo*

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9210118	04/12/2019	10:00	04/15/2019	15:00
9210127	04/12/2019	10:00	04/15/2019	15:00
9210144	04/12/2019	10:00	04/15/2019	15:00
9210161	04/12/2019	10:00	04/15/2019	15:00
9210135	04/12/2019	10:00	04/15/2019	15:00
9210141	04/12/2019	10:00	04/15/2019	15:00
9210162	04/12/2019	10:00	04/15/2019	15:00
9210136	04/12/2019	10:00	04/15/2019	15:00
9210163	04/12/2019	10:00	04/15/2019	15:00
9210165	04/12/2019	10:00	04/15/2019	15:00
9210166	04/12/2019	10:00	04/15/2019	15:00
9210171	04/12/2019	10:00	04/15/2019	15:00
9210174	04/12/2019	10:00	04/15/2019	15:00
9210170	04/12/2019	10:00	04/15/2019	15:00
9210169	04/12/2019	10:00	04/15/2019	15:00
9210168	04/12/2019	10:00	04/15/2019	15:00
9210175	04/12/2019	10:00	04/15/2019	15:00
9210164	04/12/2019	10:00	04/15/2019	15:00
9210173	04/12/2019	10:00	04/15/2019	15:00
9210167	04/12/2019	11:00	04/15/2019	15:00
9210179	04/12/2019	11:00	04/15/2019	15:00
9210181	04/12/2019	11:00	04/15/2019	15:00
9210188	04/12/2019	11:00	04/15/2019	15:00
9210187	04/12/2019	11:00	04/15/2019	15:00
9210176	04/12/2019	11:00	04/15/2019	15:00
9210180	04/12/2019	11:00	04/15/2019	15:00
9210184	04/12/2019	11:00	04/15/2019	15:00
9210182	04/12/2019	11:00	04/15/2019	15:00
9210172	04/12/2019	11:00	04/15/2019	15:00
9210191	04/12/2019	11:00	04/15/2019	15:00
9210185	04/12/2019	11:00	04/15/2019	15:00
9210189	04/12/2019	11:00	04/15/2019	15:00
9210186	04/12/2019	11:00	04/15/2019	15:00
9210139	04/12/2019	11:00	04/15/2019	15:00
9210190	04/12/2019	11:00	04/15/2019	15:00
9210178	04/12/2019	11:00	04/15/2019	15:00
9210158	04/12/2019	11:00	04/15/2019	15:00
9210177	04/12/2019	11:00	04/15/2019	15:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Heritage School	Main School	Bachicha		1
68	Heritage School	Main School	R 102A		1
68	Heritage School	Main School	R 102B		1
68	Heritage School	Main School	R207		1
68	Heritage School	Main School	R103		1
68	Heritage School	Main School	R104		1
68	Heritage School	Main School	R105		1
68	Heritage School	Main School	R108		1
68	Heritage School	Main School	R10		1
68	Heritage School	Main School	R112		1
68	Heritage School	Main School	R112		1
68	Heritage School	Main School	R114		1
68	Heritage School	Main School	R116		1
68	Heritage School	Main School	R200		1
68	Heritage School	Main School	R201		1
68	Heritage School	Main School	R203		1
68	Heritage School	Main School	R202		1
68	Heritage School	Main School	R204		1
68	Heritage School	Main School	R207		1
68	Heritage School	Main School	R206		1
68	Heritage School	Main School	R208		1
68	Heritage School	Main School	R208		1
68	Heritage School	Main School	R300		1
68	Heritage School	Main School	R300		1
68	Heritage School	Main School	R210		1
68	Heritage School	Main School	R209		1
68	Heritage School	Main School	R212		1
68	Heritage School	Main School	R214		1
68	Heritage School	Main School	R310		1
68	Heritage School	Main School	R310		1
68	Heritage School	Main School	R308		1
68	Heritage School	Main School	R308		1
68	Heritage School	Main School	Sajbel		1
68	Heritage School	Main School	R306		1
68	Heritage School	Main School	R306		1
68	Heritage School	Main School	R304		1
68	Heritage School	Main School	R301		1
68	Heritage School	Main School	R302		1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9210118	2019-04-12	10:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	BACHICHA		1	< 0.3
9210127	2019-04-12	10:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	R 102A		1	< 0.3
9210135	2019-04-12	10:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	103		1	< 0.3
9210136	2019-04-12	10:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	108		1	< 0.3
9210139	2019-04-12	11:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	306		1	< 0.3
9210141	2019-04-12	10:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	104		1	< 0.3
9210144	2019-04-12	10:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	R 102B		1	< 0.3
9210158	2019-04-12	11:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	301		1	0.5
9210161	2019-04-12	10:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	207		1	< 0.3
9210162	2019-04-12	10:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	105		1	< 0.3
9210163	2019-04-12	10:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	10		1	< 0.3
9210164	2019-04-12	10:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	204		1	< 0.3
9210165	2019-04-12	10:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	112		1	< 0.3
9210166	2019-04-12	10:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	112		1	< 0.3
9210167	2019-04-12	11:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	206		1	< 0.3
9210168	2019-04-12	10:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	203		1	0.6
9210169	2019-04-12	10:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	201		1	< 0.3
9210170	2019-04-12	10:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	200		1	< 0.3
9210171	2019-04-12	10:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	114		1	< 0.3
9210172	2019-04-12	11:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	310		1	0.6
9210173	2019-04-12	10:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	207		1	< 0.3
9210174	2019-04-12	10:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	116		1	< 0.3
9210175	2019-04-12	10:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	202		1	< 0.3
9210176	2019-04-12	11:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	210		1	< 0.3
9210177	2019-04-12	11:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	302		1	< 0.3
9210178	2019-04-12	11:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	304		1	< 0.3
9210179	2019-04-12	11:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	208		1	0.5
9210180	2019-04-12	11:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	209		1	0.8
9210181	2019-04-12	11:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	208		1	0.6
9210182	2019-04-12	11:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	214		1	< 0.3
9210184	2019-04-12	11:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	212		1	0.6
9210185	2019-04-12	11:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	308		1	< 0.3
9210186	2019-04-12	11:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	SAJBEL		1	< 0.3
9210187	2019-04-12	11:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	300		1	< 0.3
9210188	2019-04-12	11:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	300		1	0.5

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9210189	2019-04-12	11:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	308		1	< 0.3
9210190	2019-04-12	11:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	306		1	< 0.3
9210191	2019-04-12	11:00 am	2019-04-15	3:00 pm	68	HERITAGE SCHOOL	MAIN SCHOOL	310		1	< 0.3

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Highland Park Elementary

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00
* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9220573	05/08/2019	14:00	05/10/2019	16:00
9220577	05/08/2019	14:00	05/10/2019	16:00
9220582	05/08/2019	14:00	05/10/2019	16:00
9220578	05/08/2019	14:00	05/10/2019	16:00
9220579	05/08/2019	15:00	05/10/2019	16:00
9220580	05/08/2019	15:00	05/10/2019	16:00
9220583	05/08/2019	15:00	05/10/2019	16:00
9220584	05/08/2019	15:00	05/10/2019	16:00
9220591	05/08/2019	15:00	05/10/2019	16:00
9220592	05/08/2019	15:00	05/10/2019	16:00
9220581	05/08/2019	15:00	05/10/2019	16:00
9220599	05/08/2019	15:00	05/10/2019	16:00
9220588	05/08/2019	15:00	05/10/2019	16:00
9220589	05/08/2019	15:00	05/10/2019	16:00
9220585	05/08/2019	15:00	05/10/2019	16:00
9220586	05/08/2019	15:00	05/10/2019	16:00
9220587	05/08/2019	15:00	05/10/2019	16:00
9220590	05/08/2019	15:00	05/10/2019	16:00
9220595	05/08/2019	15:00	05/10/2019	16:00
9220593	05/08/2019	15:00	05/10/2019	16:00
9220594	05/08/2019	15:00	05/10/2019	16:00
9220596	05/08/2019	15:00	05/10/2019	16:00
9220597	05/08/2019	15:00	05/10/2019	16:00
9220598	05/08/2019	15:00	05/10/2019	16:00
9220600	05/08/2019	15:00	05/10/2019	16:00
9220301	05/08/2019	15:00	05/10/2019	16:00
9220302	05/08/2019	15:00	05/10/2019	16:00
9220305	05/08/2019	15:00	05/10/2019	16:00
9220307	05/08/2019	15:00	05/10/2019	16:00
9220303	05/08/2019	15:00	05/10/2019	16:00
9220304	05/08/2019	15:00	05/10/2019	16:00
9220306	05/08/2019	15:00	05/10/2019	16:00
9220308	05/08/2019	15:00	05/10/2019	16:00
9220309	05/08/2019	15:00	05/10/2019	16:00
9220313	05/08/2019	15:00	05/10/2019	16:00
9220310	05/08/2019	15:00	05/10/2019	16:00
9220311	05/08/2019	15:00	05/10/2019	16:00
9220312	05/08/2019	15:00	05/10/2019	16:00
9220314	05/08/2019	15:00	05/10/2019	16:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=oth

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Highland Park	Main Building	Cafeteria		1
68	Highland Park	Main Building	Cafeteria		1
68	Highland Park	Main Building	Gym		1
68	Highland Park	Main Building	Gym		1
68	Highland Park	Main Building	Rm 4-24		1
68	Highland Park	Main Building	Rm 4-26		1
68	Highland Park	Main Building	Rm 4-23		1
68	Highland Park	Main Building	Rm 4-25		1
68	Highland Park	Main Building	Rm 5-28		1
68	Highland Park	Main Building	Rm 5-30		1
68	Highland Park	Main Building	Rm 5-29		1
68	Highland Park	Main Building	Rm 5-27		1
68	Highland Park	Main Building	Bruce		1
68	Highland Park	Main Building	Media		1
68	Highland Park	Main Building	Media		1
68	Highland Park	Main Building	Media		1
68	Highland Park	Main Building	pecial Ed Rm		1
68	Highland Park	Main Building	Reading Rm		1
68	Highland Park	Main Building	Rm 31		1
68	Highland Park	Main Building	Rm 32		1
68	Highland Park	Main Building	Rm 33		1
68	Highland Park	Main Building	Rm 21		1
68	Highland Park	Main Building	Rm 27		1
68	Highland Park	Main Building	Rm 20		1
68	Highland Park	Main Building	Rm 22		1
68	Highland Park	Main Building	Rm 2-18		1
68	Highland Park	Main Building	Rm 2-16		1
68	Highland Park	Main Building	Rm 1-17		1
68	Highland Park	Main Building	Rm 1-15		1
68	Highland Park	Main Building	Rm 2-14		1
68	Highland Park	Main Building	Rm 2-14		1
68	Highland Park	Main Building	Rm 1-13		1
68	Highland Park	Main Building	Rm 1-11		1
68	Highland Park	Main Building	Rm 1-10		1
68	Highland Park	Main Building	Rm 1-09		1
68	Highland Park	Main Building	Rm 1-01		1
68	Highland Park	Main Building	Rm 1-01		1
68	Highland Park	Main Building	Ess Room		1
68	Highland Park	Main Building	eneding Rm		1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9220301	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 2-18		1	5.6
9220302	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 2-16		1	4.6
9220303	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 2-14		1	4.8
9220304	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 2-14		1	6.0
9220305	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 1-17		1	4.7
9220306	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 1-13		1	4.6
9220307	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 1-15		1	5.3
9220308	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 1-11		1	5.2
9220309	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 1-10		1	5.3
9220310	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 1-01		1	5.9
9220311	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 1-01		1	5.8
9220312	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	ESS ROOM		1	3.2
9220313	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 1-09		1	4.7
9220314	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	SENEADING RM		1	2.8
9220573	2019-05-08	2:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	CAFETERIA		1	6.6
9220577	2019-05-08	2:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	CAFETERIA		1	7.7
9220578	2019-05-08	2:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	GYM		1	4.9
9220579	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 4-24		1	2.5
9220580	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 4-26		1	4.6
9220581	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 5-29		1	4.0
9220582	2019-05-08	2:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	GYM		1	5.0
9220583	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 4-23		1	5.1
9220584	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 4-25		1	5.1
9220585	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	MEDIA		1	3.0
9220586	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	MEDIA		1	2.6
9220587	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	SPECIAL ED RM		1	4.4
9220588	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	BRUCE		1	3.3
9220589	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	MEDIA		1	3.3
9220590	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	READING RM		1	3.3
9220591	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 5-28		1	4.8
9220592	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 5-30		1	6.8
9220593	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 32		1	1.0
9220594	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 33		1	1.4
9220595	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 31		1	1.2
9220596	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 21		1	2.5

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9220597	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 27		1	3.1
9220598	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 20		1	4.2
9220599	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 5-27		1	4.3
9220600	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	HIGHLAND PARK	MAIN BUILDING	RM 22		1	4.4

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Irving Elementary

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00

* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9226001	05/17/2019	9:30	05/20/2019	15:00
9226002	05/17/2019	9:30	05/20/2019	15:00
9226003	05/17/2019	9:30	05/20/2019	15:00
9226008	05/17/2019	9:30	05/20/2019	15:00
9226009	05/17/2019	9:30	05/20/2019	15:00
9226004	05/17/2019	9:30	05/20/2019	15:00
9226005	05/17/2019	9:30	05/20/2019	15:00
9226010	05/17/2019	9:30	05/20/2019	15:00
9226006	05/17/2019	9:30	05/20/2019	15:00
9226007	05/17/2019	9:30	05/20/2019	15:00
9226015	05/17/2019	9:30	05/20/2019	15:00
9226016	05/17/2019	9:30	05/20/2019	15:00
9226011	05/17/2019	9:30	05/20/2019	15:00
9226017	05/17/2019	9:30	05/20/2019	15:00
9226018	05/17/2019	9:30	05/20/2019	15:00
9226023	05/17/2019	9:30	05/20/2019	15:00
9226024	05/17/2019	9:30	05/20/2019	15:00
9226012	05/17/2019	9:30	05/20/2019	15:00
9226025	05/17/2019	9:30	05/20/2019	15:00
9226027	05/17/2019	9:30	05/20/2019	15:00
9226013	05/17/2019	9:30	05/20/2019	15:00
9226019	05/17/2019	9:30	05/20/2019	15:00
9226014	05/17/2019	9:30	05/20/2019	15:00
9226020	05/17/2019	9:30	05/20/2019	15:00
9226026	05/17/2019	9:30	05/20/2019	15:00
9226021	05/17/2019	9:30	05/20/2019	15:00
9226028	05/17/2019	9:30	05/20/2019	15:00
9226029	05/17/2019	9:30	05/20/2019	15:00
9226022	05/17/2019	9:30	05/20/2019	15:00
9226030	05/17/2019	9:30	05/20/2019	15:00
9226031	05/17/2019	9:30	05/20/2019	15:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Irving	Main School	Library		1
68	Irving	Main School	Library		1
68	Irving	Main School	R1191		1
68	Irving	Main School	R1193		1
68	Irving	Main School	R1196		1
68	Irving	Main School	R1145		1
68	Irving	Main School	R1143		1
68	Irving	Main School	R1144		1
68	Irving	Main School	R1136		1
68	Irving	Main School	R1135		1
68	Irving	Main School	R1132		1
68	Irving	Main School	R1129		1
68	Irving	Main School	R1128		1
68	Irving	Main School	R1124		1
68	Irving	Main School	R1122		1
68	Irving	Main School	R1101		1
68	Irving	Main School	R1102		1
68	Irving	Main School	R1103		1
68	Irving	Main School	R1104		1
68	Irving	Main School	R1113		1
68	Irving	Main School	R1105		1
68	Irving	Main School	R1106		1
68	Irving	Main School	R1110		1
68	Irving	Main School	R1110		1
68	Irving	Main School	R1198		1
68	Irving	Main School	R1198		1
68	Irving	Main School	R1198		1
68	Irving	Main School	Gym		1
68	Irving	Main School	Gym		1
68	Irving	Main School	Cafeteria		1
68	Irving	Main School	Cafeteria		1

Radon test result report for:**IRVING
MAIN SCHOOL**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9226023	1101	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	2.7 ± 0.3	2019-05-22
9226024	1102	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	2.7 ± 0.3	2019-05-22
9226012	1103	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	2.7 ± 0.3	2019-05-22
9226025	1104	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	2.8 ± 0.3	2019-05-22
9226013	1105	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	4.0 ± 0.4	2019-05-22
9226019	1106	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	3.5 ± 0.4	2019-05-22
9226020	1110	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	3.3 ± 0.3	2019-05-22
9226014	1110	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	3.7 ± 0.4	2019-05-22
9226027	1113	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	2.6 ± 0.3	2019-05-22
9226018	1122	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	2.9 ± 0.3	2019-05-22
9226017	1124	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	2.1 ± 0.3	2019-05-22
9226011	1128	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	2.6 ± 0.3	2019-05-22
9226016	1129	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	2.6 ± 0.3	2019-05-22
9226015	1132	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	2.3 ± 0.3	2019-05-22
9226007	1135	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	2.0 ± 0.3	2019-05-22
9226006	1136	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	1.9 ± 0.3	2019-05-22
9226005	1143	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	1.8 ± 0.3	2019-05-22
9226010	1144	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	2.2 ± 0.3	2019-05-22
9226004	1145	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	1.9 ± 0.3	2019-05-22
9226003	1191	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	2.2 ± 0.3	2019-05-22
9226008	1193	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	2.0 ± 0.3	2019-05-22
9226009	1196	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	3.1 ± 0.3	2019-05-22
9226026	1198	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	2.3 ± 0.3	2019-05-22
9226021	1198	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	1.4 ± 0.3	2019-05-22
9226028	1198	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	2.1 ± 0.3	2019-05-22
9226030	CAFETERIA	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	2.4 ± 0.3	2019-05-22
9226031	CAFETERIA	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	2.6 ± 0.3	2019-05-22
9226029	GYM	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	1.6 ± 0.3	2019-05-22
9226022	GYM	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	1.5 ± 0.3	2019-05-22
9226001	LIBRARY	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	2.5 ± 0.3	2019-05-22
9226002	LIBRARY	2019-05-17 @ 10:00 am	2019-05-20 @ 3:00 pm	2.5 ± 0.3	2019-05-22

Minnequa Elementary

(from test kit) Times should be in 24 hour format, 1pm = 13:00 (+ / - 5 degrees) (your designations for facility, building and room) (optional) (enter proper code)
 * round times so that 9:31 and 10:28 both display 10:00, for example 0=Basement, 1=1st, 2=2nd, 3=other

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>	<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
9210104	04/09/2019	14:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	Cafeteria		1
9210124	04/09/2019	14:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	Cafeteria		1
9210149	04/09/2019	14:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R19		1
9210150	04/09/2019	14:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R15		1
9210143	04/09/2019	14:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	Library		1
9210140	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	Library		1
9210156	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R15		1
9210120	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R14		1
9210148	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R10		1
9210105	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R11		1
9210142	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R9		1
9210108	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R8		1
9210147	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R7		1
9210101	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R6		1
9210157	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R5		1
9210106	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R4		1
9210115	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R3		1
9210103	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R1		1
9210107	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R1		1
9210132	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R1		1
9210110	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	Gym		1
9210112	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R12		1
9210114	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R12		1
9210113	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R13		1
9210133	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R26		1
9210131	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R25		1
9210129	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R24		1
9210130	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	Teacher Lounge		1
9210117	04/09/2019	15:00	04/11/2019	15:00	68	Minnequa Elementary	Main School	R23		1

Radon test result report for:
**MINNEQUA ELEMENTARY
 MAIN SCHOOL**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9210103	1	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	< 0.3	2019-04-16
9210107	1	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	0.7 ± 0.5	2019-04-16
9210132	1	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	0.7 ± 0.5	2019-04-16
9210148	10	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	< 0.3	2019-04-16
9210105	11	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	0.9 ± 0.5	2019-04-16
9210114	12	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	1.4 ± 0.5	2019-04-16
9210112	12	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	0.9 ± 0.5	2019-04-16
9210113	13	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	< 0.3	2019-04-16
9210120	14	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	0.8 ± 0.6	2019-04-16
9210150	15	2019-04-09 @ 2:00 pm	2019-04-11 @ 3:00 pm	0.6 ± 0.5	2019-04-16
9210156	15	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	0.6 ± 0.5	2019-04-16
9210149	19	2019-04-09 @ 2:00 pm	2019-04-11 @ 3:00 pm	< 0.3	2019-04-16
9210117	23	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	1.4 ± 0.5	2019-04-16
9210129	24	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	0.8 ± 0.5	2019-04-16
9210131	25	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	0.9 ± 0.5	2019-04-16
9210133	26	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	0.8 ± 0.5	2019-04-16
9210115	3	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	< 0.3	2019-04-16
9210106	4	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	< 0.3	2019-04-16
9210157	5	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	0.6 ± 0.5	2019-04-16
9210101	6	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	0.7 ± 0.5	2019-04-16
9210147	7	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	< 0.3	2019-04-16
9210108	8	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	1.1 ± 0.5	2019-04-16
9210142	9	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	0.8 ± 0.6	2019-04-16
9210124	CAFETERIA	2019-04-09 @ 2:00 pm	2019-04-11 @ 3:00 pm	0.9 ± 0.6	2019-04-16
9210104	CAFETERIA	2019-04-09 @ 2:00 pm	2019-04-11 @ 3:00 pm	0.5 ± 0.5	2019-04-16
9210110	GYM	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	1.3 ± 0.6	2019-04-16
9210143	LIBRARY	2019-04-09 @ 2:00 pm	2019-04-11 @ 3:00 pm	0.8 ± 0.5	2019-04-16
9210140	LIBRARY	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	< 0.3	2019-04-16
9210130	TEACJER LOUNGE	2019-04-09 @ 3:00 pm	2019-04-11 @ 3:00 pm	< 0.3	2019-04-16

Morton Elementary

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00
* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9226033	05/17/2019	11:00	05/20/2019	16:00
9226032	05/17/2019	11:00	05/20/2019	16:00
9226034	05/17/2019	11:00	05/20/2019	16:00
9226035	05/17/2019	11:00	05/20/2019	16:00
9226036	05/17/2019	11:00	05/20/2019	16:00
9226037	05/17/2019	11:00	05/20/2019	16:00
9226039	05/17/2019	11:00	05/20/2019	16:00
9226040	05/17/2019	11:00	05/20/2019	16:00
9226041	05/17/2019	11:00	05/20/2019	16:00
9226042	05/17/2019	11:00	05/20/2019	16:00
9226043	05/17/2019	11:00	05/20/2019	16:00
9226044	05/17/2019	11:00	05/20/2019	16:00
9226038	05/17/2019	11:00	05/20/2019	16:00
9226045	05/17/2019	11:00	05/20/2019	16:00
9226047	05/17/2019	11:00	05/20/2019	16:00
9226046	05/17/2019	11:00	05/20/2019	16:00
9226049	05/17/2019	11:00	05/20/2019	16:00
9226050	05/17/2019	11:00	05/20/2019	16:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Morton	Main School	Library		1
68	Morton	Main School	Library		1
68	Morton	Main School	Cafeteria		1
68	Morton	Main School	Cafeteria		1
68	Morton	Main School	R112		1
68	Morton	Main School	R111		1
68	Morton	Main School	R114		1
68	Morton	Main School	R113		1
68	Morton	Main School	R107		1
68	Morton	Main School	R106		1
68	Morton	Main School	R105		1
68	Morton	Main School	R104		1
68	Morton	Main School	R101		1
68	Morton	Main School	R103		1
68	Morton	Main School	R100		1
68	Morton	Main School	R102		1
68	Morton	Main School	IT Rm		1
68	Morton	Main School	IT Rm		1

May 22, 2019

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

**MORTON
MAIN SCHOOL**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9226034	CAFETERIA	2019-05-17 @ 11:00 am	2019-05-20 @ 4:00 pm	< 0.3	2019-05-22
9226035	CAFETERIA	2019-05-17 @ 11:00 am	2019-05-20 @ 4:00 pm	< 0.3	2019-05-22
9226049	IT RM	2019-05-17 @ 11:00 am	2019-05-20 @ 4:00 pm	< 0.3	2019-05-22
9226050	IT RM	2019-05-17 @ 11:00 am	2019-05-20 @ 4:00 pm	< 0.3	2019-05-22
9226033	LIBRARY	2019-05-17 @ 11:00 am	2019-05-20 @ 4:00 pm	< 0.3	2019-05-22
9226032	LIBRARY	2019-05-17 @ 11:00 am	2019-05-20 @ 4:00 pm	0.9 ± 0.3	2019-05-22
9226047	R100	2019-05-17 @ 11:00 am	2019-05-20 @ 4:00 pm	< 0.3	2019-05-22
9226038	R101	2019-05-17 @ 11:00 am	2019-05-20 @ 4:00 pm	< 0.3	2019-05-22
9226046	R102	2019-05-17 @ 11:00 am	2019-05-20 @ 4:00 pm	< 0.3	2019-05-22
9226045	R103	2019-05-17 @ 11:00 am	2019-05-20 @ 4:00 pm	0.5 ± 0.3	2019-05-22
9226044	R104	2019-05-17 @ 11:00 am	2019-05-20 @ 4:00 pm	< 0.3	2019-05-22
9226043	R105	2019-05-17 @ 11:00 am	2019-05-20 @ 4:00 pm	< 0.3	2019-05-22
9226041	R107	2019-05-17 @ 11:00 am	2019-05-20 @ 4:00 pm	< 0.3	2019-05-22
9226037	R111	2019-05-17 @ 11:00 am	2019-05-20 @ 4:00 pm	< 0.3	2019-05-22
9226036	R112	2019-05-17 @ 11:00 am	2019-05-20 @ 4:00 pm	< 0.3	2019-05-22
9226040	R113	2019-05-17 @ 11:00 am	2019-05-20 @ 4:00 pm	< 0.3	2019-05-22
9226039	R114	2019-05-17 @ 11:00 am	2019-05-20 @ 4:00 pm	< 0.3	2019-05-22

Paragon

(from test kit)

Times should be in 24 hour format, 1pm = 13:00

(+ / - 5 degrees, (your designations for facility, building and room)

(optional)

(enter proper code)

* round times so that 9:31 and 10:28 both display 10:00, for example

0=Basement, 1=1st, 2=2nd, 3=other

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>	<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
9210255	04/05/2019	13:00	04/08/2019	16:00	68	Paragon	Main School	Kindergarten		1st
9210258	04/05/2019	13:00	04/08/2019	16:00	68	Paragon	Main School	R9		1st
9210248	04/05/2019	13:00	04/08/2019	17:00	68	Paragon	Main School	R10		1st
9210246	04/05/2019	13:00	04/08/2019	17:00	68	Paragon	Main School	R8		1st
9210243	04/05/2019	13:00	04/08/2019	17:00	68	Paragon	Main School	R11		1st
9210262	04/05/2019	13:00	04/08/2019	17:00	68	Paragon	Main School	R7		1st
9210245	04/05/2019	13:00	04/08/2019	17:00	68	Paragon	Main School	R12		1st
9210244	04/05/2019	13:00	04/08/2019	17:00	68	Paragon	Main School	R11		1st
9210257	04/05/2019	13:00	04/08/2019	17:00	68	Paragon	Main School	R12		1st
9210265	04/05/2019	13:00	04/08/2019	17:00	68	Paragon	Main School	R1		1st
9210250	04/05/2019	13:00	04/08/2019	17:00	68	Paragon	Main School	R1		1st
9210236	04/05/2019	13:00	04/08/2019	17:00	68	Paragon	Main School	R24		1st
9210256	04/05/2019	13:00	04/08/2019	17:00	68	Paragon	Main School	R21		1st
9210263	04/05/2019	14:00	04/08/2019	17:00	68	Paragon	Main School	R23		1st
9210251	04/05/2019	14:00	04/08/2019	17:00	68	Paragon	Main School	R3		1st
9210252	04/05/2019	14:00	04/08/2019	17:00	68	Paragon	Main School	R3		1st
9210242	04/05/2019	14:00	04/08/2019	17:00	68	Paragon	Main School	R21		1st
9210249	04/05/2019	14:00	04/08/2019	17:00	68	Paragon	Main School	R14		1st
9210235	04/05/2019	14:00	04/08/2019	17:00	68	Paragon	Main School	R15		1st
9210260	04/05/2019	14:00	04/08/2019	17:00	68	Paragon	Main School	Gym		1st
9210241	04/05/2019	14:00	04/08/2019	17:00	68	Paragon	Main School	Gym		1st
9210259	04/05/2019	14:00	04/08/2019	17:00	68	Paragon	Basement	Cafeteria		0
9210237	04/05/2019	14:00	04/08/2019	17:00	68	Paragon	Main School	Computer Room		1st
9210253	04/05/2019	14:00	04/08/2019	17:00	68	Paragon	Main School	Computer Room		1st
9210239	04/05/2019	14:00	04/08/2019	17:00	68	Paragon	Main School	Media Center		1st
9210254	04/05/2019	14:00	04/08/2019	17:00	68	Paragon	Main School	Media Center		1st

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9210235	2019-04-05	2:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	R15		1	0.9
9210236	2019-04-05	1:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	R24		1	1.0
9210237	2019-04-05	2:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	COMPUTER ROOM		1	0.9
9210239	2019-04-05	2:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	MEDIA CENTER		1	0.8
9210241	2019-04-05	2:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	GYM		1	0.8
9210242	2019-04-05	2:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	R21		1	1.3
9210243	2019-04-05	1:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	R11		1	0.9
9210244	2019-04-05	1:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	R11		1	0.7
9210245	2019-04-05	1:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	R12		1	0.6
9210246	2019-04-05	1:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	R8		1	0.7
9210248	2019-04-05	1:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	R10		1	0.8
9210249	2019-04-05	2:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	R14		1	0.7
9210250	2019-04-05	1:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	R1		1	0.6
9210251	2019-04-05	2:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	R3		1	1.1
9210252	2019-04-05	2:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	R3		1	1.4
9210253	2019-04-05	2:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	COMPUTER ROOM		1	0.6
9210254	2019-04-05	2:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	MEDIA CENTER		1	0.5
9210255	2019-04-05	1:00 pm	2019-04-08	4:00 pm	68	PARAGON	MAIN SCHOOL	KINDERGARTEN		1	1.5
9210256	2019-04-05	1:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	R21		1	0.7
9210257	2019-04-05	1:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	R12		1	0.5
9210258	2019-04-05	1:00 pm	2019-04-08	4:00 pm	68	PARAGON	MAIN SCHOOL	R9		1	0.8
9210259	2019-04-05	2:00 pm	2019-04-08	5:00 pm	68	PARAGON	BASEMENT	CAFETERIA		0	3.4
9210260	2019-04-05	2:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	GYM		1	0.6
9210262	2019-04-05	1:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	R7		1	<0.3
9210263	2019-04-05	2:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	R23		1	0.9
9210265	2019-04-05	1:00 pm	2019-04-08	5:00 pm	68	PARAGON	MAIN SCHOOL	R1		1	0.9

Parkview Elementary

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00
* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9220539	05/08/2019	15:00	05/10/2019	16:00
9220540	05/08/2019	15:00	05/10/2019	16:00
9220545	05/08/2019	15:00	05/10/2019	16:00
9220546	05/08/2019	15:00	05/10/2019	16:00
9220547	05/08/2019	15:00	05/10/2019	16:00
9220542	05/08/2019	15:00	05/10/2019	16:00
9220551	05/08/2019	15:00	05/10/2019	16:00
9220552	05/08/2019	15:00	05/10/2019	16:00
9220548	05/08/2019	15:00	05/10/2019	16:00
9220553	05/08/2019	15:00	05/10/2019	16:00
9220554	05/08/2019	15:00	05/10/2019	16:00
9220555	05/08/2019	15:00	05/10/2019	16:00
9220556	05/08/2019	15:00	05/10/2019	16:00
9220557	05/08/2019	15:00	05/10/2019	16:00
9220561	05/08/2019	15:00	05/10/2019	16:00
9220562	05/08/2019	15:00	05/10/2019	16:00
9220559	05/08/2019	15:00	05/10/2019	16:00
9220560	05/08/2019	15:00	05/10/2019	16:00
9220558	05/08/2019	15:00	05/10/2019	16:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=oth

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Parkview	Main Building	Rm 101		1
68	Parkview	Main Building	Rm 102		1
68	Parkview	Main Building	Rm 103		1
68	Parkview	Main Building	Rm 105	Rm 106	1
68	Parkview	Main Building	Rm 106		1
68	Parkview	Main Building	Rm 114		1
68	Parkview	Main Building	Rm 107		1
68	Parkview	Main Building	Rm 108		1
68	Parkview	Main Building	Media		1
68	Parkview	Main Building	Media		1
68	Parkview	Main Building	computer Rm		1
68	Parkview	Main Building	computer Rm		1
68	Parkview	Main Building	Rm 127		1
68	Parkview	Main Building	Rm 126		1
68	Parkview	Main Building	Rm 125		1
68	Parkview	Main Building	Cafeteria		1
68	Parkview	Main Building	Cafeteria		1
68	Parkview	Main Building	Music Rm		1
68	Parkview	Main Building	Music Rm		1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9220539	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	PARKVIEW	MAIN BUILDING	RM 101		1	< 0.3
9220540	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	PARKVIEW	MAIN BUILDING	RM 102		1	0.8
9220542	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	PARKVIEW	MAIN BUILDING	RM 114		1	1.1
9220545	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	PARKVIEW	MAIN BUILDING	RM 103		1	0.6
9220546	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	PARKVIEW	MAIN BUILDING	RM 105	RM 106	1	< 0.3
9220547	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	PARKVIEW	MAIN BUILDING	RM 106		1	0.8
9220548	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	PARKVIEW	MAIN BUILDING	MEDIA		1	0.8
9220551	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	PARKVIEW	MAIN BUILDING	RM 107		1	< 0.3
9220552	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	PARKVIEW	MAIN BUILDING	RM 108		1	1.0
9220553	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	PARKVIEW	MAIN BUILDING	MEDIA		1	0.9
9220554	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	PARKVIEW	MAIN BUILDING	COMPUTER RM		1	0.7
9220555	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	PARKVIEW	MAIN BUILDING	COMPUTER RM		1	0.8
9220556	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	PARKVIEW	MAIN BUILDING	RM 127		1	0.7
9220557	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	PARKVIEW	MAIN BUILDING	RM 126		1	0.6
9220558	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	PARKVIEW	MAIN BUILDING	MUSIC RM		1	0.9
9220559	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	PARKVIEW	MAIN BUILDING	CAFETERIA		1	1.0
9220560	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	PARKVIEW	MAIN BUILDING	MUSIC RM		1	1.0
9220561	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	PARKVIEW	MAIN BUILDING	RM 125		1	0.9
9220562	2019-05-08	3:00 pm	2019-05-10	4:00 pm	68	PARKVIEW	MAIN BUILDING	CAFETERIA		1	< 0.3

***Pueblo Academy of Arts
(Pitts)***

(from test kit)

Times should be in 24 hour format, 1pm = 13:00

* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9210045	04/26/2019	8:00	04/29/2019	17:00
9210043	04/26/2019	8:00	04/29/2019	17:00
9210046	04/26/2019	8:00	04/29/2019	17:00
9210047	04/26/2019	8:00	04/29/2019	17:00
9210049	04/26/2019	8:00	04/29/2019	17:00
9210052	04/26/2019	8:00	04/29/2019	17:00
9210053	04/26/2019	8:00	04/29/2019	17:00
9210048	04/26/2019	8:00	04/29/2019	17:00
9210050	04/26/2019	8:00	04/29/2019	17:00
9210054	04/26/2019	8:00	04/29/2019	17:00
9210055	04/26/2019	8:00	04/29/2019	17:00
9210056	04/26/2019	8:00	04/29/2019	17:00
9210051	04/26/2019	8:00	04/29/2019	17:00
9210059	04/26/2019	8:00	04/29/2019	17:00
9210060	04/26/2019	8:00	04/29/2019	17:00
9210057	04/26/2019	8:00	04/29/2019	17:00
9210061	04/26/2019	8:00	04/29/2019	17:00
9210062	04/26/2019	8:00	04/29/2019	17:00
9210058	04/26/2019	8:00	04/29/2019	17:00
9210063	04/26/2019	8:00	04/29/2019	17:00
9210064	04/26/2019	8:00	04/29/2019	17:00
9210065	04/26/2019	8:00	04/29/2019	17:00
9210067	04/26/2019	8:00	04/29/2019	17:00
9210066	04/26/2019	8:00	04/29/2019	17:00
9210068	04/26/2019	8:00	04/29/2019	17:00
9210069	04/26/2019	8:00	04/29/2019	17:00
9210070	04/26/2019	8:00	04/29/2019	17:00
9210074	04/26/2019	8:00	04/29/2019	17:00
9210071	04/26/2019	8:00	04/29/2019	17:00
9210075	04/26/2019	8:00	04/29/2019	17:00
9210072	04/26/2019	8:00	04/29/2019	17:00
9210078	04/26/2019	8:00	04/29/2019	17:00
9210073	04/26/2019	8:00	04/29/2019	17:00
9210081	04/26/2019	8:00	04/29/2019	17:00
9210080	04/26/2019	8:00	04/29/2019	17:00
9210079	04/26/2019	8:00	04/29/2019	17:00
9210076	04/26/2019	8:00	04/29/2019	17:00
9210077	04/26/2019	8:00	04/29/2019	17:00
9210082	04/26/2019	8:00	04/29/2019	17:00
9210083	04/26/2019	8:00	04/29/2019	17:00
9210084	04/26/2019	8:00	04/29/2019	17:00
9210085	04/26/2019	9:00	04/29/2019	17:00
9210086	04/26/2019	9:00	04/29/2019	17:00
9210089	04/26/2019	9:00	04/29/2019	17:00
9210087	04/26/2019	9:00	04/29/2019	17:00

TAB]

9210088	04/26/2019	9:00	04/29/2019	17:00
9210091	04/26/2019	9:00	04/29/2019	17:00
9210090	04/26/2019	9:00	04/29/2019	17:00
9210093	04/26/2019	9:00	04/29/2019	17:00
9210092	04/26/2019	9:00	04/29/2019	17:00
9210095	04/26/2019	9:00	04/29/2019	17:00
9210094	04/26/2019	9:00	04/29/2019	17:00
9210096	04/26/2019	9:00	04/29/2019	17:00
9210098	04/26/2019	9:00	04/29/2019	17:00
9210097	04/26/2019	9:00	04/29/2019	17:00
9210099	04/26/2019	9:00	04/29/2019	17:00
9210100	04/26/2019	9:00	04/29/2019	17:00
9209902	04/26/2019	9:00	04/29/2019	17:00
9209901	04/26/2019	9:00	04/29/2019	17:00
9209905	04/26/2019	9:00	04/29/2019	17:00
9209903	04/26/2019	9:00	04/29/2019	17:00
9209906	04/26/2019	9:00	04/29/2019	17:00
9209907	04/26/2019	9:00	04/29/2019	17:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Pitts	Main School	R27		1
68	Pitts	Main School	R26		1
68	Pitts	Main School	R25		1
68	Pitts	Main School	R24		1
68	Pitts	Main School	R23		1
68	Pitts	Main School	R202		1
68	Pitts	Main School	R201		1
68	Pitts	Main School	R22		1
68	Pitts	Main School	R21		1
68	Pitts	Main School	Nurse		1
68	Pitts	Main School	R14		1
68	Pitts	Main School	Johnson		1
68	Pitts	Main School	R13		1
68	Pitts	Main School	R12		1
68	Pitts	Main School	R103		1
68	Pitts	Main School	R102		1
68	Pitts	Main School	R101		1
68	Pitts	Main School	R11		1
68	Pitts	Main School	R11		1
68	Pitts	Main School	R11		1
68	Pitts	Main School	R10		1
68	Pitts	Main School	R10		1
68	Pitts	Main School	Cafeteria #1		1
68	Pitts	Main School	Cafeteria #2		1
68	Pitts	Main School	Veight Room		1
68	Pitts	Main School	Veight Room		1
68	Pitts	Main School	Gym #1		1
68	Pitts	Main School	Gym #1		1
68	Pitts	Main School	Stage		1
68	Pitts	Main School	Stage		1
68	Pitts	Main School	Gym #2		1
68	Pitts	Main School	Gym #2		1
68	Pitts	Main School	R54		1
68	Pitts	Main School	R54		1
68	Pitts	Main School	R52		1
68	Pitts	Main School	R53		1
68	Pitts	Main School	R51		1
68	Pitts	Main School	Library		1
68	Pitts	Main School	R50		1
68	Pitts	Main School	R49		1
68	Pitts	Main School	R48		1
68	Pitts	Main School	R47		1
68	Pitts	Main School	R46		1
68	Pitts	Main School	R45		1
68	Pitts	Main School	R403		1

TAB]

68	Pitts	Main School	R401	1
68	Pitts	Main School	R44	1
68	Pitts	Main School	R43	1
68	Pitts	Main School	R42	1
68	Pitts	Main School	R41	1
68	Pitts	Main School	Study Hall	1
68	Pitts	Main School	Study Hall	1
68	Pitts	Main School	R38	1
68	Pitts	Main School	R37	1
68	Pitts	Main School	R36	1
68	Pitts	Main School	R35	1
68	Pitts	Main School	R302	1
68	Pitts	Main School	R301	1
68	Pitts	Main School	R34	1
68	Pitts	Main School	R33	1
68	Pitts	Main School	R32	1
68	Pitts	Main School	R31	1
68	Pitts	Main School	R30	1

Radon test result report for:**PITTS
MAIN SCHOOL**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9210064	10	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.7 ± 0.3	2019-05-01
9210065	10	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.6 ± 0.3	2019-05-01
9210061	101	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	< 0.3	2019-05-01
9210057	102	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	< 0.3	2019-05-01
9210060	103	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.7 ± 0.3	2019-05-01
9210058	11	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.7 ± 0.3	2019-05-01
9210062	11	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.7 ± 0.3	2019-05-01
9210063	11	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	1.0 ± 0.3	2019-05-01
9210059	12	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	1.4 ± 0.3	2019-05-01
9210051	13	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	1.4 ± 0.3	2019-05-01
9210055	14	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	1.3 ± 0.3	2019-05-01
9210053	201	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.7 ± 0.3	2019-05-01
9210052	202	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.5 ± 0.3	2019-05-01
9210050	21	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.9 ± 0.3	2019-05-01
9210048	22	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.8 ± 0.3	2019-05-01
9210049	23	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.8 ± 0.3	2019-05-01
9210047	24	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.8 ± 0.3	2019-05-01
9210046	25	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.8 ± 0.3	2019-05-01
9210043	26	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.7 ± 0.3	2019-05-01
9210045	27	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.7 ± 0.3	2019-05-01
9209907	30	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	1.6 ± 0.3	2019-05-01
9209902	301	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	1.6 ± 0.3	2019-05-01
9210100	302	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	1.8 ± 0.3	2019-05-01
9209906	31	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	1.2 ± 0.3	2019-05-01
9209903	32	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	1.5 ± 0.3	2019-05-01
9209905	33	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	1.6 ± 0.3	2019-05-01
9209901	34	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	1.7 ± 0.3	2019-05-01
9210099	35	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	1.6 ± 0.3	2019-05-01
9210097	36	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	1.7 ± 0.3	2019-05-01
9210098	37	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	1.5 ± 0.3	2019-05-01
9210096	38	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	1.7 ± 0.3	2019-05-01
9210088	401	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	1.1 ± 0.3	2019-05-01
9210087	403	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	1.2 ± 0.3	2019-05-01
9210092	41	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	1.1 ± 0.3	2019-05-01
9210093	42	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	0.8 ± 0.3	2019-05-01
9210090	43	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	1.4 ± 0.3	2019-05-01
9210091	44	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	1.2 ± 0.3	2019-05-01

Radon test result report for:**PITTS
MAIN SCHOOL**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9210089	45	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	1.2 ± 0.3	2019-05-01
9210086	46	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	1.1 ± 0.3	2019-05-01
9210085	47	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	1.2 ± 0.3	2019-05-01
9210084	48	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	1.5 ± 0.3	2019-05-01
9210083	49	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	1.1 ± 0.3	2019-05-01
9210082	50	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	1.0 ± 0.3	2019-05-01
9210076	51	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.5 ± 0.3	2019-05-01
9210080	52	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.7 ± 0.3	2019-05-01
9210079	53	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.7 ± 0.3	2019-05-01
9210073	54	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.5 ± 0.3	2019-05-01
9210081	54	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.6 ± 0.3	2019-05-01
9210067	CAFETERIA #1	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.8 ± 0.3	2019-05-01
9210066	CAFETERIA #2	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.7 ± 0.3	2019-05-01
9210070	GYM #1	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	1.2 ± 0.3	2019-05-01
9210074	GYM #1	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.8 ± 0.3	2019-05-01
9210078	GYM #2	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.8 ± 0.3	2019-05-01
9210072	GYM #2	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.8 ± 0.3	2019-05-01
9210056	JOHNSON	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	1.2 ± 0.3	2019-05-01
9210077	LIBRARY	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	2.5 ± 0.3	2019-05-01
9210054	NURSE	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.9 ± 0.3	2019-05-01
9210071	STAGE	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.7 ± 0.3	2019-05-01
9210075	STAGE	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	0.9 ± 0.3	2019-05-01
9210094	STUDY HALL	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	1.5 ± 0.3	2019-05-01
9210095	STUDY HALL	2019-04-26 @ 9:00 am	2019-04-29 @ 5:00 pm	1.2 ± 0.3	2019-05-01
9210068	WEIGHT ROOM	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	1.7 ± 0.3	2019-05-01
9210069	WEIGHT ROOM	2019-04-26 @ 8:00 am	2019-04-29 @ 5:00 pm	1.5 ± 0.3	2019-05-01

Radon test result report for:
SOUTH HIGH SCHOOL
MAIN SCHOOL

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9209926	1	2019-04-26 @ 9:00 am	2019-04-29 @ 4:00 pm	< 0.3	2019-05-01
9209913	10	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209927	109	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	0.5 ± 0.3	2019-05-01
9209963	11	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	0.6 ± 0.3	2019-05-01
9209964	11	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	0.6 ± 0.3	2019-05-01
9209917	110	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209925	111	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209918	112	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	0.7 ± 0.3	2019-05-01
9209924	113	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209919	114	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209923	115	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	0.6 ± 0.3	2019-05-01
9209922	119	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	0.6 ± 0.3	2019-05-01
9209965	12	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209916	121	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	0.5 ± 0.3	2019-05-01
9209921	121	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	0.6 ± 0.3	2019-05-01
9209943	123	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	1.2 ± 0.3	2019-05-01
9209941	125	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	1.0 ± 0.3	2019-05-01
9209944	127	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	1.4 ± 0.3	2019-05-01
9209945	129	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	1.2 ± 0.3	2019-05-01
9209961	13	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	0.7 ± 0.3	2019-05-01
9209951	133	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	1.0 ± 0.3	2019-05-01
9209954	134	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	1.2 ± 0.3	2019-05-01
9209947	135	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	1.1 ± 0.3	2019-05-01
9209953	136	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	0.9 ± 0.3	2019-05-01
9209950	137	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	1.1 ± 0.3	2019-05-01
9209952	138	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	1.3 ± 0.3	2019-05-01
9209948	139	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	1.2 ± 0.3	2019-05-01
9209966	14	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209949	140	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	1.4 ± 0.3	2019-05-01
9209946	142	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	0.9 ± 0.3	2019-05-01
9209962	15	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209967	16	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209956	17	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209955	18	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	2.3 ± 0.3	2019-05-01
9209957	19	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	3.4 ± 0.3	2019-05-01
9209908	2	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209958	20	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	3.0 ± 0.3	2019-05-01

Radon test result report for:
SOUTH HIGH SCHOOL
MAIN SCHOOL

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9209960	21	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	2.6 ± 0.3	2019-05-01
9209959	22	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	1.9 ± 0.3	2019-05-01
9209971	23	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	0.6 ± 0.3	2019-05-01
9209968	24	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209970	25	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209969	26	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	0.6 ± 0.3	2019-05-01
9209973	27	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209972	28	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209975	29	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	0.7 ± 0.3	2019-05-01
9209932	3	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	0.8 ± 0.3	2019-05-01
9209931	31	2019-04-26 @ 9:00 am	2019-04-29 @ 4:00 pm	< 0.3	2019-05-01
9209940	32	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209942	34	2019-04-26 @ 10:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209939	35	2019-04-26 @ 10:00 am	2019-04-29 @ 4:00 pm	< 0.3	2019-05-01
9209976	36	2019-04-26 @ 11:00 am	2019-04-29 @ 4:00 pm	1.5 ± 0.3	2019-05-01
9209936	36	2019-04-26 @ 10:00 am	2019-04-29 @ 4:00 pm	1.6 ± 0.3	2019-05-01
9209974	37	2019-04-26 @ 11:00 am	2019-04-29 @ 4:00 pm	< 0.3	2019-05-01
9209977	38	2019-04-26 @ 11:00 am	2019-04-29 @ 4:00 pm	1.4 ± 0.3	2019-05-01
9209978	38	2019-04-26 @ 11:00 am	2019-04-29 @ 4:00 pm	1.7 ± 0.3	2019-05-01
9209983	39	2019-04-26 @ 11:00 am	2019-04-29 @ 4:00 pm	< 0.3	2019-05-01
9209909	4	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209979	40	2019-04-26 @ 11:00 am	2019-04-29 @ 4:00 pm	3.7 ± 0.3	2019-05-01
9209980	40	2019-04-26 @ 11:00 am	2019-04-29 @ 4:00 pm	4.6 ± 0.4	2019-05-01
9209981	41	2019-04-26 @ 11:00 am	2019-04-29 @ 4:00 pm	0.5 ± 0.3	2019-05-01
9209930	5	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209911	6	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209933	60	2019-04-26 @ 10:00 am	2019-04-29 @ 4:00 pm	3.2 ± 0.3	2019-05-01
9209937	61	2019-04-26 @ 10:00 am	2019-04-29 @ 4:00 pm	4.0 ± 0.3	2019-05-01
9209934	62	2019-04-26 @ 10:00 am	2019-04-29 @ 4:00 pm	2.6 ± 0.3	2019-05-01
9209938	63	2019-04-26 @ 10:00 am	2019-04-29 @ 4:00 pm	9.6 ± 0.6	2019-05-01
9209928	7	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209912	8	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209929	9	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	0.6 ± 0.3	2019-05-01
9209984	CAFETERIA	2019-04-26 @ 11:00 am	2019-04-29 @ 4:00 pm	1.5 ± 0.3	2019-05-01
9209982	CAFETERIA	2019-04-26 @ 11:00 am	2019-04-29 @ 4:00 pm	1.1 ± 0.3	2019-05-01
9209989	GYM	2019-04-26 @ 11:00 am	2019-04-29 @ 4:00 pm	0.9 ± 0.3	2019-05-01
9209990	GYM	2019-04-26 @ 11:00 am	2019-04-29 @ 4:00 pm	1.2 ± 0.3	2019-05-01

May 1, 2019

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:
**SOUTH HIGH SCHOOL
MAIN SCHOOL**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9209935	HALLWAY BY R6	2019-04-26 @ 11:00 am	2019-04-29 @ 4:00 pm	< 0.3	2019-05-01
9209991	HEALTH ROOM	2019-04-26 @ 11:00 am	2019-04-29 @ 4:00 pm	0.5 ± 0.3	2019-05-01
9209986	JROTC	2019-04-26 @ 11:00 am	2019-04-29 @ 4:00 pm	1.3 ± 0.3	2019-05-01
9209987	JROTC	2019-04-26 @ 11:00 am	2019-04-29 @ 4:00 pm	1.3 ± 0.3	2019-05-01
9209915	MEDIA CENTER	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	0.9 ± 0.3	2019-05-01
9209920	MEDIA CENTER	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	1.0 ± 0.3	2019-05-01
9209910	STAGE	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	1.5 ± 0.3	2019-05-01
9209904	STAGE	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	1.7 ± 0.3	2019-05-01
9209914	TEACHER LOUNGE	2019-04-26 @ 9:00 am	2019-04-29 @ 3:00 pm	< 0.3	2019-05-01
9209985	TRAINING ROOM	2019-04-26 @ 11:00 am	2019-04-29 @ 4:00 pm	< 0.3	2019-05-01
9209988	WEIGHT ROOM	2019-04-26 @ 11:00 am	2019-04-29 @ 4:00 pm	< 0.3	2019-05-01

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

PSAS

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00

* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9209809	04/15/2019	16:00	04/18/2019	17:00
9209801	04/15/2019	16:00	04/18/2019	17:00
9209803	04/15/2019	16:00	04/18/2019	17:00
9210128	04/15/2019	16:00	04/18/2019	17:00
9209805	04/15/2019	16:00	04/18/2019	17:00
9209806	04/15/2019	16:00	04/18/2019	17:00
9209802	04/15/2019	16:00	04/18/2019	17:00
9209808	04/15/2019	16:00	04/18/2019	17:00
9209807	04/15/2019	16:00	04/18/2019	17:00
9209811	04/15/2019	16:00	04/18/2019	17:00
9209812	04/15/2019	16:00	04/18/2019	17:00
9209814	04/15/2019	16:00	04/18/2019	17:00
9209817	04/15/2019	16:00	04/18/2019	17:00
9209815	04/15/2019	16:00	04/18/2019	17:00
9209804	04/15/2019	16:00	04/18/2019	17:00
9209820	04/15/2019	16:00	04/18/2019	17:00
9209913	04/15/2019	16:00	04/18/2019	17:00
9209816	04/15/2019	16:00	04/18/2019	17:00
9209819	04/15/2019	16:00	04/18/2019	17:00
9209827	04/15/2019	16:00	04/18/2019	17:00
9209821	04/15/2019	16:00	04/18/2019	17:00
9209822	04/15/2019	16:00	04/18/2019	17:00
9209818	04/15/2019	16:00	04/18/2019	17:00
9209825	04/15/2019	16:00	04/18/2019	17:00
9209828	04/15/2019	16:00	04/18/2019	17:00
9209823	04/15/2019	16:00	04/18/2019	17:00
9209824	04/15/2019	16:00	04/18/2019	17:00
9209826	04/15/2019	16:00	04/18/2019	17:00
9209829	04/15/2019	16:00	04/18/2019	17:00
9209830	04/15/2019	16:00	04/18/2019	17:00
9209836	04/15/2019	16:00	04/18/2019	17:00
9209835	04/15/2019	16:00	04/18/2019	17:00
9209834	04/15/2019	16:00	04/18/2019	17:00
9209831	04/15/2019	16:00	04/18/2019	17:00
9209833	04/15/2019	16:00	04/18/2019	17:00
9209832	04/15/2019	16:00	04/18/2019	17:00
9209838	04/15/2019	16:00	04/18/2019	17:00
9209839	04/15/2019	16:00	04/18/2019	17:00
9209841	04/15/2019	16:00	04/18/2019	17:00
9209910	04/15/2019	16:00	04/18/2019	17:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional) (enter proper
 0=Basement)

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	PSAS	Main School	Music room		0
68	PSAS	Main School	Music Room		0
68	PSAS	Main School	R20		1
68	PSAS	Main School	R21		1
68	PSAS	Main School	R22		1
68	PSAS	Main School	R24		1
68	PSAS	Main School	R25		1
68	PSAS	Main School	R31		1
68	PSAS	Main School	R30		1
68	PSAS	Main School	R33		1
68	PSAS	Main School	R32		1
68	PSAS	Main School	R35		1
68	PSAS	Main School	R35		1
68	PSAS	Main School	R34		1
68	PSAS	Main School	R36		1
68	PSAS	Main School	Gym		1
68	PSAS	Main School	Gym		1
68	PSAS	Main School	Cafeteria		0
68	PSAS	Main School	Cafeteria		0
68	PSAS	Main School	R37		1
68	PSAS	Main School	R38		1
68	PSAS	Main School	R39		1
68	PSAS	Main School	R40		1
68	PSAS	Main School	R40		1
68	PSAS	Main School	Library		1
68	PSAS	Main School	Library		1
68	PSAS	Main School	R5		1
68	PSAS	Main School	R4		1
68	PSAS	Main School	R7		1
68	PSAS	Main School	R8		1
68	PSAS	Main School	R6		1
68	PSAS	Main School	R3		1
68	PSAS	Main School	Portable 1		1
68	PSAS	Main School	Portable 2		1
68	PSAS	Main School	Portable 3		1
68	PSAS	Main School	Portable 4		1
68	PSAS	Main School	Portable 5		1
68	PSAS	Main School	Portable 6		1
68	PSAS	Main School	Portable 7		1
68	PSAS	Main School	R26		1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9209801	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	MUSIC ROOM		0	1.7
9209802	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	25		1	< 0.3
9209803	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	20		1	1.0
9209804	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	36		1	< 0.3
9209805	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	22		1	1.3
9209806	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	24		1	0.9
9209807	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	30		1	0.5
9209808	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	31		1	0.6
9209809	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	MUSIC ROOM		0	1.3
9209811	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	33		1	1.1
9209812	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	32		1	0.7
9209814	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	35		1	1.1
9209815	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	R34		1	1.4
9209816	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	CAFETERIA		0	1.0
9209817	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	R35		1	< 0.3
9209818	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	40		1	0.5
9209819	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	CAFETERIA		0	0.9
9209820	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	GYM		1	0.7
9209821	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	R38		1	0.7
9209822	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	R39		1	< 0.3
9209823	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	LIBRARY		1	1.0
9209824	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	R5		1	0.7
9209825	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	40		1	< 0.3
9209826	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	R4		1	0.8
9209827	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	R37		1	1.2
9209828	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	LIBRARY		1	1.0
9209829	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	R7		1	0.5
9209830	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	R8		1	0.7
9209831	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	PORTABLE 2		1	< 0.3
9209832	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	PORTABLE 4		1	< 0.3
9209833	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	PORTABLE 3		1	< 0.3
9209834	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	PORTABLE 1		1	< 0.3
9209835	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	R3		1	< 0.3
9209836	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	R6		1	< 0.3
9209838	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	PORTABLE 5		1	< 0.3

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9209839	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	PORTABLE 6		1	< 0.3
9209841	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	PORTABLE 7		1	0.6
9209910	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	R26		1	
9209913	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	GYM		1	
9210128	2019-04-15	4:00 pm	2019-04-18	5:00 pm	68	PSAS	MAIN SCHOOL	21		1	1.3

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Risley Middle School

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00
* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9220505	05/03/2019	17:00	05/07/2019	14:00
9220506	05/03/2019	17:00	05/07/2019	14:00
9220508	05/03/2019	17:00	05/07/2019	14:00
9220510	05/03/2019	17:00	05/07/2019	14:00
9220511	05/03/2019	17:00	05/07/2019	14:00
9220512	05/03/2019	17:00	05/07/2019	14:00
9220501	05/03/2019	17:00	05/07/2019	14:00
9220519	05/03/2019	17:00	05/07/2019	14:00
9220520	05/03/2019	17:00	05/07/2019	14:00
9220515	05/03/2019	17:00	05/07/2019	14:00
9220516	05/03/2019	17:00	05/07/2019	14:00
9220523	05/03/2019	17:00	05/07/2019	14:00
9220524	05/03/2019	17:00	05/07/2019	14:00
9220517	05/03/2019	17:00	05/07/2019	14:00
9220518	05/03/2019	17:00	05/07/2019	14:00
9220525	05/03/2019	17:00	05/07/2019	14:00
9220526	05/03/2019	17:00	05/07/2019	14:00
9220531	05/03/2019	17:00	05/07/2019	14:00
9220532	05/03/2019	17:00	05/07/2019	14:00
9220527	05/03/2019	17:00	05/07/2019	14:00
9220528	05/03/2019	17:00	05/07/2019	14:00
9220534	05/03/2019	17:00	05/07/2019	14:00
9220529	05/03/2019	17:00	05/07/2019	14:00
9220536	05/03/2019	17:00	05/07/2019	14:00
9220537	05/03/2019	15:00	05/07/2019	14:00
9220541	05/03/2019	15:00	05/07/2019	14:00
9220543	05/03/2019	17:00	05/07/2019	14:00
9220544	05/03/2019	17:00	05/07/2019	14:00
9220550	05/03/2019	17:00	05/07/2019	14:00
9220549	05/03/2019	17:00	05/07/2019	14:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Risley Middle School	Main School	R101		1
68	Risley Middle School	Main School	R103		1
68	Risley Middle School	Main School	R105		1
68	Risley Middle School	Main School	R106		1
68	Risley Middle School	Main School	R108		1
68	Risley Middle School	Main School	R109		1
68	Risley Middle School	Main School	R111		1
68	Risley Middle School	Main School	R113		1
68	Risley Middle School	Main School	R114		1
68	Risley Middle School	Main School	R115		1
68	Risley Middle School	Main School	R117		1
68	Risley Middle School	Main School	R118		1
68	Risley Middle School	Main School	R119		1
68	Risley Middle School	Main School	R121		1
68	Risley Middle School	Main School	R120		1
68	Risley Middle School	Main School	R122		1
68	Risley Middle School	Main School	R122		1
68	Risley Middle School	Main School	R122		1
68	Risley Middle School	Main School	R129		1
68	Risley Middle School	Main School	R146		1
68	Risley Middle School	Main School	R148		1
68	Risley Middle School	Main School	R150		1
68	Risley Middle School	Main School	R142		1
68	Risley Middle School	Main School	R141		1
68	Risley Middle School	Main School	R141		1
68	Risley Middle School	Main School	R139		1
68	Risley Middle School	Main School	R139		1
68	Risley Middle School	Main School	R133		1
68	Risley Middle School	Main School	R130		1
68	Risley Middle School	Main School	R130		1

Radon test result report for:
RISLEY MIDDLE SCHOOL
MAIN SCHOOL

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9220505	101	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	< 0.3	2019-05-08
9220506	103	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	0.5 ± 0.3	2019-05-08
9220508	105	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	< 0.3	2019-05-08
9220510	106	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	< 0.3	2019-05-08
9220511	108	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	1.1 ± 0.3	2019-05-08
9220512	109	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	< 0.3	2019-05-08
9220501	111	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	0.5 ± 0.3	2019-05-08
9220519	113	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	< 0.3	2019-05-08
9220520	114	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	0.5 ± 0.3	2019-05-08
9220515	115	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	0.8 ± 0.3	2019-05-08
9220516	117	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	0.6 ± 0.3	2019-05-08
9220523	118	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	< 0.3	2019-05-08
9220524	119	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	0.6 ± 0.3	2019-05-08
9220518	120	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	0.6 ± 0.3	2019-05-08
9220517	121	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	0.6 ± 0.3	2019-05-08
9220525	122	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	< 0.3	2019-05-08
9220526	122	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	0.7 ± 0.3	2019-05-08
9220531	122	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	0.7 ± 0.3	2019-05-08
9220532	129	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	< 0.3	2019-05-08
9220549	130	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	0.7 ± 0.3	2019-05-08
9220550	130	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	0.8 ± 0.3	2019-05-08
9220544	133	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	0.6 ± 0.3	2019-05-08
9220541	139	2019-05-03 @ 3:00 pm	2019-05-07 @ 2:00 pm	1.4 ± 0.3	2019-05-08
9220543	139	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	1.6 ± 0.3	2019-05-08
9220537	141	2019-05-03 @ 3:00 pm	2019-05-07 @ 2:00 pm	0.9 ± 0.3	2019-05-08
9220536	141	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	0.9 ± 0.3	2019-05-08
9220529	142	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	0.9 ± 0.3	2019-05-08
9220527	146	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	0.8 ± 0.3	2019-05-08
9220528	148	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	0.8 ± 0.3	2019-05-08
9220534	150	2019-05-03 @ 5:00 pm	2019-05-07 @ 2:00 pm	0.6 ± 0.3	2019-05-08

Roncalli Stem School

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00

* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9209793	04/24/2019	16:00	04/26/2019	17:00
9209795	04/24/2019	16:00	04/26/2019	17:00
9209792	04/24/2019	16:00	04/26/2019	17:00
9209800	04/24/2019	16:00	04/26/2019	17:00
9210001	04/24/2019	16:00	04/26/2019	17:00
9210002	04/24/2019	16:00	04/26/2019	17:00
9210004	04/24/2019	16:00	04/26/2019	17:00
9210003	04/24/2019	16:00	04/26/2019	17:00
9210005	04/24/2019	16:00	04/26/2019	17:00
9210008	04/24/2019	16:00	04/26/2019	17:00
9210009	04/24/2019	16:00	04/26/2019	17:00
9210006	04/24/2019	16:00	04/26/2019	17:00
9210012	04/24/2019	16:00	04/26/2019	17:00
9210015	04/24/2019	16:00	04/26/2019	17:00
9210016	04/24/2019	16:00	04/26/2019	17:00
9209799	04/24/2019	16:00	04/26/2019	17:00
9210010	04/24/2019	16:00	04/26/2019	17:00
9210011	04/24/2019	16:00	04/26/2019	17:00
9210022	04/24/2019	17:00	04/26/2019	17:00
9210024	04/24/2019	17:00	04/26/2019	17:00
9210025	04/24/2019	17:00	04/26/2019	17:00
9210007	04/24/2019	17:00	04/26/2019	17:00
9210013	04/24/2019	17:00	04/26/2019	17:00
9210017	04/24/2019	17:00	04/26/2019	17:00
9210018	04/24/2019	17:00	04/26/2019	17:00
9210023	04/24/2019	17:00	04/26/2019	17:00
9210026	04/24/2019	17:00	04/26/2019	17:00
9210031	04/24/2019	17:00	04/26/2019	17:00
9210019	04/24/2019	17:00	04/26/2019	17:00
9210014	04/24/2019	17:00	04/26/2019	17:00
9210020	04/24/2019	17:00	04/26/2019	17:00
9210021	04/24/2019	17:00	04/26/2019	17:00
9210028	04/24/2019	17:00	04/26/2019	17:00
9210030	04/24/2019	17:00	04/26/2019	17:00
9210029	04/24/2019	17:00	04/26/2019	17:00
9210034	04/24/2019	17:00	04/26/2019	17:00
9210035	04/24/2019	17:00	04/26/2019	17:00
9210036	04/24/2019	17:00	04/26/2019	17:00
9210027	04/24/2019	17:00	04/26/2019	17:00
9210037	04/24/2019	17:00	04/26/2019	17:00
9210033	04/24/2019	17:00	04/26/2019	17:00
9210032	04/24/2019	17:00	04/26/2019	17:00
9210038	04/24/2019	17:00	04/26/2019	17:00
9210040	04/24/2019	17:00	04/26/2019	17:00
9210039	04/24/2019	17:00	04/26/2019	17:00

TAB]

9210041	04/24/2019	17:00	04/26/2019	17:00
9210042	04/24/2019	17:00	04/26/2019	17:00
9210044	04/24/2019	17:00	04/26/2019	17:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=othe

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Roncalli Middle School	Main School	R1		1
68	Roncalli Middle School	Main School	R19		1
68	Roncalli Middle School	Main School	R18		1
68	Roncalli Middle School	Main School	R25		1
68	Roncalli Middle School	Main School	R29		1
68	Roncalli Middle School	Main School	R32		1
68	Roncalli Middle School	Main School	Cafeteria		1
68	Roncalli Middle School	Main School	Cafeteria		1
68	Roncalli Middle School	Main School	onference Rm		1
68	Roncalli Middle School	Main School	Stage/Studio		1
68	Roncalli Middle School	Main School	Stage/Studio		1
68	Roncalli Middle School	Main School	R7		1
68	Roncalli Middle School	Main School	R8		1
68	Roncalli Middle School	Main School	R8		1
68	Roncalli Middle School	Main School	Media		1
68	Roncalli Middle School	Main School	Media		1
68	Roncalli Middle School	Main School	R13		1
68	Roncalli Middle School	Main School	R15		1
68	Roncalli Middle School	Main School	R20		1
68	Roncalli Middle School	Main School	R22		1
68	Roncalli Middle School	Main School	Special Ed		1
68	Roncalli Middle School	Main School	Band Rm		1
68	Roncalli Middle School	Main School	Band Rm		1
68	Roncalli Middle School	Main School	R2		1
68	Roncalli Middle School	Main School	R4		1
68	Roncalli Middle School	Main School	R5		1
68	Roncalli Middle School	Main School	R6		1
68	Roncalli Middle School	Main School	R3		1
68	Roncalli Middle School	Main School	R9		1
68	Roncalli Middle School	Main School	R10		1
68	Roncalli Middle School	Main School	R11		1
68	Roncalli Middle School	Main School	R12		1
68	Roncalli Middle School	Main School	R14		1
68	Roncalli Middle School	Main School	R16		1
68	Roncalli Middle School	Main School	R17		1
68	Roncalli Middle School	Main School	R21		1
68	Roncalli Middle School	Main School	R26		1
68	Roncalli Middle School	Main School	R24		1
68	Roncalli Middle School	Main School	R28		1
68	Roncalli Middle School	Main School	R27		1
68	Roncalli Middle School	Main School	R30		1
68	Roncalli Middle School	Main School	Gym		1
68	Roncalli Middle School	Main School	Gym		1
68	Roncalli Middle School	Main School	Gym#2		1
68	Roncalli Middle School	Main School	Gym#2		1

TAB]

68	Roncalli Middle School	Main School Modular 45A	1
68	Roncalli Middle School	Main School Modular 45B	1
68	Roncalli Middle School	Main School Modular 45B	1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9209792	2019-04-24	4:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	18		1	2.5
9209793	2019-04-24	4:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	1		1	2.4
9209795	2019-04-24	4:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	19		1	3.3
9209799	2019-04-24	4:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	MEDIA		1	2.5
9209800	2019-04-24	4:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	25		1	1.2
9210001	2019-04-24	4:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	29		1	2.2
9210002	2019-04-24	4:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	32		1	1.5
9210003	2019-04-24	4:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	CAFETERIA		1	2.9
9210004	2019-04-24	4:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	CAFETERIA		1	2.3
9210005	2019-04-24	4:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	CONFRENCE RM		1	2.8
9210006	2019-04-24	4:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	7		1	3.2
9210007	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	BAND RM		1	2.6
9210008	2019-04-24	4:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	STAGE/STUDIO		1	4.9
9210009	2019-04-24	4:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	STAGE/STUDIO		1	4.8
9210010	2019-04-24	4:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	13		1	3.2
9210011	2019-04-24	4:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	15		1	2.8
9210012	2019-04-24	4:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	8		1	3.9
9210013	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	BAND RM		1	2.4
9210014	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	10		1	2.5
9210015	2019-04-24	4:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	8		1	3.9
9210016	2019-04-24	4:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	MEDIA		1	2.8
9210017	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	2		1	2.4
9210018	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	4		1	2.6
9210019	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	9		1	3.1
9210020	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	11		1	2.8
9210021	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	12		1	2.4
9210022	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	20		1	2.0
9210023	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	5		1	2.7
9210024	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	22		1	2.0
9210025	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	SPECIAL ED		1	2.4
9210026	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	6		1	2.4
9210027	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	28		1	3.1
9210028	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	14		1	2.2
9210029	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	17		1	2.8
9210030	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	16		1	2.5

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9210031	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	3		1	2.2
9210032	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	GYM		1	2.2
9210033	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	30		1	3.1
9210034	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	21		1	2.7
9210035	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	26		1	1.4
9210036	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	24		1	2.0
9210037	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	27		1	1.1
9210038	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	GYM		1	2.3
9210039	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	GYM#2		1	1.5
9210040	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	GYM#2		1	1.5
9210041	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	MODULAR 45A		1	< 0.3
9210042	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	MODULAR 45B		1	< 0.3
9210044	2019-04-24	5:00 pm	2019-04-26	5:00 pm	68	RONCALLI MIDDLE SCHOOL	MAIN SCHOOL	MODULAR 45B		1	< 0.3

Service Center

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00
* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9210102	04/23/2019	15:00	04/25/2019	15:00
9209715	04/23/2019	15:00	04/25/2019	15:00
9209712	04/23/2019	15:00	04/25/2019	15:00
9209716	04/23/2019	15:00	04/25/2019	15:00
9209718	04/23/2019	15:00	04/25/2019	16:00
9209719	04/23/2019	15:00	04/25/2019	16:00
9209720	04/23/2019	15:00	04/25/2019	16:00
9209717	04/23/2019	15:00	04/25/2019	16:00
9209722	04/23/2019	15:00	04/25/2019	16:00
9209721	04/23/2019	15:00	04/25/2019	16:00
9209723	04/23/2019	15:00	04/25/2019	16:00
9209724	04/23/2019	15:00	04/25/2019	16:00
9209726	04/23/2019	15:00	04/25/2019	16:00
9209728	04/23/2019	15:00	04/25/2019	16:00
9209730	04/23/2019	15:00	04/25/2019	16:00
9209731	04/23/2019	15:00	04/25/2019	16:00
9209733	04/23/2019	15:00	04/25/2019	16:00
9209725	04/23/2019	16:00	04/25/2019	16:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=oth

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	Service Center	Main Building	Johnson Office		1
68	Service Center	Main Building	Glen Saiz		1
68	Service Center	Main Building	Conference Room		1
68	Service Center	Main Building	Lawson		1
68	Service Center	Main Building	Marquenn		1
68	Service Center	Main Building	Kitchen		1
68	Service Center	Main Building	Office		1
68	Service Center	Main Building	Brain DDY		1
68	Service Center	Main Building	Ich Room		1
68	Service Center	Main Building	Heating Room		1
68	Service Center	Main Building	Pop Room		1
68	Service Center	Main Building	Shop Office		1
68	Service Center	Main Building	Splanker		1
68	Service Center	Main Building	Wood Shop		1
68	Service Center	Main Building	Wood Shop Office		1
68	Service Center	Main Building	Wood Shop Main		1
68	Service Center	Main Building	Blinds		1
68	Service Center	Main Building	Lunch Room		1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9209712	2019-04-23	3:00 pm	2019-04-25	3:00 pm	68	SERVICE CENTER	MAIN BUILDING	CONFERENCE ROOM		1	< 0.3
9209715	2019-04-23	3:00 pm	2019-04-25	3:00 pm	68	SERVICE CENTER	MAIN BUILDING	GLEN SAIZ		1	1.0
9209716	2019-04-23	3:00 pm	2019-04-25	3:00 pm	68	SERVICE CENTER	MAIN BUILDING	LAWSON		1	0.5
9209717	2019-04-23	3:00 pm	2019-04-25	4:00 pm	68	SERVICE CENTER	MAIN BUILDING	BRAIN DDY		1	0.5
9209718	2019-04-23	3:00 pm	2019-04-25	4:00 pm	68	SERVICE CENTER	MAIN BUILDING	MARQUENN		1	0.5
9209719	2019-04-23	3:00 pm	2019-04-25	4:00 pm	68	SERVICE CENTER	MAIN BUILDING	KITCHEN		1	0.6
9209720	2019-04-23	3:00 pm	2019-04-25	4:00 pm	68	SERVICE CENTER	MAIN BUILDING	OFFICE		1	0.5
9209721	2019-04-23	3:00 pm	2019-04-25	4:00 pm	68	SERVICE CENTER	MAIN BUILDING	HEATING ROOM		1	< 0.3
9209722	2019-04-23	3:00 pm	2019-04-25	4:00 pm	68	SERVICE CENTER	MAIN BUILDING	ICH ROOM		1	0.5
9209723	2019-04-23	3:00 pm	2019-04-25	4:00 pm	68	SERVICE CENTER	MAIN BUILDING	POP ROOM		1	0.6
9209724	2019-04-23	3:00 pm	2019-04-25	4:00 pm	68	SERVICE CENTER	MAIN BUILDING	SHOP OFFICE		1	0.8
9209725	2019-04-23	4:00 pm	2019-04-25	4:00 pm	68	SERVICE CENTER	MAIN BUILDING	LUNCH ROOM		1	0.6
9209726	2019-04-23	3:00 pm	2019-04-25	4:00 pm	68	SERVICE CENTER	MAIN BUILDING	SPLANKER		1	1.1
9209728	2019-04-23	3:00 pm	2019-04-25	4:00 pm	68	SERVICE CENTER	MAIN BUILDING	WOOD SHOP		1	0.8
9209730	2019-04-23	3:00 pm	2019-04-25	4:00 pm	68	SERVICE CENTER	MAIN BUILDING	WOOD SHOP OFFICE		1	0.5
9209731	2019-04-23	3:00 pm	2019-04-25	4:00 pm	68	SERVICE CENTER	MAIN BUILDING	WOOD SHOP MAIN		1	0.8
9209733	2019-04-23	3:00 pm	2019-04-25	4:00 pm	68	SERVICE CENTER	MAIN BUILDING	BLINDS		1	1.5
9210102	2019-04-23	3:00 pm	2019-04-25	3:00 pm	68	SERVICE CENTER	MAIN BUILDING	JOHNSON OFFICE		1	0.7

South High School

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00

* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9209904	04/26/2019	9:00	04/29/2019	15:00
9209910	04/26/2019	9:00	04/29/2019	15:00
9209908	04/26/2019	9:00	04/29/2019	15:00
9209909	04/26/2019	9:00	04/29/2019	15:00
9209911	04/26/2019	9:00	04/29/2019	15:00
9209912	04/26/2019	9:00	04/29/2019	15:00
9209913	04/26/2019	9:00	04/29/2019	15:00
9209914	04/26/2019	9:00	04/29/2019	15:00
9209915	04/26/2019	9:00	04/29/2019	15:00
9209920	04/26/2019	9:00	04/29/2019	15:00
9209917	04/26/2019	9:00	04/29/2019	15:00
9209918	04/26/2019	9:00	04/29/2019	15:00
9209919	04/26/2019	9:00	04/29/2019	15:00
9209921	04/26/2019	9:00	04/29/2019	15:00
9209916	04/26/2019	9:00	04/29/2019	15:00
9209922	04/26/2019	9:00	04/29/2019	15:00
9209923	04/26/2019	9:00	04/29/2019	15:00
9209924	04/26/2019	9:00	04/29/2019	15:00
9209925	04/26/2019	9:00	04/29/2019	15:00
9209927	04/26/2019	9:00	04/29/2019	15:00
9209929	04/26/2019	9:00	04/29/2019	15:00
9209928	04/26/2019	9:00	04/29/2019	15:00
9209930	04/26/2019	9:00	04/29/2019	15:00
9209932	04/26/2019	9:00	04/29/2019	15:00
9209926	04/26/2019	9:00	04/29/2019	16:00
9209931	04/26/2019	9:00	04/29/2019	16:00
9209936	04/26/2019	10:00	04/29/2019	16:00
9209937	04/26/2019	10:00	04/29/2019	16:00
9209938	04/26/2019	10:00	04/29/2019	16:00
9209934	04/26/2019	10:00	04/29/2019	16:00
9209933	04/26/2019	10:00	04/29/2019	16:00
9209939	04/26/2019	10:00	04/29/2019	16:00
9209940	04/26/2019	10:00	04/29/2019	15:00
9209942	04/26/2019	10:00	04/29/2019	15:00
9209943	04/26/2019	10:00	04/29/2019	15:00
9209941	04/26/2019	10:00	04/29/2019	15:00
9209944	04/26/2019	10:00	04/29/2019	15:00
9209945	04/26/2019	10:00	04/29/2019	15:00
9209946	04/26/2019	10:00	04/29/2019	15:00
9209948	04/26/2019	10:00	04/29/2019	15:00
9209949	04/26/2019	10:00	04/29/2019	15:00
9209952	04/26/2019	10:00	04/29/2019	15:00
9209950	04/26/2019	10:00	04/29/2019	15:00
9209947	04/26/2019	10:00	04/29/2019	15:00
9209953	04/26/2019	10:00	04/29/2019	15:00

TAB]

9209954	04/26/2019	10:00	04/29/2019	15:00
9209951	04/26/2019	10:00	04/29/2019	15:00
9209955	04/26/2019	10:00	04/29/2019	15:00
9209957	04/26/2019	10:00	04/29/2019	15:00
9209958	04/26/2019	10:00	04/29/2019	15:00
9209960	04/26/2019	10:00	04/29/2019	15:00
9209959	04/26/2019	10:00	04/29/2019	15:00
9209956	04/26/2019	10:00	04/29/2019	15:00
9209962	04/26/2019	10:00	04/29/2019	15:00
9209961	04/26/2019	10:00	04/29/2019	15:00
9209964	04/26/2019	10:00	04/29/2019	15:00
9209963	04/26/2019	10:00	04/29/2019	15:00
9209965	04/26/2019	10:00	04/29/2019	15:00
9209966	04/26/2019	10:00	04/29/2019	15:00
9209967	04/26/2019	10:00	04/29/2019	15:00
9209968	04/26/2019	10:00	04/29/2019	15:00
9209971	04/26/2019	10:00	04/29/2019	15:00
9209969	04/26/2019	10:00	04/29/2019	15:00
9209970	04/26/2019	10:00	04/29/2019	15:00
9209972	04/26/2019	10:00	04/29/2019	15:00
9209973	04/26/2019	10:00	04/29/2019	15:00
9209975	04/26/2019	10:00	04/29/2019	15:00
9209974	04/26/2019	11:00	04/29/2019	16:00
9209976	04/26/2019	11:00	04/29/2019	16:00
9209978	04/26/2019	11:00	04/29/2019	16:00
9209977	04/26/2019	11:00	04/29/2019	16:00
9209979	04/26/2019	11:00	04/29/2019	16:00
9209980	04/26/2019	11:00	04/29/2019	16:00
9209983	04/26/2019	11:00	04/29/2019	16:00
9209981	04/26/2019	11:00	04/29/2019	16:00
9209982	04/26/2019	11:00	04/29/2019	16:00
9209984	04/26/2019	11:00	04/29/2019	16:00
9209985	04/26/2019	11:00	04/29/2019	16:00
9209986	04/26/2019	11:00	04/29/2019	16:00
9209987	04/26/2019	11:00	04/29/2019	16:00
9209988	04/26/2019	11:00	04/29/2019	16:00
9209989	04/26/2019	11:00	04/29/2019	16:00
9209990	04/26/2019	11:00	04/29/2019	16:00
9209991	04/26/2019	11:00	04/29/2019	16:00
9209935	04/26/2019	11:00	04/29/2019	16:00

(+ / - 5 degrees) (your designations for facility, building and room)
 for example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=oth

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	South High School	Main School	Stage		1
68	South High School	Main School	Stage		1
68	South High School	Main School	R2		1
68	South High School	Main School	R4		1
68	South High School	Main School	R6		1
68	South High School	Main School	R8		1
68	South High School	Main School	R10		1
68	South High School	Main School	Teacher Lounge		1
68	South High School	Main School	Media Center		1
68	South High School	Main School	Media Center		1
68	South High School	Main School	R110		1
68	South High School	Main School	R112		1
68	South High School	Main School	R114		1
68	South High School	Main School	R121		1
68	South High School	Main School	R121		1
68	South High School	Main School	R119		1
68	South High School	Main School	R115		1
68	South High School	Main School	R113		1
68	South High School	Main School	R111		1
68	South High School	Main School	R109		1
68	South High School	Main School	R9		1
68	South High School	Main School	R7		1
68	South High School	Main School	R5		1
68	South High School	Main School	R3		1
68	South High School	Main School	R1		1
68	South High School	Main School	R31		1
68	South High School	Main School	R36		1
68	South High School	Main School	R61		1
68	South High School	Main School	R63		1
68	South High School	Main School	R62		1
68	South High School	Main School	R60		1
68	South High School	Main School	R35		1
68	South High School	Main School	R32		1
68	South High School	Main School	R34		1
68	South High School	Main School	R123		1
68	South High School	Main School	R125		1
68	South High School	Main School	R127		1
68	South High School	Main School	R129		1
68	South High School	Main School	R142		1
68	South High School	Main School	R139		1
68	South High School	Main School	R140		1
68	South High School	Main School	R138		1
68	South High School	Main School	R137		1
68	South High School	Main School	R135		1
68	South High School	Main School	R136		1

TAB]

68	South High School	Main School	R134	1
68	South High School	Main School	R133	1
68	South High School	Main School	R18	1
68	South High School	Main School	R19	1
68	South High School	Main School	R20	1
68	South High School	Main School	R21	1
68	South High School	Main School	R22	1
68	South High School	Main School	R17	1
68	South High School	Main School	R15	1
68	South High School	Main School	R13	1
68	South High School	Main School	R11	1
68	South High School	Main School	R11	1
68	South High School	Main School	R12	1
68	South High School	Main School	R14	1
68	South High School	Main School	R16	1
68	South High School	Main School	R24	1
68	South High School	Main School	R23	1
68	South High School	Main School	R26	1
68	South High School	Main School	R25	1
68	South High School	Main School	R28	1
68	South High School	Main School	R27	1
68	South High School	Main School	R29	1
68	South High School	Main School	R37	1
68	South High School	Main School	R36	1
68	South High School	Main School	R38	1
68	South High School	Main School	R38	1
68	South High School	Main School	R40	1
68	South High School	Main School	R40	1
68	South High School	Main School	R39	1
68	South High School	Main School	R41	1
68	South High School	Main School	Cafeteria	1
68	South High School	Main School	Cafeteria	1
68	South High School	Main School	raining Room	1
68	South High School	Main School	JROTC	1
68	South High School	Main School	JROTC	1
68	South High School	Main School	Veight Room	1
68	South High School	Main School	Gym	1
68	South High School	Main School	Gym	1
68	South High School	Main School	health Room	1
68	South High School	Main School	allway by R6	1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9209904	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	STAGE		1	1.7
9209908	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	2		1	< 0.3
9209909	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	4		1	< 0.3
9209910	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	STAGE		1	1.5
9209911	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	6		1	< 0.3
9209912	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	8		1	< 0.3
9209913	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	10		1	< 0.3
9209914	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	TEACHER LOUNGE		1	< 0.3
9209915	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	MEDIA CENTER		1	0.9
9209916	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	121		1	0.5
9209917	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	110		1	< 0.3
9209918	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	112		1	0.7
9209919	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	114		1	< 0.3
9209920	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	MEDIA CENTER		1	1.0
9209921	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	121		1	0.6
9209922	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	119		1	0.6
9209923	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	115		1	0.6
9209924	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	113		1	< 0.3
9209925	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	111		1	< 0.3
9209926	2019-04-26	9:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	1		1	< 0.3
9209927	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	109		1	0.5
9209928	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	7		1	< 0.3
9209929	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	9		1	0.6
9209930	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	5		1	< 0.3
9209931	2019-04-26	9:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	31		1	< 0.3
9209932	2019-04-26	9:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	3		1	0.8
9209933	2019-04-26	10:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	60		1	3.2
9209934	2019-04-26	10:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	62		1	2.6
9209935	2019-04-26	11:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	HALLWAY BY R6		1	< 0.3
9209936	2019-04-26	10:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	36		1	1.6
9209937	2019-04-26	10:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	61		1	4.0
9209938	2019-04-26	10:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	63		1	9.6
9209939	2019-04-26	10:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	35		1	< 0.3
9209940	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	32		1	< 0.3
9209941	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	125		1	1.0

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9209942	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	34		1	< 0.3
9209943	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	123		1	1.2
9209944	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	127		1	1.4
9209945	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	129		1	1.2
9209946	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	142		1	0.9
9209947	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	135		1	1.1
9209948	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	139		1	1.2
9209949	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	140		1	1.4
9209950	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	137		1	1.1
9209951	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	133		1	1.0
9209952	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	138		1	1.3
9209953	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	136		1	0.9
9209954	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	134		1	1.2
9209955	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	18		1	2.3
9209956	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	17		1	< 0.3
9209957	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	19		1	3.4
9209958	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	20		1	3.0
9209959	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	22		1	1.9
9209960	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	21		1	2.6
9209961	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	13		1	0.7
9209962	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	15		1	< 0.3
9209963	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	11		1	0.6
9209964	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	11		1	0.6
9209965	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	12		1	< 0.3
9209966	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	14		1	< 0.3
9209967	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	16		1	< 0.3
9209968	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	24		1	< 0.3
9209969	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	26		1	0.6
9209970	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	25		1	< 0.3
9209971	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	23		1	0.6
9209972	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	28		1	< 0.3
9209973	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	27		1	< 0.3
9209974	2019-04-26	11:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	37		1	< 0.3
9209975	2019-04-26	10:00 am	2019-04-29	3:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	29		1	0.7
9209976	2019-04-26	11:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	36		1	1.5

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9209977	2019-04-26	11:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	38		1	1.4
9209978	2019-04-26	11:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	38		1	1.7
9209979	2019-04-26	11:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	40		1	3.7
9209980	2019-04-26	11:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	40		1	4.6
9209981	2019-04-26	11:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	41		1	0.5
9209982	2019-04-26	11:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	CAFETERIA		1	1.1
9209983	2019-04-26	11:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	39		1	< 0.3
9209984	2019-04-26	11:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	CAFETERIA		1	1.5
9209985	2019-04-26	11:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	TRAINING ROOM		1	< 0.3
9209986	2019-04-26	11:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	JROTC		1	1.3
9209987	2019-04-26	11:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	JROTC		1	1.3
9209988	2019-04-26	11:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	WEIGHT ROOM		1	< 0.3
9209989	2019-04-26	11:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	GYM		1	0.9
9209990	2019-04-26	11:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	GYM		1	1.2
9209991	2019-04-26	11:00 am	2019-04-29	4:00 pm	68	SOUTH HIGH SCHOOL	MAIN SCHOOL	HEALTH ROOM		1	0.5

South Park Elementary

TAB]

(from test kit)

Times should be in 24 hour format, 1pm = 13:00

* round times so that 9:31 and 10:28 both display 10:00, fo

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>
9220316	05/10/2019	14:00	05/13/2019	16:00
9220315	05/10/2019	14:00	05/13/2019	16:00
9220318	05/10/2019	14:00	05/13/2019	16:00
9220317	05/10/2019	14:00	05/13/2019	16:00
9220321	05/10/2019	14:00	05/13/2019	16:00
9220322	05/10/2019	14:00	05/13/2019	16:00
9220319	05/10/2019	14:00	05/13/2019	16:00
9220323	05/10/2019	14:00	05/13/2019	16:00
9220324	05/10/2019	14:00	05/13/2019	16:00
9220325	05/10/2019	14:00	05/13/2019	16:00
9220326	05/10/2019	14:00	05/13/2019	16:00
9220329	05/10/2019	14:00	05/13/2019	16:00
9220330	05/10/2019	14:00	05/13/2019	16:00
9220331	05/10/2019	14:00	05/13/2019	16:00
9220332	05/10/2019	14:00	05/13/2019	16:00
9220320	05/10/2019	14:00	05/13/2019	16:00
9220333	05/10/2019	14:00	05/13/2019	16:00
9220327	05/10/2019	14:00	05/13/2019	16:00
9220338	05/10/2019	14:00	05/13/2019	16:00
9220337	05/10/2019	14:00	05/13/2019	16:00
9220334	05/10/2019	14:00	05/13/2019	16:00
9220339	05/10/2019	14:00	05/13/2019	16:00
9220328	05/10/2019	14:00	05/13/2019	16:00
9220335	05/10/2019	14:00	05/13/2019	16:00
9220340	05/10/2019	14:00	05/13/2019	16:00
9220336	05/10/2019	14:00	05/13/2019	16:00
9220341	05/10/2019	14:00	05/13/2019	16:00
9220342	05/10/2019	14:00	05/13/2019	16:00
9220343	05/10/2019	14:00	05/13/2019	16:00
9220344	05/10/2019	14:00	05/13/2019	16:00
9220347	05/10/2019	14:00	05/13/2019	16:00
9220348	05/10/2019	14:00	05/13/2019	16:00
9220345	05/10/2019	14:00	05/13/2019	16:00
9220346	05/10/2019	14:00	05/13/2019	16:00
9220353	05/10/2019	14:00	05/13/2019	16:00
9220349	05/10/2019	14:00	05/13/2019	16:00

(+ / - 5 degrees) (your designations for facility, building and room)
 r example

(optional)

(enter proper code)
 0=Basement, 1=1st, 2=2nd, 3=oth

<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
68	South Park	Main School	Modular 1-A		1
68	South Park	Main School	Modular 1-B		1
68	South Park	Main School	Cafeteria		1
68	South Park	Main School	Cafeteria		1
68	South Park	Main School	Gym		1
68	South Park	Main School	Gym		1
68	South Park	Main School	Rm 124		1
68	South Park	Main School	Rm 120		1
68	South Park	Main School	Rm 119		1
68	South Park	Main School	Rm 125		1
68	South Park	Main School	Rm 131		1
68	South Park	Main School	Rm 131		1
68	South Park	Main School	Innunizao's rm		1
68	South Park	Main School	Library		1
68	South Park	Main School	Library		1
68	South Park	Main School	Rm 116		1
68	South Park	Main School	m - Alverauto		1
68	South Park	Main School	ander Putten		1
68	South Park	Main School	computer Rm		1
68	South Park	Main School	inciples Office		1
68	South Park	Main School	Rm 103		1
68	South Park	Main School	Rm 22		1
68	South Park	Main School	Rm 20		1
68	South Park	Main School	Rm 19		1
68	South Park	Main School	Rm 21		1
68	South Park	Main School	Rm 18		1
68	South Park	Main School	Rm 16		1
68	South Park	Main School	Rm 17		1
68	South Park	Main School	Rm 15		1
68	South Park	Main School	Rm 14		1
68	South Park	Main School	Rm 12		1
68	South Park	Main School	Rm 13		1
68	South Park	Main School	Rm 11		1
68	South Park	Main School	Rm 9		1
68	South Park	Main School	Rm 10		1
68	South Park	Main School	Rm 8		1

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9220315	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	MODULAR 1-B		1	< 0.3
9220316	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	MODULAR 1-A		1	< 0.3
9220317	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	CAFETERIA		1	2.5
9220318	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	CAFETERIA		1	3.0
9220319	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 124		1	0.5
9220320	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 116		1	3.6
9220321	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	GYM		1	3.6
9220322	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	GYM		1	3.8
9220323	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 120		1	1.1
9220324	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 119		1	1.4
9220325	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 125		1	1.1
9220326	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 131		1	1.2
9220327	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	VANDER PUTTEN		1	2.2
9220328	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 20		1	4.7
9220329	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 131		1	1.4
9220330	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	PANNUNIZAO'S RM		1	3.6
9220331	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	LIBRARY		1	1.9
9220332	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	LIBRARY		1	2.3
9220333	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM - ALVERAUTO		1	3.7
9220334	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 103		1	1.9
9220335	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 19		1	4.4
9220336	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 18		1	2.9
9220337	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	PRINCIPLES OFFICE		1	1.9
9220338	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	COMPUTER RM		1	2.5
9220339	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 22		1	3.9
9220340	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 21		1	5.7
9220341	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 16		1	4.1
9220342	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 17		1	4.3
9220343	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 15		1	4.7
9220344	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 14		1	3.8
9220345	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 11		1	5.1
9220346	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 9		1	4.3
9220347	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 12		1	4.1
9220348	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 13		1	4.2
9220349	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 8		1	2.2

P8487 / BRANDICE ESLINGER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9220353	2019-05-10	2:00 pm	2019-05-13	4:00 pm	68	SOUTH PARK	MAIN SCHOOL	RM 10		1	3.8

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Sunset Park Elementary

(from test kit)

Times should be in 24 hour format, 1pm = 13:00

(+ / - 5 degrees) (your designations for facility, building and room)

(optional)

(enter proper code)

* round times so that 9:31 and 10:28 both display 10:00, for example

0=Basement, 1=1st, 2=2nd, 3=other

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>	<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>
9210207	04/05/2019	9:00	04/08/2019	15:00	68	Sunset Elementary	Main School	R23		1st
9210202	04/05/2019	10:00	04/08/2019	15:00	68	Sunset Elementary	Main School	R25		1st
9210206	04/05/2019	10:00	04/08/2019	15:00	68	Sunset Elementary	Main School	R24		1st
9210209	04/05/2019	10:00	04/08/2019	15:00	68	Sunset Elementary	Main School	R26		1st
9210213	04/05/2019	10:00	04/08/2019	16:00	68	Sunset Elementary	Main School	R27		1st
9210214	04/05/2019	10:00	04/08/2019	16:00	68	Sunset Elementary	Main School	R29		1st
9210203	04/05/2019	10:00	04/08/2019	16:00	68	Sunset Elementary	Main School	R28		1st
9210210	04/05/2019	10:00	04/08/2019	16:00	68	Sunset Elementary	Main School	R30		1st
9210215	04/05/2019	10:00	04/08/2019	16:00	68	Sunset Elementary	Main School	R31		1st
9210204	04/05/2019	10:00	04/08/2019	16:00	68	Sunset Elementary	Main School	R31		1st
9210211	04/05/2019	10:00	04/08/2019	16:00	68	Sunset Elementary	Main School	R22		1st
9210218	04/05/2019	10:00	04/08/2019	16:00	68	Sunset Elementary	Main School	R20		1st
9210208	04/05/2019	11:00	04/08/2019	16:00	68	Sunset Elementary	Main School	R21		1st
9210216	04/05/2019	11:00	04/08/2019	16:00	68	Sunset Elementary	Main School	R19		1st
9210220	04/05/2019	11:00	04/08/2019	16:00	68	Sunset Elementary	Main School	R18		1st
9210217	04/05/2019	11:00	04/08/2019	16:00	68	Sunset Elementary	Main School	R16		1st
9210224	04/05/2019	11:00	04/08/2019	16:00	68	Sunset Elementary	Main School	R17		1st
9210223	04/05/2019	11:00	04/08/2019	16:00	68	Sunset Elementary	Main School	R15		1st
9210221	04/05/2019	11:00	04/08/2019	16:00	68	Sunset Elementary	Main School	R14		1st
9210212	04/05/2019	11:00	04/08/2019	16:00	68	Sunset Elementary	Main School	R14		1st
9210225	04/05/2019	11:00	04/08/2019	16:00	68	Sunset Elementary	Main School	R12		1st
9210222	04/05/2019	11:00	04/08/2019	16:00	68	Sunset Elementary	Main School	R13		1st
9210226	04/05/2019	11:00	04/08/2019	16:00	68	Sunset Elementary	Main School	R11		1st
9210229	04/05/2019	11:00	04/08/2019	16:00	68	Sunset Elementary	Main School	R10		1st
9210230	04/05/2019	11:00	04/08/2019	16:00	68	Sunset Elementary	Main School	R9		1st
9210231	04/05/2019	11:00	04/08/2019	16:00	68	Sunset Elementary	Main School	Art Room		1st
9210205	04/05/2019	11:00	04/08/2019	16:00	68	Sunset Elementary	Main School	Media Center		1st
9210232	04/05/2019	11:00	04/08/2019	16:00	68	Sunset Elementary	Main School	ESS Room		1st
9210234	04/05/2019	11:00	04/08/2019	16:00	68	Sunset Elementary	Main School	Gym		1st
921233	04/05/2019	11:00	04/08/2019	16:00	68	Sunset Elementary	Main School	Gym		1st
9210238	04/05/2019	11:00	04/08/2019	16:00	68	Sunset Elementary	Main School	Cafeteria		1st
9210219	04/05/2019	11:00	04/08/2019	16:00	68	Sunset Elementary	Main School	Cafeteria		1st
9210227	04/05/2019	11:00	04/08/2019	16:00	68	Sunset Elementary	Main School	Cafeteria		1st

April 11, 2019

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
921233		1990-05-29 @ 9:00 am	1990-05-31 @ 3:00 pm	0.6	1990-06-04

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Radon test result report for:
**SUNSET ELEMENTARY
 MAIN SCHOOL**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9210229	10	2019-04-05 @ 11:00 am	2019-04-08 @ 4:00 pm	1.4 ± 0.3	2019-04-10
9210226	11	2019-04-05 @ 11:00 am	2019-04-08 @ 4:00 pm	1.3 ± 0.3	2019-04-10
9210225	12	2019-04-05 @ 11:00 am	2019-04-08 @ 4:00 pm	1.0 ± 0.3	2019-04-10
9210222	13	2019-04-05 @ 11:00 am	2019-04-08 @ 4:00 pm	1.4 ± 0.3	2019-04-10
9210212	14	2019-04-05 @ 11:00 am	2019-04-08 @ 4:00 pm	1.2 ± 0.3	2019-04-10
9210221	14	2019-04-05 @ 11:00 am	2019-04-08 @ 4:00 pm	1.3 ± 0.3	2019-04-10
9210223	15	2019-04-05 @ 11:00 am	2019-04-08 @ 4:00 pm	1.5 ± 0.3	2019-04-10
9210217	16	2019-04-05 @ 11:00 am	2019-04-08 @ 4:00 pm	1.5 ± 0.3	2019-04-10
9210224	17	2019-04-05 @ 11:00 am	2019-04-08 @ 4:00 pm	1.0 ± 0.3	2019-04-10
9210220	18	2019-04-05 @ 11:00 am	2019-04-08 @ 4:00 pm	1.2 ± 0.3	2019-04-10
9210216	19	2019-04-05 @ 11:00 am	2019-04-08 @ 4:00 pm	0.8 ± 0.3	2019-04-10
9210218	20	2019-04-05 @ 10:00 am	2019-04-08 @ 4:00 pm	1.3 ± 0.3	2019-04-10
9210208	21	2019-04-05 @ 11:00 am	2019-04-08 @ 4:00 pm	1.2 ± 0.3	2019-04-10
9210211	22	2019-04-05 @ 10:00 am	2019-04-08 @ 4:00 pm	1.1 ± 0.3	2019-04-10
9210206	24	2019-04-05 @ 10:00 am	2019-04-08 @ 3:00 pm	2.2 ± 0.3	2019-04-10
9210202	25	2019-04-05 @ 10:00 am	2019-04-08 @ 3:00 pm	2.6 ± 0.3	2019-04-10
9210209	26	2019-04-05 @ 10:00 am	2019-04-08 @ 3:00 pm	2.4 ± 0.3	2019-04-10
9210213	27	2019-04-05 @ 10:00 am	2019-04-08 @ 4:00 pm	2.0 ± 0.3	2019-04-10
9210203	28	2019-04-05 @ 10:00 am	2019-04-08 @ 4:00 pm	2.4 ± 0.3	2019-04-10
9210214	29	2019-04-05 @ 10:00 am	2019-04-08 @ 4:00 pm	2.8 ± 0.3	2019-04-10
9210210	30	2019-04-05 @ 10:00 am	2019-04-08 @ 4:00 pm	2.0 ± 0.3	2019-04-10
9210204	31	2019-04-05 @ 10:00 am	2019-04-08 @ 4:00 pm	1.9 ± 0.3	2019-04-10
9210215	31	2019-04-05 @ 10:00 am	2019-04-08 @ 4:00 pm	1.7 ± 0.3	2019-04-10
9210230	9	2019-04-05 @ 11:00 am	2019-04-08 @ 4:00 pm	1.4 ± 0.3	2019-04-10
9210231	ART ROOM	2019-04-05 @ 11:00 am	2019-04-08 @ 4:00 pm	0.8 ± 0.3	2019-04-10
9210219	CAFITERIA	2019-04-05 @ 11:00 am	2019-04-08 @ 4:00 pm	1.5 ± 0.3	2019-04-10
9210238	CAFITERIA	2019-04-05 @ 11:00 am	2019-04-08 @ 4:00 pm	1.2 ± 0.3	2019-04-10
9210227	CAFITERIA	2019-04-05 @ 11:00 am	2019-04-08 @ 4:00 pm	1.0 ± 0.3	2019-04-10
9210232	ESS ROOM	2019-04-05 @ 11:00 am	2019-04-08 @ 4:00 pm	1.0 ± 0.3	2019-04-10
9210205	MEDIA CENTER	2019-04-05 @ 11:00 am	2019-04-08 @ 4:00 pm	1.0 ± 0.3	2019-04-10
9210207	R23	2019-04-05 @ 9:00 am	2019-04-08 @ 3:00 pm	2.2 ± 0.3	2019-04-10